TOWN OF YORKTOWN PLANNING BOARD

Albert. A. Capellini Community and Cultural Center, 1974 Commerce Street, Yorktown Heights, New York 10598, Phone: (914) 962-6565, Fax: (914) 962-3986

PUBLIC MEETING AGENDA YORKTOWN TOWN HALL BOARD ROOM

363 Underhill Avenue, Yorktown Heights, NY 10598

February 28, 2022 7:00 PM

1. Correspondence

2. Meeting Minutes - February 14, 2022

WORK SESSION

3. Old Hill Farm Solar Farm

Discussion Site Plan & Special Use Permit

Location: 16.08-1-4 & 17; 571 East Main Street, Jefferson Valley *Contact:* Hillside Solar LLC *Description:* Proposed 3.75 MW ground mounted solar panels disturbing 15 acres on a 19.4 acre property in the R1-20 zone.

4. Kitchawan Solar

Discussion Site Plan & Special Permit

Location: 70.06-1-2 & 3; 716 Kitchawan Road Contact: Ecogy Kitchawan Community Solar Farm, LLC Description: Proposed 2 MW ground mounted large-scale solar energy system.

5. Ryder Subdivision

Discussion Minor Subdivision

Location: 48.06-1-12; 532 Underhill Avenue *Contact:* Site Design Consultants *Description:* Proposed to subdivide a parcel with an existing residence into 2 building lots on 6.086 acres in the R1-20 zone. The Board previously reviewed this application from 2013 – 2015.

6. Martino Contracting

Discussion Site Plan

Location: 6.17-2-62; 286 East Main Street, Jefferson Valley Contact: Site Design Consultants Description: Proposed subdivision for a two-story office/warehouse/garage and apartment building in the Country Commercial zone and one single-family house in the R1-80 zone.

7. Grishaj Major Subdivision Discussion Subdivision

Location: 16.17-2-77; 3319 Stony Street *Contact:* Site Design Consultants *Description:* Proposed 10 lot subdivision on 8 acres in the R1-20 zone. Plan proposes to connect to High Point Drive and South Shelley Street.

8. Home & Hearth Discussion Site Plan

Location: 15.12-1-2; 1750 East Main Street Contact: Site Design Consultants Description: Proposed demolition of two existing buildings to construct a new 5,500 SF showroom/warehouse and 4,500 SF storage building on 1.99 acres in the C-4 zone.

9. Town Board Referral

Gas Station Special Use Permit Location: 15.15-1-46; 1770 East Main Street Contact: Neil Carnow, AIA project architect Description: Proposed modifications to existing convenience store building.

10. Town Board Referral *Withdrawn from this Agenda* Gas Station Special Use Permit

Location: 36.06-1-25; 3451 Crompond Road *Contact:* Vincent Franceschelli *Description:* Proposed remodel of existing station and convenience store.

Last revised: February 25, 2022

Correspondence

Draft Minutes

Old Hill Farm

CIVIL ENGINEER

PROJECT CONTACTS

BERGMANN 2 WINNERS CIRCLE, SUITE 102 **ALBANY, NY 12205** CONTACT: ERIC REDDING, PE PHONE: 518.556.3631

APPLICANT HILLSIDE SOLAR LLC 227 GUARD HILL ROAD **BEDFORD CORNERS, NY 10549** CONTACT: KATHRYN HOENIG PHONE: 914.953.5312

ELECTRICAL ENGINEER TBD

OWNER

OLD HILL FARM LLC 227 GUARD HILL ROAD **BEDFORD CORNERS, NY 10549**

PRELIMINARY DEVELOPMENT PLANS FOR PROPOSED

OLD HILL FARM SOLAR FARM SOLAR DEVELOPMENT 571 EAST MAIN STREET JEFFERSON VALLEY, NEW YORK







SITE LOCATION MAP

DRAWING INDEX

/ING NO.	DRAWING TITLE	SHEET NO.
:000	COVER	1
:001	GENERAL NOTES	2
:002	AREA PARCEL PLAN	3
:003	EXISTING CONDITIONS PLAN	4
:004	OVERALL SITE PLAN	5
:005	SITE PLAN	6
:006	GRADING & EROSION & SEDIMENT CONTROL PLAN	7
:007	GRADING PLAN DETAILS	8
:008	LANDSCAPING & TREE MITIGATION PLAN	9
:009	PHASING PLAN	10
:010	DETAILS I	11
:011	DETAILS II	12
:012	DETAILS III	13



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD **BEDFORD CORNERS, NY 10549**

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	WD
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

COVER



SEC	QUENCE OF CONSTRUCTION:	ST	ORM WATER POLLUTION PREVENTION PLAN NOTES:
1.	PRE-CONSTRUCTION MEETING HELD TO INCLUDE PROJECT MANAGER, OPERATOR'S ENGINEER, CONTRACTOR, AND SUB-CONTRACTORS PRIOR TO LAND DISTURBING ACTIVITIES.	1.	THE CONTRACTOR SHALL PROVIDE A QUALIFIED INSPECT WORK WEEK AND PROVIDE A REPORT AT LEAST ONCE P
2.	CONSTRUCT CONSTRUCTION ENTRANCE/EXIT AT LOCATIONS DESIGNATED ON PLANS.	2.	EROSION CONTROL MEASURES WILL BE IMPLEMENTED IN GUIDELINES FOR URBAN EROSION SEDIMENT CONTROL
3. 4.	HAVE A QUALIFIED PROFESSIONAL CONDUCT AN ASSESSMENT OF THE SITE PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.	3.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAI
5.	BEGIN CLEARING AND GRUBBING OPERATIONS. CLEARING AND GRUBBING SHALL BE DONE ONLY IN AREAS WHERE EARTHWORK WILL BE PERFORMED AND ONLY IN AREAS WHERE CONSTRUCTION IS PLANNED TO COMMENCE WITHIN 14 DAYS AFTER CLEARING AND GRUBBING.	4.	UNTIL GROUND COVER IS ESTABLISHED. REMOVE AND STOCKPILE TOPSOIL AS DIRECTED BY THE MINIMUM 4" DEPTH. ALL DISTURBED AREAS TO BE HYDRO
6.	CONSTRUCT GRAVEL ROAD TO BE USED DURING CONSTRUCTION	5.	MANAGER TO PROMOTE VEGETATION AS SOON AS PRAC
7.	STRIP TOPSOIL AND STOCKPILE IN A LOCATION ACCEPTABLE TO CONSTRUCTION MANAGER. WHEN STOCKPILE IS COMPLETE, INSTALL PERIMETER SILT FENCE, SEED SURFACE WITH 100% PERENNIAL RYEGRASS MIXTURE AT A RATE OF 2-4 LBS. PER 1000 SF. APPLY 90-100 LBS PER 1000 SF OF MULCH.	6.	OR EQUIVALENT AND ANCHORED IN ACCORDANCE WITH CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTEN CONTROLS. EROSION CONTROL MEASURES SHALL NOT
8.	COMMENCE EARTHWORK CUT AND FILLS. THE WORK SHALL BE PROGRESSED TO ALLOW A REASONABLE TRANSFER OF CUT AND FILL EARTH FOR ROUGH GRADING AND EARTH MOVING. THE CONTRACTOR WILL BE GIVEN SOME LATITUDE TO VARY FROM THE FOLLOWING SCHEDULE IN ORDER TO MEET THE FIELD CONDITIONS ENCOUNTERED. CONTRACTOR SHALL REVIEW VARIATIONS TO SWPPP WITH DESIGN ENGINEER AND QUALIFIED PROFESSIONAL PRIOR TO IMPLEMENTATION.	7.	BEEN ACHIEVED. ALL EROSION CONTROL MEASURES ARE TO BE REPLACE AND SHALL BE REPLACED WHEN THEY HAVE REACHED T
10.	CONSTRUCT SOLAR ARRAY AREA IN THREE PHASES AS DETAILED IN SHEET C009 OF THIS PLAN SET. CONTRACTOR SHALL CONSTRUCT EACH PHASE INDIVIDUALLY AND SHALL NOT PROCEED TO THE FOLLOWING PHASE UNTIL THE SOLAR RACKING HAS BEEN INSTALLED AND THE PHASE AREA HAS BEEN TEMPORARILY STABILIZED WITH SEED AND MULCH.	8.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTOR CONTRACTOR'S RESPONSIBILITY TO MAINTAIN EROSION
11.	REMOVE GRAVEL DRIVEWAY USED DURING CONSTRUCTION AND CONSTRUCT THE PROPOSED PERVIOUS GRAVEL DRIVEWAY AFTER CONSTRUCTION ACTIVITIES SUCH AS THE INSTALLATION OF THE PANELS AND PERIMETER FENCE. THE SUB-GRADE	9.	THE CONTRACTOR SHALL DESIGNATE A MEMBER OF HIS/ CONTROL AND EROSION CONTROL STRUCTURES THROU
	MATERIAL WHERE THE DRIVEWAY IS TO BE INSTALLED SHALL BE DECOMPACTED PER NYSDEC'S "DEEP-RIPPING AND DECOMPACTION" MANUAL, DATED APRIL 2008. CONTRACTOR SHALL AVOID FREQUENT HEAVY TRAFFIC ON THE LIMITED USE PERVIOUS GRAVEL.	10.	ALL DISTURBED AREAS SHALL BE FINISH GRADED TO PRO AS PRACTICABLE. STABILIZATION PRACTICES (TEMPORA ETC.) MUST BE IMPLEMENTED WITHIN SEVEN (7) DAYS W
12.	AS ROADWAY AND ACCESS DRIVES ARE BROUGHT TO GRADE, THEY WILL BE STABILIZED WITH CRUSHED STONE SUBBASE AT A DEPTH SPECIFIED ON PLANS TO PREVENT EROSION AS SOON AS PRACTICABLE.		OR PERMANENTLY CEASED, AND NOT EXPECTED TO RES
13.	STABILIZE ALL AREAS AS SOON AS PRACTICABLE, IDLE IN EXCESS OF 7 DAYS AND IN WHICH CONSTRUCTION WILL NOT RECOMMENCE WITHIN 14 DAYS.	11.	DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-C
14.	INSTALL UTILITIES. TRENCH EXCAVATION/BACKFILL AREAS SHOULD BE STABILIZED PROGRESSIVELY AT THE END OF EACH WORKDAY WITH SEED AND STRAW MULCH AT A RATE OF 100% PERENNIAL RYE GRASS AT 2-4 LBS/1000 SF MULCHED AT 90-100 LBS/1000 SF.	12. 13.	DUST SHALL BE CONTROLLED BY WATERING. ADJOINING PROPERTIES SHALL BE PROTECTED FROM EX PROPOSED SITE.
15.	STABILIZE ALL AREAS IDLE IN EXCESS OF 7 DAYS IN WHICH CONSTRUCTION WILL NOT RECOMMENCE WITHIN 14 DAYS.	14.	EROSION CONTROL MEASURES SHOULD BE RELOCATED PROGRESSES AND RECONSTRUCTED TO THE NYS STAN
16.	REMOVE TEMPORARY CONSTRUCTION EXITS AND PERIMETER SILT FENCE ONCE SITE HAS ACHIEVED 80% UNIFORM STABILIZATION.	15.	PERIMETER AREAS SHALL BE TEMPORARILY STABILIZED AT THE END OF EACH WEEK WITH 100% PERENNIAL RYE
<u>GEN</u>	<u>VERAL NOTES:</u>	16.	SLOPE TRACKING SHALL BE IMPLEMENTED ON ALL SLOPE
1.	RECORD MAPS, THEY ARE NOT CERTIFIED TO THE ACCURACY OF THEIR LOCATION AND/OR COMPLETENESS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION AND EXTENT OF ALL UNDERGROUND STRUCTURES AND UTILITIES PRIOR TO ANY DIGGING OR CONSTRUCTION ACTIVITIES IN THEIR VICINITY. THE CONTRACTOR SHALL HAVE ALL EXISTING UTILITIES FIELD STAKED BEFORE STARTING WORK BY CALLING 1-800-962-7962.		AND PRIOR TO FINAL SLOPE GRADING AND STABILIZATIC
2.	THE CONTRACTOR SHALL PERFORM ALL WORK IN COMPLIANCE WITH TITLE 29 OF FEDERAL REGULATIONS, PART 1926, SAFETY AND	SIT	E STABILIZATION:
3.	HIGHWAY DRAINAGE ALONG ALL ROADS AND PRIVATE DRIVES SHALL BE KEPT CLEAN OF MUD, DEBRIS ETC. AT ALL TIMES.	1.	WHEN FINAL GRADE IS ACHIEVED DURING NON-GERMINAT THE NEXT PLANTING SEASON.
4.	THE CONTRACTOR SHALL CONSULT THE DESIGN ENGINEER BEFORE DEVIATING FROM THESE PLANS.	2.	MULCHES SHOULD BE APPLIED AT THE RATES SHOWN IN ⁻ SHOULD BE VISIBLE THROUGH THE MULCH.
5. 6.	IN ALL TRENCH EXCAVATIONS, CONTRACTOR MUST LAY THE TRENCH SIDE SLOPES BACK TO A SAFE SLOPE, USE A TRENCH SHIELD OR PROVIDE SHEETING AND BRACING. IE SUSPICIOUS AND/OR HAZARDOUS MATERIAL IS ENCOUNTERED DURING DEMOLITION/CONSTRUCTION, ALL WORK SHALL STOP	3.	STRAW AND HAY MULCH SHOULD BE ANCHORED OR TACK WINDBLOWN. A TRACTOR-DRAWN IMPLEMENTS MAY BE US THIS METHOD SHOULD BE LIMITED TO SLOPES NO STEEPE
	AND THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH AND THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION SHALL BE NOTIFIED IMMEDIATELY. WORK SHALL NOT RESUME UNTIL THE DEVELOPER HAS OUTLINED APPROPRIATE ACTION FOR DEALING WITH THE WASTE MATERIAL AND THE DEVELOPMENT PLANS ARE MODIFIED AS MAY BE NECESSARY	4.	CONTOUR. NOTE: CRIMPING OF HAY OR STRAW BY RUNNI BEFORE SEEDING IS APPLIED THE CONTRACTOR SHALL SI SUSTAIN THE SEED GERMINATION AND ESTABLISHMENT C
7.	EXCAVATED WASTE MATERIAL REMOVED FROM THE SITE SHALL BE PLACED AT A LOCATION ACCEPTABLE TO THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION.	5.	GRADED AREAS SHOULD BE SCARIFIED OR OTHERWISE LO TOPSOIL TO THE SURFACE AREAS AND TO PROVIDE A ROU COMPACTED SOILS SHOULD BE SCARIFIED TO A DEPTH O
8.	AREAS DISTURBED OR DAMAGED AS PART OF THIS PROJECTS CONSTRUCTION THAT ARE OUTSIDE OF THE PRIMARY WORK AREA SHALL BE RESTORED, AT THE CONTRACTORS EXPENSE, TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE.	6	SEEDING.
9.	UNLESS COVERED BY THE CONTRACT SPECIFICATIONS OR AS NOTED ON THE PLANS, ALL WORK SHALL CONFORM TO THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS DATED JANUARY 1, 2020 AND ANY SUBSEQUENT APPENDICES.	0.	INCHES. SPREADING SHOULD BE DONE IN SUCH A MANNE ADDITIONAL PREPARATION OR TILLAGE. IRREGULARITIES CORRECTED IN ORDER TO PREVENT FORMATION OF DEPF
\ // Δ		7.	TOPSOIL SHOULD NOT BE PLACED WHILE THE TOPSOIL OF EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHER PREPARATION.
1.	WHENEVER POSSIBLE COVERED TRASH CONTAINERS SHOULD BE USED.	8.	WHEN USED AS A MULCH REPLACEMENT, THE APPLICATIO
2.	DAILY SITE CLEANUP IS REQUIRED TO REDUCE DEBRIS AND POLLUTANTS IN THE ENVIRONMENT.	9.	POLYMERIC AND GUM TACKIFIERS MIXED AND APPLIED AC
3. 4.	CONTRACTOR SHALL PROVIDE A SAFE STORAGE SPACE FOR ALL PAINTS, STAINS AND SOLVENTS INSIDE A COVERED STORAGE AREA. ALL FUELS, OILS, AND GREASE MUST BE KEPT IN CONTAINERS AT ALL TIMES.		TACK MULCH. AVOID APPLICATION DURING RAIN AND ON W HIGHER THAN 45° F ARE TYPICALLY REQUIRED. APPLICATI AT CRESTS OF RIDGES AND BANKS TO PREVENT LOSS BY UNIFORMLY. BINDERS MAY BE APPLIED AFTER MULCH IS S
EDC		10.	SYNTHETIC BINDERS, OR CHEMICAL BINDERS, MAY BE USI
<u> </u>	INSTALL EROSION CONTROL MEASURES AS INDICATED ON THE PLAN PRIOR TO THE START OF ANY EXCAVATION WORK. EROSION	11.	MULCH ON SLOPES OF 8% OR STEEPER SHOULD BE HELD
	CONTROL MEASURES WILL BE IMPLEMENTED IN ACCORDANCE WITH THE NEW YORK STATE GUIDELINES FOR URBAN EROSION SEDIMENT CONTROL MANUAL, NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION, AND THE GOVERNING MUNICIPAL REQUIREMENTS.	12.	MAY BE STAPLED OVER THE MULCH ACCORDING TO MANU SHREDDED PAPER HYDROMULCH SHOULD NOT BE USED (
2.	REMOVE AND STOCKPILE TOPSOIL AS DIRECTED BY THE CONSTRUCTION MANAGER REPLACE TOPSOIL TO A MINIMUM 4" DEPTH WITH TOPSOIL OR AMENDED SOIL. ALL DISTURBED AREAS TO BE SEEDED TO PROMOTE VEGETATION AS SOON AS PRACTICABLE.	10	LIME FERTILIZER SEED AND MULCH DISTURDED A DEAD
3.	IF THE SEASONS PROHIBITS TEMPORARY SEEDING, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW HAY OR EQUIVALENT AND ANCHORED IN ACCORDANCE WITH THE "STANDARDS", NETTING OR LIQUID MULCH BINDER.	13.	SLOPES OR OBVIOUS AREAS WHERE POTENTIAL EROSION MEDIUM (FGM) SHALL BE USED. FGM SHALL BE APPLIED PI
4.	CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REMOVAL OF TEMPORARY SEDIMENTATION CONTROLS. EROSION CONTROL MEASURES SHALL NOT BE REMOVED BEFORE 80% UNIFORM VEGETATIVE COVER HAS BEEN ACHIEVED.	14.	ONCE A SECTION OF THE ALIGNMENT HAS BEEN STABILIZI UNTIL THE SECTION HAS ACHIEVED 80% PERENNIAL VEGE FINAL STABILIZATION WHEN IT HAS A MINIMUM 80% PEREN
5.	ALL EROSION CONTROL MEASURES ARE TO BE REPLACED WHENEVER THEY BECOME CLOGGED OR INOPERABLE AND SHALL BE REPLACED AT A MINIMUM OF EVERY 3 MONTHS.		COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELER RESIST SLIDING OR OTHER MOVEMENTS.
6.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF TOPSOIL OR AMENDED TO ALL DISTURBED AREAS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN EROSION CONTROL MEASURES AT ALL TIMES.		
7.	THE CONTRACTOR SHALL DESIGNATE A MEMBER OF HIS/HER FIRM TO BE RESPONSIBLE TO MONITOR EROSION CONTROL, EROSION CONTROL, EROSION CONTROL STRUCTURES, TREE PROTECTION AND PRESERVATION THROUGHOUT CONSTRUCTION.		
8.	ALL DISTURBED AREAS SHALL BE FINISH GRADED TO PROMOTE VEGETATION ON ALL EXPOSED AREAS AS SOON AS PRACTICABLE. STABILIZATION PRACTICES (TEMPORARY/PERMANENT SEEDING, MULCHING, GEOTEXTILES, ETC.) MUST BE IMPLEMENTED WITHIN SEVEN (7) DAYS WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, AND NOT EXPECTED TO RESUME WITHIN FOURTEEN (14) DAYS.		
9.	PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES. ALL CONSTRUCTION DEBRIS AND SEDIMENT SPOILS, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAYS MUST BE REMOVED IMMEDIATELY.		
10.	DUST SHALL BE CONTROLLED BY WATERING.		
11.	ADJOINING PROPERTY SHALL BE PROTECTED FROM EXCAVATION AND FILLING OPERATIONS ON THE PROPOSED SITE.		
12.	SLUFE TRAUNING SHALL DE IMPLEMENTED ON ALL SLUPE I ON 3 OK GREATER AT THE END OF EACH WORK DAY AND PRIOR TO		

FINAL SLOPE GRADING AND STABILIZATION.

RACTOR SHALL PROVIDE A QUALIFIED INSPECTOR TO INSPECT THE PROJECT AT THE END OF EACH EK AND PROVIDE A REPORT AT LEAST ONCE PER WEEK.

CONTROL MEASURES WILL BE IMPLEMENTED IN ACCORDANCE WITH THE NEW YORK STATE ES FOR URBAN EROSION SEDIMENT CONTROL MANUAL, WESTCHESTER COUNTY DEPARTMENT OF ND THE TOWN OF YORKTOWN REQUIREMENTS.

RACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE BEST MANAGEMENT PRACTICES (BMP'S) OUND COVER IS ESTABLISHED.

ND STOCKPILE TOPSOIL AS DIRECTED BY THE CONSTRUCTION MANAGER. REPLACE TOPSOIL TO A " DEPTH. ALL DISTURBED AREAS TO BE HYDROSEEDED AS DIRECTED BY THE CONSTRUCTION TO PROMOTE VEGETATION AS SOON AS PRACTICABLE.

SONS PROHIBITS TEMPORARY SEEDING, THE DISTURBED AREAS WILL BE MULCHED WITH STRAW HAY ALENT AND ANCHORED IN ACCORDANCE WITH THE "STANDARDS", NETTING OR LIQUID MULCH BINDER.

OR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REMOVAL OF TEMPORARY SEDIMENTATION S. EROSION CONTROL MEASURES SHALL NOT BE REMOVED BEFORE 80% UNIFORM VEGETATION HAS IEVED.

ON CONTROL MEASURES ARE TO BE REPLACED WHENEVER THEY BECOME CLOGGED OR INOPERABLE L BE REPLACED WHEN THEY HAVE REACHED THE DESIGN LIFE INDICATED IN THE NYS GUIDELINES IN EROSION SEDIMENT CONTROL DESIGN MANUAL OR EVERY THREE MONTHS.

RACTOR SHALL BE RESPONSIBLE FOR RESTORATION OF TOPSOIL TO ALL DISTURBED AREAS. IT IS THE TOR'S RESPONSIBILITY TO MAINTAIN EROSION CONTROL MEASURES AT ALL TIMES.

RACTOR SHALL DESIGNATE A MEMBER OF HIS/HER FIRM TO BE RESPONSIBLE TO MONITOR EROSION AND EROSION CONTROL STRUCTURES THROUGHOUT CONSTRUCTION.

RBED AREAS SHALL BE FINISH GRADED TO PROMOTE VEGETATION ON ALL EXPOSED AREAS AS SOON ICABLE. STABILIZATION PRACTICES (TEMPORARY/PERMANENT SEEDING, MULCHING, GEOTEXTILES, T BE IMPLEMENTED WITHIN SEVEN (7) DAYS WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY ANENTLY CEASED, AND NOT EXPECTED TO RESUME WITHIN FOURTEEN (14) DAYS.

ADWAYS MUST BE KEPT CLEAN AT ALL TIMES. ALL CONSTRUCTION DEBRIS AND SEDIMENT SPOILS, , WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAYS MUST BE REMOVED IMMEDIATELY.

PROPERTIES SHALL BE PROTECTED FROM EXCAVATION AND FILLING OPERATIONS ON THE

CONTROL MEASURES SHOULD BE RELOCATED INWARD AS PERIMETER SLOPE CONSTRUCTION SES AND RECONSTRUCTED TO THE NYS STANDARDS & SPECIFICATION AT THE END OF EACH DAY.

R AREAS SHALL BE TEMPORARILY STABILIZED WITH SEED AND MULCH PROGRESSIVELY AT MINIMUM ID OF EACH WEEK WITH 100% PERENNIAL RYEGRASS MIX AT A RATE OF 2-4 LBS PER 1000 SF AND

CKING SHALL BE IMPLEMENTED ON ALL SLOPE 1 ON 3 OR GREATER AT THE END OF EACH WORK DAY R TO FINAL SLOPE GRADING AND STABILIZATION.

ION:

L GRADE IS ACHIEVED DURING NON-GERMINATING MONTHS, THE AREA SHOULD BE MULCHED UNTIL THE BEGINNING OF LANTING SEASON.

HOULD BE APPLIED AT THE RATES SHOWN IN THE MULCH APPLICATION RATES TABLE. VERY LITTLE BARE GROUND VISIBLE THROUGH THE MULCH.

) HAY MULCH SHOULD BE ANCHORED OR TACKIFIED IMMEDIATELY AFTER APPLICATION TO PREVENT BEING N. A TRACTOR-DRAWN IMPLEMENTS MAY BE USED TO "CRIMP" THE STRAW OR HAY INTO THE SOIL - ABOUT 3 INCHES. DD SHOULD BE LIMITED TO SLOPES NO STEEPER THAN 3H:1V. THE MACHINERY SHOULD BE OPERATED ALONG THE NOTE: CRIMPING OF HAY OR STRAW BY RUNNING OVER IT WITH TRACKED MACHINERY IS NOT RECOMMENDED.

EDING IS APPLIED THE CONTRACTOR SHALL SPREAD SOIL TO PREVENT PONDING AND CONFIRM THAT SOIL WILL IE SEED GERMINATION AND ESTABLISHMENT OF VEGETATION.

REAS SHOULD BE SCARIFIED OR OTHERWISE LOOSENED TO A DEPTH OF 3 TO 5 INCHES TO PERMIT BONDING OF THE) THE SURFACE AREAS AND TO PROVIDE A ROUGHENED SURFACE TO PREVENT TOPSOIL FROM SLIDING DOWN SLOPE. D SOILS SHOULD BE SCARIFIED TO A DEPTH OF 6 TO 12 INCHES, ALONG CONTOUR WHEREVER POSSIBLE, PRIOR TO

R AMENDED SOIL SHOULD BE UNIFORMLY DISTRIBUTED ACROSS THE DISTURBED AREA TO A MINIMUM DEPTH OF 6 READING SHOULD BE DONE IN SUCH A MANNER THAT SODDING OR SEEDING CAN PROCEED WITH A MINIMUM OF PREPARATION OR TILLAGE. IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOIL PLACEMENT SHOULD BE D IN ORDER TO PREVENT FORMATION OF DEPRESSIONS.

HOULD NOT BE PLACED WHILE THE TOPSOIL OR SUBSOIL IS IN A FROZEN OR MUDDY CONDITION, WHEN THE SUBSOIL IS LY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND SEEDBED ON

) AS A MULCH REPLACEMENT, THE APPLICATION RATE (THICKNESS) OF THE COMPOST SHOULD BE $\frac{1}{2}$ " TO $\frac{3}{4}$ ". COMPOST PLACED EVENLY AND SHOULD PROVIDE 100% SOIL COVERAGE. NO SOIL SHOULD BE VISIBLE.

AND GUM TACKIFIERS MIXED AND APPLIED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS MAY BE USED TO H. AVOID APPLICATION DURING RAIN AND ON WINDY DAYS. A 24-HOUR CURING PERIOD AND A SOIL TEMPERATURE AN 45° F ARE TYPICALLY REQUIRED. APPLICATION SHOULD GENERALLY BE HEAVIEST AT EDGES OF SEEDED AREAS AND OF RIDGES AND BANKS TO PREVENT LOSS BY WIND. THE REMAINDER OF THE AREA SHOULD HAVE BINDER APPLIED . BINDERS MAY BE APPLIED AFTER MULCH IS SPREAD OR SPRAYED INTO THE MULCH AS IT IS BEING BLOWN ONTO THE (ING STRAW AND BINDER TOGETHER IS GENERALLY MORE EFFECTIVE.

BINDERS, OR CHEMICAL BINDERS, MAY BE USED AS RECOMMENDED BY THE MANUFACTURER TO ANCHOR MULCH SUFFICIENT DOCUMENTATION IS PROVIDED TO SHOW THEY ARE NON-TOXIC TO NATIVE PLANT AND ANIMAL SPECIES.

SLOPES OF 8% OR STEEPER SHOULD BE HELD IN PLACE WITH NETTING. LIGHTWEIGHT PLASTIC, FIBER, OR PAPER NETS APLED OVER THE MULCH ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.

PAPER HYDROMULCH SHOULD NOT BE USED ON SLOPES STEEPER THAN 5%. WOOD FIBER HYDROMULCH MAY BE STEEPER SLOPES PROVIDED A TACKIFIER IS USED. THE APPLICATION RATE FOR ANY HYDROMULCH SHOULD BE 2,000 A MINIMUM.

LIZER, SEED, AND MULCH DISTURBED AREAS PER THE EROSION AND SEDIMENT CONTROL PLANS. IN AREAS OF STEEP OBVIOUS AREAS WHERE POTENTIAL EROSION MAY OCCUR, AN EROSION CONTROL MAT OR FLEXIBLE GROWTH GM) SHALL BE USED. FGM SHALL BE APPLIED PER MANUFACTURER SPECIFICATIONS.

CTION OF THE ALIGNMENT HAS BEEN STABILIZED. NO CONSTRUCTION TRAFFIC SHALL OCCUR TO REMOVE ANY BMPS SECTION HAS ACHIEVED 80% PERENNIAL VEGETATIVE COVER. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED ILIZATION WHEN IT HAS A MINIMUM 80% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NONVEGETATIVE H A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO DING OR OTHER MOVEMENTS.



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD **BEDFORD CORNERS, NY 10549**

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

GENERAL NOTES





NUMBER	TAX ID	PARCEL OWNER	NUMBER	TAX ID	PAF
1	16.08-1-51	DANIELLE DISALVO	6	16.08-1-56	MICHAEI
2	16.08-1-50	TERRENCE & MURPHY	7	16.08-1-55	THC
3	16.08-1-49	LINDA EINFRANK	8	16.08-1-54	ALFREDO
4	16.08-1-48	LOUISE MILLER	9	16.08-1-53	MCHI
5	16.08-1-57	WILLIAM & OFRIAS	10	16.08-1-52	MICH

2022 1:33 PN

OMAS & FURIA

HELE & MILAZZO





2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY NOT FOR CONSTRUCTION

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

AREA PARCEL PLAN







SCHEDULE B EXCEPTIONS:

- 5. COVENANTS, RESTRICTIONS, EASEMENTS AND AGREEMENTS FOUND OF RECORD:
- A. TERMS, CONDITIONS, EASEMENTS AND RESERVATIONS CONTAINED IN DEED MADE BY JAMES CURRY HILL, ET AL. TO WESTCHESTER LIGHTING COMPANY, DATED 9/19/1931 AND RECORDED 11/12/1931 IN LIBER 3193 CP. 313, AS MODIFIED BY: TRANSMISSION LINE AS SHOWN.
- (I) RELEASE MADE BETWEEN SMALL SHOPPING CENTERS VENTURE AND CONSOLIDATED COMPANY OF NEW YORK, INC., RECORDED 10/2/1972 IN LIBER 7084 CP. 402 (RELEASES EASEMENTS GRANTED IN LIBER 3193 CP.313); AND
- (II) RELEASE OF EASEMENT MADE BETWEEN CONSOLIDATED COMPANY OF NEW YORK, INC. AND SMALL SHOPPING CENTERS VENTURE, RECORDED 11/24/1972 IN LIBER 7094 CP. 647 (RELEASES EASEMENTS GRANTED IN LIBER 3193 CP.313). (SEE EXHIBIT A)
- B. UTILITY EASEMENT GRANT TO WESTCHESTER LIGHTING COMPANY AND NEW YORK TELEPHONE COMPANY, RECORDED 6/14/1940 IN LIBER 3837 CP. 48. (EXHIBIT B). DOES NOT AFFECT SUBJECT PROPERTY.
- C. GRANT OF PIPELINE EASEMENT TO ALGONQUIN GAS TRANSMISSION COMPANY, RECORDED 7/21/1952 IN LIBER 5118 CP. 386. (EXHIBIT C). DOES NOT AFFECT SUBJECT PROPERTY.
- D. UTILITY EASEMENT GRANT TO CONSOLIDATED COMPANY OF NEW YORK, INC., RECORDED 10/9/1967 IN LIBER 6737 CP. 754. (EXHIBIT D) BLANKET IN NATURE
- E. NEW YORK TELEPHONE COMPANY EASEMENT AGREEMENT, RECORDED 10/10/1967 IN LIBER 6738 CP. 134. (EXHIBIT E) DOES NOT AFFECT SUBJECT PROPERTY.

GENERAL NOTES:

- 1. UNDERGROUND UTILITIES SHOWN HEREON BASED ON UTILITY EVIDENCE VISIBLE AT GROUND SURFACE AND RECORD DRAWINGS AND ARE SUBJECT TO FIELD VERIFICATION BY EXCAVATION. UTILITIES SHOWN DO NOT PURPORT TO CONSTITUTE OR REPRESENT ALL UTILITIES LOCATED UPON OR ADJACENT TO THE SURVEYED PREMISES.
- 2. THE OFFSETS OR DIMENSIONS SHOWN HEREON, FROM THE PROPERTY LINES TO THE STRUCTURES, ARE FOR A SPECIFIC PURPOSE AND USE; THEREFORE, THEY ARE NOT INTENDED TO MONUMENT THE PROPERTY LINES OR TO GUIDE THE ERECTION OF FENCES, ADDITIONAL STRUCTURES OR ANY OTHER IMPROVEMENTS.
- 3. EASEMENTS AND/OR SUBSURFACE STRUCTURES RECORDED OR UNRECORDED ARE NOT GUARANTEED UNLESS PHYSICALLY EVIDENT ON THE PREMISES AT THE TIME OF THE SURVEY.
- 4. SUBJECT TO ALL RIGHTS, EASEMENTS, COVENANTS AND RESTRICTIONS OF RECORD.
- 5. REFERENCE IS MADE TO STEWART TITLE INSURANCE COMPANY, TITLE NUMBER 837326 (S-NY-CP-BTA), EFFECTIVE DATE AUGUST 11, 2017.
- 6. BASIS OF BEARING IS NEW YORK STATE PLANE COORDINATE SYSTEM EAST ZONE. CONTROL WAS ESTABLISHED USING NYSNET VRS SYSTEM. THE HORIZONTAL DATUM IS RELATIVE TO NAD83
- THE VERTICAL POSITION OF THE HEREIN SURVEY IS BASED ON THE NYSNET RTK GPS NETWORK AND IS SUBJECT TO FURTHER ADJUSTMENT TO ANY LOCAL NGS BENCHMARKS. THE VERTICAL DATUM IS RELATIVE TO NAVD 1988

MAP REFERENCES:

- MAP ENTITLED "THE NEW YORK EDISON CO. JAMES CURRY HILL & THEODORE HILL JR. - PURCHASE, 132 KV RIGHT OF WAY BETWEEN PUTNAM-WESTCHESTER CO. LINE & MILLWOOD" DATED SEPT 3, 1931, N-664.
- 2. MAP ENTITLED "SUBDIVISION MAP OF JEFFERSON VALLEY INDUSTRIAL PARK NO 1 FOR JEFFERSON VALLEY CORP.", BY J. HENRY CARPENTER & CO., DATED FEB. 3, 1964, AND FILED IN THE WESTCHESTER COUNTY CLERK'S OFFICE QN MAY 25, 1964 AS MAP NO. 13954.
- MAP ENTITLED "AMENDED SUBDIVISION MAP OF JEFFERSON VALLEY INDUSTRIAL PARK NO 1 FOR JEFFERSON VALLEY CORP.", BY J. HENRY CARPENTER & CO., DATED OCTOBER 2 1964, AND FILED IN THE WESTCHESTER COUNTY CLERK'S OFFICE ON FEB 1, 1965 AS MAP NO. 14225.
- MAP ENTITLED "SUBDIVISION MAP SHOWING RE-SUBDIVISION OF JEFFERSON VALLEY INDUSTRIAL PARK NO. 1" BY J. HENRY CARPENTER & CO., LAST REVISED MAY 24, 1990, AND FILED IN THE WESTCHESTER COUNTY CLERK'S OFFICE ON JUNE 11, 1990 AS MAP NO. 24181.

CERTIFICATIONS INDICATED HEREON SIGNIFY THAT THIS SURVEY WAS PREPARED IN ACCORDANCE WITH THE EXISTING CODE OF PRACTICE FOR LAND SURVEYORS ADOPTED BY THE N.Y. STATE ASSOCIATION OF PROFESSIONAL LAND SURVEYORS. SAID CERTIFICATIONS SHALL RUN ONLY TO THE PERSON FOR WHOM THE SURVEY IS PREPARED, AND ON BEHALF OF THE TITLE COMPANY, GOVERNMENTAL AGENCY AND LENDING INSTITUTION LISTED HEREON, AND TO THE ASSIGNEES OF THE LENDING INSTITUTION OR SUBSEQUENT OWNERS.

		PROPERTY LINE
		ADJOINER PROPERTY LINE
		ROAD RIGHT-OF-WAY
~~~~~~~~~~~~~~~~~		STONE WALL
		ROAD CENTERLINE
——————————————————————————————————————	DHE	OVERHEAD WIRE
→	→	STREAM CENTERLINE
		CONTOUR - MAJOR
		CONTOUR - MINOR
SWL	SWL	SWALE CENTERLINE
		EDGE OF ASPHALT
$\gamma\gamma\gamma\gamma$	$\gamma\gamma\gamma\gamma$	EXISTING TREELINE
	• • • • • ₩ET • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • •	PALUSTRINE FORESTED WETLAND (PI
	-⊙-	UTILITY POLE
		IRON MONUMENT
	•	FOUND CONCRETE MONUMENT
	<del></del>	EXISTING SIGN
	•	GUY WIRE



2 Winners Circle, Suite 102 Albany, NY 12205

www.bergmannpc.com office: 518.862.0325

### HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

### OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

### PRELIMINARY NOT FOR CONSTRUCTION

### Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

### EXISTING CONDITIONS PLAN

Drawing Number

**COO3** 

4 of 13



	SITE PLAN DATA TABLE			
SITE IS LOCATED IN THE "R1-	-20" ONE-FAMILY RESIDENTIAL			
PROPOSED USE: SOLAR ENE	RGY SYSTEM			
PARCEL 16.08-1-17 TOWN OF YORKTOWN, COU STATE OF NEW YORK	NTY OF WESTCHESTER			
APPLICANT: POWERFLEX 805 THIRD AVENUE NEW YORK, NY, 120022 (917) 426-9523	OWNER(S) OF ROMER BEAT	FRECORD: O		
PLANS PREPARED BY: BERGMANN 2 WINNERS CIRCLE, SUITE 102 ALBANY, NY 12205 (518) 862-0325				
DESCRIPTION	REQUIRED	PROPOSED		
MIN. LOT SIZE	N/A 844,987± SF			
MINIMUM LOT WIDTH	N/A	900± FT		
MIN. SIDE YARD SETBACK	50 FT	50± FT		
MIN. FRONT YARD SETBACK	50 FT	51± FT		
MIN. REAR YARD SETBACK	50 FT	50± FT		

#### <u>NOTES</u>

REQUIRED ZONING STANDARDS REFLECT THE MOST STRICT RESIDENTIAL ZONING REQUIREMENTS OF THE TOWN OF YORKTOWN PER SECTION 300 ATTACHMENT 1 APPENDIX A RESIDENCE ZONE STANDARDS.

#### LEGEND

~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	

	OHE -				OHE -		
	\rightarrow -				\rightarrow -		
	— x -				× —		
	- DHE -				DHE -		
	· UGE -				uge -		
	· SWL -				SWL -		
\frown	γ	γ	γ	Υ	γ	γ	
	- SWL ·				-SWL -		

_____ ___

\frown	Y	\checkmark	\checkmark	\checkmark	\searrow	\checkmark	_
202	Z	ZÇ	<u>sõ</u>	Ì	<i>õ</i> g	ÌÇ.	

-0-

PROPERTY LINE
SET BACK LINE
WETLAND SET BACK
STONE WALL
ADJOINER PROPERTY LINE
ROAD RIGHT-OF-WAY
EXISTING ROAD CENTERLINE
EXISTING OVERHEAD WIRE
EXISTING STREAM CENTERLINE
PROPOSED FENCE LINE
PROPOSED OVERHEAD UTILITY LINE
PROPOSED UNDERGROUND UTILITY LINE
PROPSED SWALE
PROPOSED TREELINE
SWALE CENTERLINE
EXISTING BUILDING
EXISTING EDGE OF ASPHALT
EXISTING TREELINE
PROPOSED DRIVEWAY
PALUSTRINE FORESTED WETLAND (PFO)
PROPOSED SOLAR PANEL
EXISTING UTILITY POLE



1" = 80' SCALE BAI

BERGMANN ARCHITECTS ENGINEERS PLANNERS

2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

OVERALL SITE PLAN





	SITE PLAN DATA TABLE	
SITE IS LOCATED IN THE "R1-	20" ONE-FAMILY RESIDENTIA	
PROPOSED USE: SOLAR ENE	RGY SYSTEM	
PARCEL 16.08-1-17 TOWN OF YORKTOWN, COUN STATE OF NEW YORK	NTY OF WESTCHESTER	
APPLICANT: POWERFLEX 805 THIRD AVENUE NEW YORK, NY, 120022 (917) 426-9523	OWNER(S) O ROMER BEA	F RECORD: TO
PLANS PREPARED BY: BERGMANN 2 WINNERS CIRCLE, SUITE 102 ALBANY, NY 12205 (518) 862-0325		
DESCRIPTION	REQUIRED	PROPOSED
MIN. LOT SIZE	N/A	844,987± SF
MINIMUM LOT WIDTH	N/A	900± FT
MIN. SIDE YARD SETBACK	50 FT	50± FT
MIN. FRONT YARD SETBACK	50 FT	51± FT
MIN. REAR YARD SETBACK	50 FT	50± FT

<u>NOTES</u>

1. REQUIRED ZONING STANDARDS REFLECT THE MOST STRICT RESIDENTIAL ZONING REQUIREMENTS OF THE TOWN OF YORKTOWN PER SECTION 300 ATTACHMENT 1 APPENDIX A RESIDENCE ZONE STANDARDS.

LEGEND

	PRC
	SET
	WE ⁻
·	STC
	ADJ
	ROA
	EXI
DHE DHE	EXIS
$-\!$	EXIS
x x	PRC
OHE OHE	PRC
UGE UGE	PRC
SVL	PRC
\longrightarrow	PRC
SWL SWL	SW
	EXIS
	EXIS
	EXIS
603030304	PRC
	PAL

_	PROPERTY LINE
_	SET BACK LINE
	WETLAND SET BACK
ö.	STONE WALL
	ADJOINER PROPERTY LINE
	ROAD RIGHT-OF-WAY
	EXISTING ROAD CENTERLINE
	EXISTING OVERHEAD WIRE
	EXISTING STREAM CENTERLINE
_	PROPOSED FENCE LINE
_	PROPOSED OVERHEAD UTILITY LINE
_	PROPOSED UNDERGROUND UTILITY LINE
_	PROPSED SWALE
)	PROPOSED TREELINE
	SWALE CENTERLINE
	EXISTING BUILDING
	EXISTING EDGE OF ASPHALT
)	EXISTING TREELINE
	PROPOSED DRIVEWAY
4	PALUSTRINE FORESTED WETLAND (PFO)
Ħ	PROPOSED SOLAR PANEL

-O- EXISTING UTILITY POLE

• 6" BOLLARD



BOLLARD LOCATION DETAIL SCALE: 1"=40'



" = 80' SCALE BA



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

SITE PLAN





LEGEND

$\begin{array}{c c} & \text{DHE} & \text{DHE} & \text{DHE} & \\ & \rightarrow & \rightarrow & \\ & & & & \\ & & & & \\ & & & &$
→ → → → → → → → → → → → → → → → → → →
→
XX DHEDHE UGEUGE
X X DHE DHE UGE UGE L000 L000 SILT
\$ILT
\$ILT
808080808
808080808

PROPERTY LINE SET BACK LINE WETLAND SET BACK STONE WALL ADJOINER PROPERTY LINE ROAD RIGHT-OF-WAY EXISTING ROAD CENTERLINE EXISTING OVERHEAD WIRE EXISTING STREAM CENTERLINE PROPOSED FENCE LINE PROPOSED OVERHEAD UTILITY LINE PROPOSED UNDERGROUND UTILITY LINE LIMITS OF DISTURBANCE PROPOSED TREELINE SILT FENCE PROFILE ALIGNMENT EXISTING EDGE OF ASPHALT EXISTING TREELINE PROPOSED DRIVEWAY

PALUSTRINE FORESTED WETLAND (PFO)

PROPOSED SOLAR PANEL

-O- EXISTING UTILITY POLE



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11



Drawing Number



7 of 13



1" = 60' SCALE BA





NO SCALE

GEOGRID MATERIAL NOTES:

MAINTENANCE.

- 1. THE GEOGRID, OR COMPARABLE PRODUCT, IS INTENDED FOR USE IN ALL CONDITIONS, IN ORDER TO ASSIST IN MATERIAL SEPARATION FROM NATIVE
- SOILS AND PRESERVE ACCESS LOADS. 2. GRAVEL FILL MATERIAL SHALL CONSIST OF 1-4" CLEAN, DURABLE, SHARP
- ANGLED CRUSHED STONE OF UNIFORM QUALITY, MEETING THE SPECIFICATION OF NYSDOT 703-02, SIZE DESIGNATION 3-5 OF TABLE 703-4. STONE MAY BE PLACED IN FRONT OF AND SPREAD WITH A TRACKED VEHICLE. GRAVEL SHALL
- NOT BE COMPACTED. 3. GEOGRID SHALL BE ENHANCED WOVEN GEOTEXTILE (HP270 OR EQUIVALENT).
- GEOGRID SHALL BE DESIGNED BASED ON EXISTING SOIL CONDITIONS AND PROPOSED HAUL ROAD SLOPES.
- 4. IF MORE THAN ONE ROLL WIDTH IS REQUIRED, ROLLS SHOULD OVERLAP A MINIMUM OF SIX INCHES.
- 5. REFER TO MANUFACTURER'S SPECIFICATION FOR PROPER TYING AND
- CONNECTIONS. 6. LIMITED USE PERVIOUS ACCESS ROAD SHALL BE DRESSED AS REQUIRED WITH ONLY 1-4" CRUSHED STONE MEETING NYSDOT 703-02 SPECIFICATIONS.

BASIS OF DESIGN: TENCATE MIRAFI BXG110 GEOGRIDS; 365 SOUTH HOLLAND DRIVE, PENDERGRASS, GA; 800-685-9990 OR 706-693-2226; WWW.MIRAFI.COM





GEOGRID MATERIAL

GRAVEL MATERIAL



ENHANCED WOVEN GEOTEXTILE (HP270 OR EQUIVALENT)

- ENHANCED WOVEN GEOTEXTILE MATERIAL NOTES: 1. SPECIFIED GEOTEXTILE WILL ONLY BE UTILIZED IN PLACID SOILS. PLACID SOILS
- CONSIST OF POORLY DRAINED SOILS COMPOSED OF FINELY TEXTURED PARTICLES AND ARE PRONE TO RUTTING. PLACID SOILS ARE TYPICALLY PRESENT IN LOW-LYING AREAS WITH HYDROLOGIC SOILS GROUP (HSG) OF C OR D OR AS SPECIFIED FROM AN ENVIRONMENTAL SCIENTIST, SOIL SCIENTIST
- OR GEOTECHNICAL DATA. 2. THE CONCERN OF POTENTIAL REDUCTION OF NATIVE INFILTRATION RATES DIE TO THE GEOTEXTILE MATERIAL WOULD NOT BE A SIGNIFICANT CONCERN IN POORLY DRAINED SOILS WHERE SEGREGATION OF PERVIOUS STONE AND NATIVE MATERIALS IS CRUCIAL FOR LONG TERM OPERATION AND

BASIS OF DESIGN: ENHANCED WOVEN GEOTEXTILE (HP270 OR EQUIVALENT)

GENERAL NOTES:

- 1. USE OF THIS DETAIL/CRITERION IS LIMITED TO ACCESS ROADS USED ON AN OCCASIONAL BASIS ONLY (I.E. PROVIDE ACCESS FOR MOWING, EQUIPMENT REPAIR OR MAINTENANCE)
- 2. LIMITED USE PERVIOUS ACCESS ROAD IS LIMITED TO LOW IMPACT IRREGULAR MAINTENANCE ACCESS ASSOCIATED WITH RENEWABLE ENERGY PROJECTS IN NEW YORK STATE.
- 3. REMOVE STUMPS. ROCKS AND DEBRIS AS NECESSARY, FILL VOIDS TO MATCH EXISTING NATIVE SOILS AND COMPACTION LEVEL.
- 4. REMOVED TOPSOIL MAY BE SPREAD IN ADJACENT AREAS AS DIRECTED BY THE PROJECT
- ENGINEER, COMPACT TO THE DEGREE OF THE NATIVE IN SITU SOIL. DO NOT PLACE IN AN AREA THAT IMPEDES STORM WATER DRAINAGE. 5. GRADE ROADWAY, WHERE NECESSARY, TO NATIVE SOILS AND DESIRED ELEVATION. MINOR
- GRADING FOR CROSS SLOPE CUT AND FILL MAY BE REQUIRED. 6. REMOVE REFUSE SOILS AS DIRECTED BY THE PROJECT ENGINEER. DO NOT PLACE IN AN AREA
- THAT IMPEDES STORM WATER DRAINAGE. 7. ROADWAY WIDTH TO BE DETERMINED BY CLIENT.
- 8. THE LIMITED USE PERVIOUS ACCESS ROAD CROSS SLOPE SHALL BE 1.5% IN MOST CASES AND SHOULD NOT EXCEED 6%. THE LONGITUDINAL SLOPE OF THE ACCESS DRIVE SHOULD NOT EXCEED 15%.
- 9. LIMITED USE PERVIOUS ACCESS ROAD IS NOT INTENDED TO BE UTILIZED FOR CONSTRUCTION WHICH MAY SUBJECT THE ACCESS TO SEDIMENT TRACKING. THIS SPECIFICATION IS TO BE DEVELOPED FOR POST-CONSTRUCTION USE. SOIL RESTORATION PRACTICES MAY BE APPLICABLE TO RESTORE CONSTRUCTION RELATED COMPACTION TO PRE-EXISTING CONDITIONS AND SHOULD BE VERIFIED BY SOIL PENETROMETER READINGS. THE PENETROMETER READINGS SHALL BE COMPARED TO THE RESPECTIVE RECORDED READINGS TAKEN PRIOR TO CONSTRUCTION, EVERY 100 LINEAR FEET ALONG THE PROPOSED ROADWAY.
- 10. TO ENSURE THAT SOIL IS NOT TRACKED ONTO THE LIMITED USE PERVIOUS ACCESS ROAD, IT SHALL NOT BE USED BY CONSTRUCTION VEHICLES TRANSPORTING SOIL, FILL MATERIAL, ETC. IF THE LIMITED USE PERVIOUS ACCESS IS COMPLETED DURING THE INITIAL PHASES OF CONSTRUCTION AND UTILIZED TO REMOVE SEDIMENT FROM CONSTRUCTION VEHICLES AND EQUIPMENT PRIOR TO ENTERING THE LIMITED USE PERVIOUS ACCESS ROAD FROM ANY LOCATION ON, OR OFF SITE. MAINTENANCE OF THE PERVIOUS ACCESS ROAD WILL BE
- REQUIRED IF SEDIMENT IS OBSERVED WITHIN THE CLEAN STONE. 11. THE LIMITED USE PERVIOUS ACCESS ROAD SHALL NOT BE CONSTRUCTED OR USED UNTIL ALL AREAS SUBJECT TO RUNOFF ONTO THE PERVIOUS ACCESS HAVE ACHIEVED FINAL STABILIZATION.
- 12. PROJECTS SHOULD AVOID INSTALLATION OF THE LIMITED USE PERVIOUS ACCESS ROAD IN POORLY DRAINED ARES, HOWEVER IF NO ALTERNATIVE LOCATION IS AVAILABLE, THE PROJECT SHALL UTILIZE WOVEN GEOTEXTILE MATERIAL AS DETAILED IN FOLLOWING NOTES.
- 13. THE DRAINAGE DITCH IS OFFERED IN THE DETAIL FOR CIRCUMSTANCES WHEN CONCENTRATED FLOW COULD NOT BE AVOIDED . THE INTENTION OF THE DESIGN IS TO MINIMIZE ALTERATIONS TO HYDROLOGY, HOWEVER WHEN DEALING WITH 5%-15% GRADES NOT PARALLEL TO THE CONTOUR, A ROADSIDE DITCH MAY BE REQUIRED. THE NYS STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROLS FOR GRASSED WATERWAYS AND VEGETATED WATERWAYS ARE APPLICABLE FOR SIZING AND STABILIZATION, DIMENSIONS FOR THE GRASSED WATERWAY SPECIFICATION WOULD BE DESIGNED FOR PROJECT SPECIFIC HYDROLOGIC RUNOFF CALCULATIONS, AND A SEPARATE DETAIL FOR THE SPECIFIC GRASSED WATERWAY WOULD BE INCLUDED IN THIS PRACTICE. RUNOFF DISCHARGE WILL BE SUBJECT TO THE OUTLET REQUIREMENTS OF THE REFERENCED STANDARD. INCREASED
- ADDITIONAL PRACTICES TO ATTENUATE RUNOFF TO PRE-DEVELOPMENT CONDITIONS. 14. IF A ROADSIDE DITCH IS NOT UTILIZED TO CAPTURE RUNOFF FROM THE ACCESS ROAD, THE PERVIOUS ACCESS ROAD WILL HAVE A WELL-ESTABLISHED PERENNIAL VEGETATIVE COVER, WHICH SHALL CONSIST OF UNIFORM VEGETATION (I.E. BUFFER), 20 FEET WIDE AND PARALLEL TO THE DOWN GRADIENT SIDE OF THE ACCESS ROAD. POST-CONSTRICTION OPERATION AND MAINTENANCE PRACTICES WILL MAINTAIN THIS VEGETATIVE COVER TO ENSURE FINAL
- STABILIZATION FOR THE LIFE OF THE ACCESS ROAD. 15. THE DESIGN PROFESSIONAL MUST ACCOUNT FOR THE LIMITED USED PERVIOUS ACCESS ROAD IN THEIR SITE ASSESSMENT / HYDROLOGY ANALYSIS. IF THE HYDROLOGY ANALYSIS SHOWS THAT THE HYDROLOGY HAS BEEN ALTERED FROM PRE- TO POST-DEVELOPMENT CONDITIONS (SEE APPENDIX A OF GP-0-20-001 FOR THE DEFINITION OF "ALTER THE HYDROLOGY ... "), THE DESIGN MUST INCLUDE THE NECESSARY DETENTION/RETENTION PRACTICES TO ATTENUATE THE RATES (10 AND 100 YEAR EVENTS) TO PRE-DEVELOPMENT CONDITIONS.

POST-DEVELOPMENT RUNOFF FROM THE ASSOCIATED ROADSIDE DITCH MAY REQUIRE



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD **BEDFORD CORNERS, NY 10549**

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

GRADING PLAN DETAILS





			PLANT	LIST				
				Matu	re Size			
Key	Qty.	Botanical Name	Common Name	Height	Spread	Installed Size	Condition	DBH
	-		Eve	rgreen Trees				
JV	75	Juniperus Virginiana	Eastern Red Cedar	30'-60'	10'-25'	8' Ht.	B&B	3"
PG	67	Picea Glauca	White Spruce	40'-60'	10'-20'	8' Ht.	B&B	3"
PG-1	5	Picea Glauca	White Spruce	40'-60'	10'-20'	12' Ht.	B&B	5"
AC	60	Abies Concolor	White Fir	50'-75'	20'-30'	6'-7' Ht.	B&B	3"
PP	64	Pinus Strobus	Eastern White Pine	50'-80'	20'-40'	7'-8' Ht.	B&B	3"
TOTAL	265							



____X____X____X____X



____ · · · ____ · · · ____ · · · ____



SEED SCHEDULE 'B' PROPOSED GRAVEL DRIVEWAY

PROPOSED TREE PLANTING

SEED LIMIT LINE

PROTECTED WOODLAND AREA TO BE DISTURBED EXISTING ROAD

ADJ. PROPERTY/R.O.W. LINE (SURVEYED) FENCE LINE

EXISTING VEGETATION

PROPOSED LIMITS OF TREE CLEARING

PALUSTRINE FORESTED WETLAND (PFO)

© STREAM

100 FT WELAND SETBACK

EXISTING TREES TO REMAIN EXISTING TREES TO BE REMOVED

	TI	REE MITIGATION D	ATA TABLE	
TREES TO BE REMOVED	TREES TO REMAIN	NUMBER OF TREES WITH DIAMETER AT BREAST HEIGHT ≤ 7"	NUMBER OF TREES WITH DIAMETER AT BREAST HEIGHT 7" - 24"	NUMBER OF TREES WITH DIAMETER AT BREAST HEIGHT > 24"
578	121	8	602	90



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY NOT FOR CONSTRUCTION

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager ECR	Discipline Lead ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

LANDSCAPING & TREE MITIGATION PLAN

80 160 240 FT 1" = 80' SCALE BAR







LEGEND

			_
	xxxxxxx	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	∞.
———— DHE —		OHE	
→ -		→	
		^	
SVL –		SVL	
\frown	ŶŶ	$\gamma\gamma\gamma$	\frown
		SWL	

Tave () () () () () () () () () (
;;///;///;;

PROPERTY LINE
SET BACK LINE
WETLAND SET BACK
STONE WALL
ADJOINER PROPERTY LINE
ROAD RIGHT-OF-WAY
EXISTING ROAD CENTERLINE
EXISTING OVERHEAD WIRE
EXISTING STREAM CENTERLINE
PROPOSED FENCE LINE
PROPOSED OVERHEAD UTILITY LINE
PROPOSED UNDERGROUND UTILITY LINE
PROPSED SWALE
PROPOSED TREELINE
SWALE CENTERLINE
EXISTING BUILDING
EXISTING EDGE OF ASPHALT
EXISTING TREELINE
PROPOSED DRIVEWAY
PALUSTRINE FORESTED WETLAND (PFO)
PHASE 1
PHASE 2

PHASE 3

PROPOSED SOLAR PANEL -O- EXISTING UTILITY POLE



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	ECR
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

PHASING PLAN

Drawing Number







1" = 80' SCALE BAI









N.T.S.

VYVVVVVVV VVVVVVV 24" MIN. _ 12' WIDTH VARIES NOTES: REPAIR ALL SETTLEMENT
 MINIMUM TOP SOIL DEPTH 6"
 MULTIPLE CONDUITS SHALL BE SPACED 7" ON CENTER

SOIL RESTORATION DETAIL

5. APPLY SOIL STABILIZATION AS NECESSARY.

3. WATER AREA TO BE SEEDED PRIOR TO LAYING SEED.

4. WATER THOROUGHLY UPON COMPLETION OF SEEDING.

SEEDING PROCEDURE:

1. CULTIVATE ENTIRE AREA TO 4"-6" DEPTH. HANDRAKE SMOOTH. SPREAD 4" OF TOPSOIL.

2. APPLY ANY SOIL MODIFICATIONS AS NECESSARY (SEE SPECIFICATIONS OR LANDSCAPE NOTES)

- LAWN SEED, VARIETY AS SPECIFIED

OR LANDSCAPE NOTES

- MATCH EXISTING GRADE AND ALLOW FOR

6" WIDE YELLOW PLASTIC TAPE WITH WORDING "CAUTION BURIED ELECTRIC LINE BELOW." TAPE SHALL BE LOCATED 12" ABOVE CONDUITS

COMPACT BACKFILL TO 95% MAX
 DENSITY; TO MATCH SURROUNDING
 CONDITIONS - NO ROCKS OR DEBRIS IN

PROVIDE 3" COMPACTED SAND BED AROUND CONDUIT

- DIRECT BURIED CONDUIT

SETTLING. FERTILIZE AND SEED

____ EXISTING GRADE

— 6" MIN. TOPSOIL

BACKFILL

UNDISTURBED SOIL

- 4 - 6" CULTIVATED SOIL (TYP.)

- 4" APPROVED TOPSOIL, SEE SPECIFICATIONS



. •



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead	
ECR	ECR	
Designer	Reviewer	
AG	WD	
Date Issued	Project Number	
07/28/2021	14064.11	

Sheet Name

DETAILS II

C011



UPLAND SEED MIX

LOW-GROWING WILDFLOWER & GRASS MIX - ERNMX #156 SEEDING RATE: 20 LB PER ACRE WITH A COVER CROP OF GRAIN RYE AT 30 LB PER ACRE

SCIENTIFIC NAME	COMMON NAME	% OF MIX
FESTUCA OVINA	SHEEP FESCUE, VARIETY NOT STATED	63.60%
LOLIUM MULTIFLORUM (L. PERENNE VAR. ITALICUM)	ANNUAL RYEGRASS	17%
LINUM PERENNE SSP. LEWISII	PERENNIAL BLUE FLAX	8%
RUDBECKIA HIRTA	BLACKEYED SUSAN, COASTAL PLAIN NC ECOTYPE	2%
COREOPSIS LANCEOLATA	LANCELEAF COREOPSIS, COASTAL PLAIN NC ECOTYPE	2%
CHRYSANTHEMUM LEUCANTHEMUM	OXEYE DAISY	2%
CHRYSANTHEMUM MAXIMUM	SHASTA DAISY	1%
CHAMAECRISTA FASCICULATA (CASSIA F.)	PARTRIDGE PEA, PA ECOTYPE	1%
PAPAVER RHOEAS, SHIRLEY MIX	CORN POPPY/SHIRLEY MIX	1%
ACHILLEA MILLEFOLIUM	COMMON YARROW	0.5%
ASTER OBLONGIFOLIUS (SYMPHYOTRICHUM OBLONGIFOLIUM)	AROMATIC ASTER, PA ECOTYPE	0.5%
EUPATORIUM COELESTINUM (CONOCLINIUM C.)	MISTFLOWER, VA ECOTYPE	0.5%
MONARDA PUNCTATA, COASTAL PLAIN SC ECOTYPE	SPOTTED BEEBALM, COASTAL PLAIN SC ECOTYPE	0.5%
ASCLEPIAS TUBEROSA	BUTTERFLY MILKWEED	0.3%
PYCNANTHEMUM TENUIFOLIUM	SLENDER MOUNTAINMINT	0.1%
COMP	ANY INFORMATION	
ERNST CON	ISERVATION SEEDS, INC.	
ADDRESS: 8884 ME	RCER PIKE, MEADVILLE, PA 16335	
PHC	NE: (800) 873-3321	

WEB: HTTP://WWW.ERNSTSEED.COM

*OR APPROVED EQUIVALENT

SEED SCHEDULE 'A'

	OBL-FACW WETLAND MIX	
	ERNMX #120	
SEEDING	RATE: 20 LB PER ACRE OR 1/2 LB PER 1000 SQ FT	
SCIENTIFIC NAME	COMMON NAME	% OF MIX
ELYMUS VIRGINICUS	VIRGINIA WILDRYE	20%
POA PALUSTRIS	FOWL BLUEGRASS	20%
CAREX LURIDA	LURID SHALLOW SEDGE	17%
CAREX LUPULINA	HOP SEDGE	9%
CAREX SCOPARIA	BLUNT BROOM SEDGE	8%
CAREX VULPINOIDEA	FOX SEDGE	5%
PANICUM CLANDESTINUM DICHANTHELIUM C.	DEERTONGUE 'TIOGA'	5%
SPARGANIUM EURYCARPUM	GIANT BUR REED	4%
SPARGANIUM AMERICANUM	EASTERN BUR REED	3%
JUNCUS EFFUSUS	SOFT RUSH	3%
CAREX CRINITA	FRINGED NODDING SEDGE	2%
LEERSIA ORYZOIDES	RICE CUTGRASS	2%
SCIRPUS CYPERINUS	WOOLGRASS	2%
JUNCUS TENUIS	PATH RUSH	0.5%
	COMPANY INFORMATION	
	ERNST CONSERVATION SEEDS INC.	
ADDR	ESS: 8884 MERCER PIKE MEADVILLE PA 16335	
	PHONE: 800 873-3321	

WEB: HTTP://WWWW.ERINSTSEED.COW

* CURRENT ERNST SEED MIX COMPOSITION OR APPROVED EQUIVALENT

* PROVIDE TEMPORARY SEEDING OF ANNUAL RYEGRASS (LOLIUM MULTIFLORUM) WITHIN SEEDING LIMITS AT RATE OF 20 LBS. PER ACRE

SITE STABILIZATION - SEED MIX N.T.S.

	SOIL A	MENDMENT A	PPLICATION RA	TE EQUIVALE	NTS
SOI	IL AMENDMENT	PER ACRE	PER 1,000 SQ. FT.	PER 1,000 SQ. YD.	NOTES
ANENT DING	AGRICULTURAL LIME	6 TONS	240 LB.	2,480 LB.	OR AS PER SOIL TEST: MAY NOT BE
PERM/ SEEI	10-10-20 FERTILIZER	1,000 L.B.	25 LB.	210 LB.	REQUIRED IN AGRICULTURAL FIELDS
DRARY DING	AGRICULTURAL LIME	1 TON	40 LB.	410 LB.	
TEMPO	10-10-20 FERTILIZER	500 LB.	12.5 LB.	100 LB.	TOPSOIL STOCKPILES

COMPOST STANDARDS	
ORGANIC MATTER CONTENT	80% - 100% (DRY WEIGHT BASIS)
ORGANIC PORTION	FIBROUS AND ELONGATED
рН	5.5 - 8.0
MOISTURE CONTENT	35% - 55%
PARTICLE SIZE	98% PASS THROUGH 1" SCREEN
SOLUBLE SALT CONCENTRATION	5.0 dS/m (mmhos/cm) MAXIMUM

	MULCH /	APPLICATION R	ATES	
	APPLICATION RATE (MIN.)			
MULCH TYPE	PER ACRE	PER 1,000 SQ. FT.	PER 1,000 SQ. YD.	NOTES
STRAW	3 TONS	140 LB.	1,240 LB.	EITHER WHEAT OR OAT STRAW, FREE OF WEEDS, NOT CHOPPED OR FINELY BROKEN
HAY	3 TONS	140 LB.	1,240 LB.	TIMOTHY, MIXED CLOVER AND TIMOTHY, OR OTHER NATIVE FORAGE GRASSES
WOOD CELLULOSE	1,500 LB.	35 LB.	310 LB.	DO NOT USE ALONE IN WINTER, DURING HOT AND DRY WEATHER OR ON STEEP SLOPES (> 3:1)
WOOD	1,000 LB. CELLULOSE	25 LB.	210 LB.	WHEN USED OVER STRAW OR HAY
WOOD CHIPS	4 - 6 TONS	185 - 275 LB.	1,650 - 2,500 LB.	MAY PREVENT GERMINATION OF GRASSES AND LEGUMES

NOTES:

- SHOULD BE TEMPORARILY STABILIZED UNTIL THE BEGINNING OF THE NEXT PLANTING SEASON.
- 2. MULCHES SHOULD BE APPLIED AT THE RATES SHOWN IN THE MULCH APPLICATION RATES TABLE. VERY LITTLE BARE GROUND SHOULD BE VISIBLE THROUGH THE MULCH.
- AFTER APPLICATION TO PREVENT BEING WINDBLOWN. 4. TOPSOIL SHOULD BE UNIFORMLY DISTRIBUTED ACROSS THE DISTURBED AREA TO MANNER THAT SEEDING CAN PROCEED WITH A MINIMUM OF ADDITIONAL
- PREPARATION OR TILLAGE. 5. TOPSOIL SHOULD NOT BE PLACED WHILE THE TOPSOIL OF SUBSOIL IS IN A SEEDBED PREPARATION.
- 6. WHEN USED AS A MULCH REPLACEMENT, THE APPLICATION RATE (THICKNESS) EVENLY AND SHOULD PROVIDE 100% SOIL COVERAGE. NO SOIL SHOULD BE VISIBLE.
- ON THE PLANS.
- 8. PERMANENT STABILIZATION SHALL BE INSTALLED IMMEDIATELY UPON COMPLETION OF EARTH DISTURBANCE.

1. WHEN FINAL GRADE IS ACHIEVED DURING NON-GERMINATING MONTHS, THE AREA

3. STRAW AND HAY MULCH SHOULD BE ANCHORED OR TACKIFIED IMMEDIATELY

A DEPTH OF 4 INCHES MINIMUM. SPREADING SHOULD BE DONE IN SUCH A

FROZEN OR MUDDY CONDITION, WHEN THE SUBSOIL IS EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND

OF THE COMPOST SHOULD BE 1/2" TO 3/4". COMPOST SHOULD BE PLACED

7. BLANKETING SHALL BE USED ON ALL SLOPES 3H:1V OR STEEPER OR AS NOTED



2 Winners Circle, Suite 102 Albany, NY 12205 www.bergmannpc.com office: 518.862.0325

HILLSIDE SOLAR LLC

227 GUARD HILL ROAD BEDFORD CORNERS, NY 10549

OLD HILL FARM SOLAR FARM

571 EAST MAIN STREET JEFFERSON VALLEY, NY 10535

Date Revised	Description
10/13/2021	REVISED PER CLIENT COMMENTS
12/01/2021	REVISED PER TREE COMMISSION COMMENTS
12/28/2021	REVISED PER FIRE DEPARTMENT COMMENTS
1/07/2022	REVISED PER SITE VISIT WITH FIRE DEPARTMENT
1/13/2022	REVISED PER ENGINEERING DEPARTMENT COMMENTS
1/20/2022	REVISED PER TCAC COMMENTS

PRELIMINARY **NOT FOR CONSTRUCTION**

Copyright © Bergmann Associates, Architects, Engineers, Landscape Architects & Surveyors, D.P.C

Project Manager	Discipline Lead
ECR	ECR
Designer	Reviewer
AG	WD
Date Issued	Project Number
07/28/2021	14064.11

Sheet Name

DETAILS III

Kitchawan Solar

FEB 2 2 2022

TOWN OF YORKTOWN

To: Yorktown Planning Board From: Yorktown Tree Conservation Advisory Commission (TCAC) Date: 18 February 2022 cc: Yorktown Planning Dept. (J. Tegeder, R. Steinberg, N. Calicchia); Engineering Dept. (L. Kobiliak); Conservation Board (K. Hughes); Town Supervisor (M. Slater); Town Clerk (D. Quast); TCAC members (L. Klein, T. Schmitt, K. Schepart)

Re: Proposed solar facility at 716 Kitchawan Road

Dear Chairman Fon and members of the Planning Board:

The TCAC has reviewed Ecogy's 16 February 2022 memo which is in response to the TCAC's 11 February 2022 memo. We find that this project is not in compliance with the requirements of Chapter 270 for the following reasons:

- 1. Ecogy states that they have submitted a mitigation plan in their 8 November 2021 memo. The TCAC notes that they did not receive this memo until after our 11 February 2022 memo was issued. However, their landscape plan does not gualify as mitigation. During the PB's work session of 24 January 2022, related to the Foothill Street solar project, the PB's lawyer, James W. Glatthaar, Esa., stated that screening plantings do not qualify as replacement trees because a screening plan is required by the solar law.
- 2. Ecogy states that "Given the number of trees and the complexity of the large tree removal area, we were not able to pinpoint exact tree locations on the site plan." Other, far more complicated projects have provided the required tree removal plans. Chapter 270 requires the submittal of a tree removal plan. It should be provided. Ecogy further states that "In addition, as far as we are aware, there are no protected woodlands on site and so we have not shown these on our plans." However, in their 8 November 2021 memo they state that "The total area of tree removal is 75,000 square feet." Given this large area of removals, the TCAC finds it hard to believe that no protected woodlands are being disturbed. Ecogy needs to provide a letter from their Certified Arborist stating that no protected woodlands are being disturbed.
- 3. Ecogy states that they "never stated we plan to mitigate the tree removal by planting replacement trees as required by the mitigation ratio. Instead, Ecogy has proposed a landscaping plan that focuses on screening, ...". As noted above, a screening plan does not qualify as a mitigation plan. The calculation of a mitigation ratio and a tree deficit are vital for the Town to understand the magnitude of what we are losing by the removal of the project's existing trees. Chapter 270 requires these calculations. They should be provided.
- 4. Ecogy states that because "the proposed plantings as described in the landscaping plan as not being considered for one-to-one replacement of the removed trees or to satisfy the mitigation ratio. Therefore, the DBH is not necessary." As noted above, a mitigation ration is vital for the Town's

understanding of its loss. In order to calculate this ratio, the DBH's of the proposed trees is required. This information needs to be provided.

- 5. Ecogy states that they "provided a proposed payment in a Memo dated November 8, 2021." Until it is determined that no protected woodlands are being disturbed, the value of this payment is in question.
- 6. Sourwood trees are native in the northeast from Pennsylvania to Florida. They are not native to the lower Hudson Valley. The TCAC suggests replacing them with the Cornus trees that are already being used in the plan. The suggestion to not replace them is not acceptable to our ethics.
- 7. The TCAC acknowledges the daunting task of planting a long and large screening. It also recognizes the maintenance needed to establish a mature hedge. Perhaps the rows of Arborvitae can be staggered like the White Pines. That way if one fails as they mature it won't result in as large a gap in the screening. Also, White Spruce can be planted as part of this staggered two row arrangement. This would reduce the quantity of Arborvitae.
- 8. The TCAC apologizes to the double comments regarding the Viburnums. We are also being diligent in reviewing your project.

Until the above deficiencies and recommendations are addressed, this proposal should not be allowed to advance further in the Planning Board review process.

Sincerely,

Tree Conservation Advisory Commission Lawrence W. Klein, P.E., Member Keith Schepart, ISA, Member Tom Schmitt, Member

Matthew Slater Town Supervisor

TOWN OF YORKTOWN CONSERVATION BOARD

Town of Yorktown Town Hall, 363 Underhill Avenue, Yorktown Heights, New York 10598, Phone (914) 962-5722

MEMORANDUM

То:	Planning Board	RECEIVED PLANNING DEPARTMENT
From:	Conservation Board	FEB 2 2 2022
Date:	February 17, 2022	TOWN OF YORKTOWN
Re:	716 Kitchawan Road – Proposed Solar Farm	

The Conservation Board at its February 16, 2021 meeting discussed a proposed solar farm located at 716 Kitchawan Road with Julia Magliozo of Ecogy. The Conservation Board has the following comments:

- The applicant has proposed a post construction stormwater management that could overflow into the wetland. The practice has not been fully developed. This measure when developed could intrude into the wetland buffer. Conservation Board would like to see the practice when fully developed to ensure the practice preserves the water quality of the wetland and provides mitigation if needed.
- The Board agrees with the Tree Advisory Board on providing a variety of screening trees instead of one long row of the same species.

Respectfully submitted:

Diane Dreier

For the Conservation Board

CC: Town Board Planning Board Supervisors Office Engineering Dept. TCAC Applicant To: Town of Yorktown Tree Conservation Advisory Commission From: Ecogy Energy cc: Town of Yorktown Planning Board Date: February 16, 2022 Re: Ecogy Kitchawan Community Solar Farm LLC Response to Memo Received from TCAC on February 11, 2022

RECEIVED PLANNING DEPARTME

Dear members of the Yorktown Tree Conservation Advisory Commission,

Please accept this Memo of explanation in response to the comments received in the TCAC Memo dated February 11, 2022 regarding the proposed Kitchawan Farm Community Solar Farm at 716 Kitchawan Road. The responses are numbered to correspond to the comments as received in the TCAC Memo.

1. *The TCAC states that we have not provided a mitigation plan.* Ecogy has provided such a plan as outlined in our Memo dated November 8, 2021 submitted to the Planning Board during the Public Hearing. As stated in the Memo, the mitigation plan includes planting trees per the landscaping plans as well as proposing a payment of \$16,800 (\$100 for every tree to be removed) into the Tree Bank Fund. Please note the exact number of trees to be planted will adhere to the most recent landscaping plans, submitted on February 1, 2022, and not the numbers listed in the previous Memo.

2. The TCAC states we have not provided a tree removal plan or show protected woodlands. Providing a tree removal plan is not reasonable. The largest area of tree removal is shown in our site plan and all trees have been inventoried, listed, and tagged on site. The complete list of inventoried trees has been submitted to the Town. Given the number of trees and the complexity of the large tree removal area, we were not able to pinpoint exact tree locations on the site plan. It would have been too cluttered and not useful information as all trees in that area will be removed. In addition, as far as we are aware, there are no protected woodlands on site and so we have not shown these on our plans.

3. The TCAC states we have not provided a mitigation ratio or tree deficit calculation. Ecogy has never stated we plan to mitigate the tree removal by planting replacement trees as required by the mitigation ratio. Instead, Ecogy has proposed a landscaping plan that focuses on screening, which will result in 198 trees and 328 shrubs being planted. We have also proposed a mitigation plan which involves paying \$100 for each of the 168 trees being removed. The new plantings and the payment into the Tree Bank Fund we believe should be considered sufficient mitigation, regardless of the mitigation ratio number.

4. *The TCAC requests the DBH for the plantings shown in the landscaping plan.* Related to point 3, the proposed plantings as described in the landscaping plan as not being considered for one-to-one replacement of the removed trees or to satisfy the mitigation ratio. Therefore, the DBH is not necessary.

5. *The TCAC states we have not provided a payment to the Tree Bank Fund.* Ecogy has provided a proposed payment in a Memo dated November 8, 2021.

6. The TCAC states two of the trees chosen, Wildfire Sourwood and Sourwood, are not native to New York and must be replaced. The Wildfire Sourwood is native to the Northeastern United States, a range which does include New York. Regardless, given that we have proposed to plant one each of those trees and they have been shown on our landscaping plans since June, we question why the TCAC has chosen to point them out at this time. Rather than finding a replacement, it may be easier for Ecogy to remove those two trees entirely from the plans.

7. The TCAC states the choice to plant 85 Green Giant Arborvitae will create a monoculture and recommends they are replaced with other tree species. The Arborvitae were chosen for their growth rate and screening ability. In addition, given the size of the site and the screening required, the Arborvitae need to remain in the plan because a large number of trees need to be planted along the access road and the Arborvitae are the most highly recommended species.

8. The TCAC recommends we replace some of the Viburnums with another species. Ecogy believes this is unnecessary given previous discussions with the TCAC. On October 18, 2021 the TCAC sent a Memo stating that the Arrowood Viburnum, as originally proposed in the landscaping plan, should be replaced with Viburnum lentago (nannyberry) and Viburnum prunifolium (Black Haw), because they are less susceptible to the leaf beetle. We made that change in the current landscaping plans and do not feel we should be forced to change the landscaping plans yet again when we have already adhered to previous TCAC recommendations.

Overall, we have been working diligently to address all TCAC comments throughout the planning process and thank the TCAC for considering our response. We feel strongly that the 716 Kitchawan solar project should not be held up due to this latest Memo and hope the TCAC will reconsider their recommendation.



TO: Town of Yorktown Planning Board FROM: Ecogy Energy DATE: Nov 08, 2021 RE: Tree Removal & Mitigation Plan For Ecogy Kitchawan Community Solar Farm (Ecogy New York XI LLC)

Ecogy Kitchawan Community Solar Farm is a proposed 2670.3 kW DC ground mounted system located at 716 Kitchawan Road, Yorktown, New York. This memo addresses the Tree Removal & Mitigation concerns associated with this project.

This project requires removal of a maximum of 168 trees, of which 20 are invasive and 148 are non-invasive. Out of the 168 trees, 15 are non-viable trees that require removal due to poor condition, whereas the remaining 153 trees are viable trees. The total area of tree removal is 75,000 square feet.

Ecogy's mitigation plan includes planting a total of 123 trees and 403 shrubs. Out of the 123 trees, 94 are Evergreens and 29 are Deciduous. Out of the 403 shrubs, 90 are Broadleaf Evergreen, 83 are Semi-Evergreens and the remaining 230 are Deciduous. There were some concerns from the Town about the visibility of the arrays from Kitchawan road, and Ecogy plans on addressing this concern by planting a total 33 trees and shrubs next to the road, in order to minimize the visibility of the arrays. A line of sight analysis from the road was requested by the Planning Board and it will be provided once it is ready.

Moreover, the Yorktown code § 270-10D(4)(f) states that the mitigation plan may include but not be limited to "Payment into the Tree Bank Fund. In lieu of replacing a lost protected tree or disturbance to a protected woodland, the payment shall be \$100 for every protected tree removed". Ecogy plans to deposit \$100 for **each** tree removed regardless of status, which is more than the recommended number of trees requiring mitigation. With this payment of \$16,800 into the Tree Bank Fund, Ecogy hopes to ensure satisfactory mitigation per the Town code in our mitigation plan.

UTILITY EQUIPMENT KEY:

- NEW UTILITY OWNED 2000 kVA TXFMR $\langle 1 \rangle$ 13.2 KV WYE PRIMARY, 480 V WYE SECONDARY
- EXISTING UTILITY POLE #W.55 $\langle 2 \rangle$

CUSTOMER EQUIPMENT KEY:

- AC DISCONNECT SWITCH (PV SYSTEM) SOLAREDGE INVERTERS AC COMBINER PANEL $\langle A \rangle$ PV SYSTEM UTILITY METER DAS
- (NEW) CUSTOMER OWNED RISER POLE WITH GOAB $\langle B \rangle$
- (NEW) CUSTOMER OWNED CLASS 1 POLE WITH $\langle c \rangle$ UTILITY SUPPLIED RECLOSER

NOTE:

- 1. MEADOW SEED MIXTURE TO BE PLANTED BETWEEN PV ARRAY ROWS
- 2. FENCING AROUND THE ARRAY WILL BE WILDLIFE FRIENDLY

SYMBOLS LEGEND:

- Ś. EXISTING UTILITY POLE
- PROPOSED UTILITY POLE ١.

LINETYPE LEGEND:

	APPROXIMATE PROPERTY LINE
	PROPERTY LINE SETBACK
xx	PROPOSED CHAINLINK FENCE
0E	OVERHEAD ELECTRIC
UE	UNDERGROUND ELECTRIC
· · ·	APPROXIMATE WETLAND BOUNDARY GIS
	10' ARRAY SETBACK







PRUNE EX TREES OVERHANGIN PROPERTY 9-PS 7-TSS SHRUB PLANTING L-4 DETAIL (TYP) 9-16 SOLAR 7-MP 5-LP 9-PSS 5-MF 6-HV 7–16 EX TREE TO BE TRANSPLANTED ||2-TSS 5-PSS 7-LB 7-VP 7—IV 5-VL 7-05 9-16 7–LB 5-MP 7-MP 5-PG VL \$000000000000 18-TSS-PROPOSED VEGETABLE GARDENS ×311.1 CLEAN UP NOTES: DEAD ASH TREES WITHIN THIS AREA TO BE REMOVED. PROTECT ALL HEALTHY TREES, WHICH ARE TO REMAIN. UNDERSTORY VEGETATION TO REMAIN + ATEI KITCHAWAN ROAD (ST. REMAIN 3-TS- $\begin{pmatrix} 2\\ L-4 \end{pmatrix}$ DECIDUOUS TREE PLANTING DETAIL (TYP) Revised Plan & Plant List per comment 01.31.22 Revised Plant List per P.B. comment to add screen trees to West 01.07.22 Revised Plant List per P.B. comment 11.01.21 10.25.21 Revised per Town review & comment Date





Date

ANICAL NAME	COMMON NAME	SIZE	NOTES	SPACING	DECIDUOUS TYPE	AV. GROWTH PER YR	YRS TO MATURE HT.	MAX. HT./MAX SPREAD
r rubrum 'Autumn Flame'	Autumn Flame Red Maple	2"-2 1/2"cal.	Full, Heavy, Matching		Deciduous	24"	26	50'/50'
elanchier canadensis	Shadblow Serviceberry	8'-10' ht.	Full, Heavy, Multi-stem, B&B		Deciduous	24"	15	30'/20'
ıla nigra 'Heritage'	Heritage River Birch	8'-10' ht.	Full, Heavy, Matching, Clumps	25' O.C.	Deciduous	24"	35	70'/60'
cis canadensis	Eastern Redbud	8'-10' ht.	Full, Heavy, Multi-stem, B&B		Deciduous	12"-24"	15	30'/35'
nus rutgersensis 'Hyperion'	Hyperion Dogwood	2"-2 1/2"cal.	Full, Heavy, Matching, Specimen, B&B	20' O.C.	Deciduous	12"-24"	10	20'/20'
nus rutgersensis 'Stellar Pink'	Stellar Pink Dogwood	2"-2 1/2"cal.	Full, Heavy, Matching, Specimen, B&B	20' O.C.	Deciduous	12"-24"	10	20'/20'
ораса	American Holly	8'-9 ht.	Full, Heavy, Specimen, B&B		Evergreen	12"-24"	15	30'/20'
perus virginiana	Eastern Red Cedar	8'-10' ht.	Full, Heavy, Specimen, B&B		Evergreen	24"	35	70'/25'
sa sylvatica 'Wildfire'	Wildfire Sourwood	2"-2 1/2" cal.	Full, Heavy, Specimen, B&B		Deciduous	12"-24"	25	50'/30'
ya virginiana	American Hophornbeam	2"-2 1/2" cal.	Full, Heavy, Specimen, B&B		Deciduous	12"-24"	20	40'/20'
dendrum arboreum	Sourwood	8'-10' ht.	Full, Heavy, Specimen, B&B		Deciduous	12"-24"	25	50'/25'
a glauca 'Black Hills'	White Spruce	8'-10' ht.	Full, Heavy, Specimen, B&B	9' O.C.	Evergreen	<12"	40	40'/15'
a glauca 'Black Hills'	White Spruce	12'-14' ht.	Full, Heavy, Specimen, B&B	12' O.C.	Evergreen	<12"	40	40'/15'
ıs strobus	White Pine	8'-10' ht.	Full, Heavy, Specimen, B&B	9' O.C.	Evergreen	24"-36"	27	80'/40'
ıs strobus	White Pine	12'-14' ht.	Full, Heavy, Specimen, B&B	9' O.C.	Evergreen	24"-36"	27	80'/40'
rcus bicolor	Swamp White Oak	2"-2 1/2"cal.	Full, Heavy, Specimen, B&B		Deciduous	12"-24"	30	60'/60'
rcus rubra	Red Oak	2"-2 1/2"cal.	Full, Heavy, Specimen, B&B		Deciduous	12"-24"	38	75'/75'
ja standishii	Green Giant Arborvitae	8'-10' ht.	Full, Heavy, Specimen, B&B	10' O.C.	Evergreen	36"	20	60'/20'
ja standishii	Green Giant Arborvitae	10'-12' ht.	Full, Heavy, Specimen, B&B	10' O.C.	Evergreen	36"	20	60'/20'
canthus floridus	Common Sweetshrub	3'-3 1/2' ht.	Full, Heavy, Container	5' O.C.	Deciduous	12"-18"	6	9'/12'
hra alnifolia	Sweet Pepperbush	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	12"-18"	5	8'/6'
nus sericea 'Baileyi'	Redtwig Dogwood	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	24"	5	9'/9'
/lus americana	American Hazelnut	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	24"	8	16'/13'
namelis virginiana	Witchhazel	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	12"-24"	10	20'/20'
glabra	Inkberry	3'-3 1/2' ht.	Full, Heavy, Matching, Container	6' O.C.	Broadleaf Evergreen	<12"	10	8'/8'
glabra 'Shamrock'	Shamrock Inkberry	3'-3 1/2' ht.	Full, Heavy, Matching, Container	6' O.C.	Broadleaf Evergreen	<12"	7	5'/5'
verticillata 'Winter Red'	Winter Red Winterberry	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	<12"	10	8'/8'
era benzoin	Spicebush	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	12"-18"	8	12'/12'
ica pensylvanica	Bayberry	3'-3 1/2' ht.	Full, Heavy, Matching, Container	6' O.C.	Semi-evergreen	12"-18"	8	12'/12'
dodendron maximum	Rosebay Rhododendron	3'-3 1/2' ht.	B & B, Full, Heavy	6' O.C.	Broadleaf Evergreen	12"-24"	7	15'/20'
bucus canadensis	Elderberry	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	12"-24"	6	12'/12'
ırnum lentago	Nannyberry	3'-3 1/2' ht.	Full, Heavy, Container	6' O.C.	Deciduous	12"-24"	10	20'/20'
ırnum prunifolium	Blackhaw Viburnum	3'-3 1/2' ht.	Full, Heavy, Container	5' O.C.	Deciduous	12"-24"	7	15'/10'

	Seal	Project Title	Graphic
C 🈡 Chalifoux LLC	SED LANDSCAPE ARCH	LANDSCAPE MASTER PLAN	
dscape Architect Street, Danbury, CT 06811 Office: 845-364-1360 I: tlchalifoux@gmail.com	States of the st	ECOGY NEW YORK XI LLC KITCHAWAN	Date
	OF NET	^{Location} 716 KITCHAWAN ROAD YORKTOWN, NY 10562	Scale AS

PLANTING NOTES:

- CONTACT CALL DIG SAFELY NEW YORK AT 811 OR WWW.DIGSAFELYNEWYORK.COM TO HAVE UNDERGROUND UTILITY LINES MARKED PRIOR TO START OF ANY EXCAVATION WORK. BASE MAP INFORMATION WAS TAKEN FROM "PARTIAL BOUNDARY AND TOPOGRAPHIC SURVEY"
- PREPARED BY TECTONIC ENGINEERING CONSULTANTS, GEOLOGISTS & LAND SURVEYORS, D.P.C., DATED APRIL 22, 2021.
- 3. EXACT LOCATION OF PLANTINGS, SPECIES TYPES AND QUANTITIES MAY VARY FROM THIS PLAN BASED ON SITE PLAN REVISIONS AND/OR ACTUAL FIELD CONDITIONS. 4. IN THE EVENT OF A DISCREPANCY BETWEEN THE QUANTITIES OF PLANTS IN THE 'PLANT LIST'
- AND THE ACTUAL QUANTITIES SHOWN ON THE PLAN THE PLAN SHALL GOVERN. 5. ANY PLANTINGS SUSCEPTIBLE TO DEER BROWSING SHALL BE SPRAYED WITH ORGANIC DEER REPELLENT, OR PROTECTED BY PHYSICAL MEASURES, SUCH AS WITH TEMPORARY FENCING
- OR TREE TUBES, WHERE APPROPRIATE. 6. ALL NEW PLANTINGS SHALL EITHER BE HAND WATERED, OR A TEMPORARY IRRIGATION
- SYSTEM SHALL BE PROVIDED UNTIL PLANTINGS ARE ESTABLISHED. THE LANDSCAPE CONTRACTOR SHALL READ ALL LANDSCAPE PLANS, SPECIFICATIONS AND VISIT THE PROJECT SITE TO BECOME FAMILIAR WITH EXISTING CONDITIONS PRIOR TO BIDDING THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL QUANTITIES SHOWN ON THESE PLANS BEFORE PRICING THE WORK.
- 8. ANY AND ALL QUESTIONS CONCERNING THE LANDSCAPE PLANS AND SPECIFICATIONS SHALL BE DIRECTED TO THE LANDSCAPE ARCHITECT
- PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGRAIND UTILITIES AND SHALL AVOID DAMAGE TO ALL UTILITIES DURING THE COURSE OF THE WORK. LOCATIONS OF EXISTING BURIED UTILITY LINES SHOWN ON THE PLANS ARE BASED UPON BEST AVAILABLE INFORMATION AND ARE TO BE CONSIDERED APPROXIMATE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR () TO VERIFY THE LOCATIONS OF UTILITY LINES AND ADJACENT TO THE WORK AREA 2) TO PROTECT OF ALL UTILITY LINES DURING THE CONSTRUCTION PERIOD 3) TO REPAIR ANY AND ALL DAMAGE TO UTILITIES, STRUCTURES, SITE APPURTENANCES, ETC. WHICH OCCURS AS A RESULT OF THE CONSTRUCTION.
- 10. THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR WATERING, MULCHING, AND OTHER REQUIREMENTS OF PLANT MATERIALS WHILE THEY ARE TEMPORARILY STORED ON OR OFF SITE. CONTRACTOR SHALL BE RESPONSIBLE FOR DELIVERY SCHEDULE AND PROTECTION BETWEEN DELIVERY AND PLANTING PER SPECIFICATIONS TO MAINTAIN HEALTHY PLANT CONDITIONS.
- II. THE LANDSCAPE CONTRACTOR SHALL COORDINATE LAYOUT OF PLANTING BEDS, PLANT MASSING, STAKED LOCATION OF TREES AND INSTALLATION OF PLANT MATERIAL WITH LANDSCAPE ARCHITECT PRIOR TO COMMENCEMENT OF WORK.
- 12. ALL LANDSCAPE MATERIAL SHALL MEET THE AMERICAN STANDARD FOR NURSERY STOCK (ANSI Z60.1-1996) PER THE AMERICAN ASSOCIATION OF NURSEYMEN. ALL PLANT MATERIAL SHALL BE HEALTHY, VIGOROUS, AND FREE OF PESTS AND DISEASE. ALL PLANT MATERIAL SHALL BE CONTAINER GROWN OR BALLED AND BURLAPPED AS INDICATED IN THE PLANT LIST.
- PER OWNER'S DIRECTION, THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO INSPECT ALL 13 PLANT MATERIAL AT THE NURSERY, PRIOR TO SELECTION OR DIGGING. CONDUCT PLANTING UNDER FAVORABLE WEATHER CONDITIONS DURING EITHER THE SPRING
- PLANTING SEASON, MARCH | TO JUNE |, OR THE FALL PLANTING SEASON, SEPTEMBER 30 UNTIL FREEZING OF THE GROUND. DURING THE FALL PLANTING SEASON, CONIFERAUS MATERIAL PLANTING SHALL BE CONDUCTED AUGUST 15 TO OCTOBER 1. DEVIATION FROM THE ABOVE PLANTING DATES WILL ONLY BE PERMITTED WITH APPROVAL IN WRITING BY THE LANDSCAPE ARCHITECT.
- THE PLANTING SOIL MIXTURE FOR ALL TREE PLANTINGS SHALL INCLUDE SOIL EXCAVATED 15 FROM THE HOLE. RATIO: 50% VIRGIN SOIL + 50% AMENDED TOP SOIL. ROOT STIMULATOR SHALL BE APPLIED TO ALL PLANT MATERIALS WITH THE EXCEPTION OF
- LAWN AREAS. APPLY AS PER THE MANUFACTURERS SPECIFICATIONS. THE LANDSCAPE CONTRACTOR SHALL RESTORE FINISH GRADES IN ALL PLANTING AREAS (PER
- GRADING PLANS) WHICH MAY HAVE BEEN DISTURBED DURING PLANTING OPERATIONS. 13. ALL TREE SAUCERS AND PLANTING BEDS ARE TO BE MULCHED WITH A MINIMUM OF 3"
- DOUBLE-GROUND HARDWOOD MULCH (NON-DYED). LANDSCAPE CONTRACTOR TO PROVIDE MULCH SAMPLE TO LANDSCAPE ARCHITECT FOR REVIEW PRIOR TO INSTALLATION. WHERE PLANTING BEDS ARE ADJACENT TO WALKS AND CURBS THE SOIL LEVEL SHALL BE 3" LOWER TO ALLOW FOR MULCH LAYER.
- 19. MULCH, STAKES, GUY WIRE, PRE-EMERGENT HERBICIDES, ETC. SHALL BE SUBSIDIARY TO INDIVIDUAL PLANTS.
- 20. LABEL EACH TREE AND SHRUB WITH A SECURELY ATTACHED, WATERPROOF TAG BEARING LEGIBLE DESIGNATION OF BOTH BOTANICAL AND COMMON NAME. LABEL EACH ORNAMENTAL GRASS, GROUNDCOVER, PERENNIAL AND ANNUAL WITH THE LABEL PROVIDED BY THE ORIGINAL GROWER OF THE PLANT. LABELS SHALL NOT BE REMOVED UNTIL AFTER PROVISIONAL ACCEPTANCE BY LANDSCAPE ARCHITECT.
- 21. STAKES AND GUY WIRES, IF USED, SHALL BE REMOVED AT THE END OF ONE FULL GROWING SEASON.
- 22. LOOSEN SOIL FOR ALL PLANTING ISLANDS AND SHRUB/PERENNIAL BEDS TO A DEPTH OF 12". 23. TOPSOIL SHALL BE FERTILE NATURAL TOPSOIL, TYPICAL OF THE LOCALITY, OBTAINED FROM WELL DRAINED AREAS. STOCKPILED TOPSOIL MAY BE USED. IT SHALL BE WITHOUT ADMIXTURE OF SUBSOIL OR SLAG AND SHALL BE FREE OF STONES, LUMPS, STICKS, PLANTS OR THEIR ROOTS, TOXIC SUBSTANCES OR OTHER EXTRANEOUS MATTER THAT MAY BE HARMFUL TO PLANT GROWTH OR WOULD INTERFERE WITH FUTURE MAINTENANCE. TOPSOIL PH RANGE SHALL BE 5.5 TO 7.0.
- 24. THERE SHALL BE NO ADDITIONS, DELETIONS OR SUBSTITUTION OF PLANT MATERIAL SPECIES WITHOUT THE WRITTEN APPROVAL BY THE OWNER OR LANDSCAPE ARCHITECT. ANY SUBSTITUTION THAT HAS NOT BEEN APPROVED SHALL BE REMOVED AND REPLACED WITH THE CORRECT PLANT AT LANDSCAPE CONTRACTOR'S EXPENSE.
- 25. THE LANDSCAPE CONTRACTOR SHALL PROVIDE THE OWNER AN UNCONDITIONAL 2-YEAR WARRANTY OF PLANT MATERIAL SHALL BEGIN FROM THE TIME OF HANDLING PLANT MATERIAL AT TIME OF DELIVERY THROUGH INSTALLATION AND END AFTER SUBSTANTIAL COMPLETION AND FINAL PUNCH-LIST APPROVAL BY LANDSCAPE ARCHITECT. WARRANTY SHALL INCLUDE ALL LABOR REQUIRED REPLACING MATERIALS ON-SITE.
- 26. THE LANDSCAPE CONTRACTOR WILL BE RESPONSIBLE FOR THE COLLECTION, REMOVAL, AND PROPER DISPOSAL OF ANY AND ALL DEBRIS GENERATED DURING THE INSTALLATION OF THE LANDSCAPE CONSTRUCTION.
- 27. ANY PLANT MATERIAL WHICH IS DISEASED, DISTRESSED, DEAD, OR REJECTED (PRIOR TO SUBSTANTIAL COMPLETION) SHALL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH MATERIAL OF THE SAME SPECIES, QUANTITY, AND SIZE AND MEETING ALL PLANT LIST SPECIFICATIONS.

Scale and North Arrow	Drawing Title PLANTING DETAILS, PLANT LIST	Drawing No.
June 3, 2021	& PLANTING NOTES	
Checked Drawn SHOWN TLC TLC		SHEET 4 OF 4

1/27/2022

FEB 1 1 2022

TOWN OF YORKTOWN

To: Yorktown Planning Board From: Yorktown Tree Conservation Advisory Commission (TCAC) Date: 11 February 2022 cc: Yorktown Planning Dept. (J. Tegeder, R. Steinberg, N. Calicchia); Engineering Dept. (L. Kobiliak); Conservation Board (K. Hughes); Town Supervisor (M. Slater); Town Clerk (D. Quast); TCAC members (L. Klein, T. Schmitt, K. Schepart)

Re: Proposed solar facility at 716 Kitchawan Road

Dear Chairman Fon and members of the Planning Board:

The TCAC has reviewed all of the referral materials in our possession for the referenced project. We find that this project is not in compliance with the requirements of Chapter 270 for the following reasons:

- The Engineer has provided no mitigation plan. Chapter 270-10.B.(1) states that "All nonadministrative permits require mitigation". Chapter 270-10.D.(1) states that "The approval authority shall require the preparation of a mitigation plan".
- 2. The Engineer has not provided a tree removal plan or area of protected woodlands disturbance. Chapter 270-8.A.(1).(b) requires "A plan or sketch showing proposed tree removals" Chapter 270-8.C.(1)(b) requires a plan showing "Within the proposed area of disturbance the location of existing trees and/or protected woodlands". Chapter 270-8.C.(1)(c) requires a plan showing "Within the proposed area of disturbance, the number, location and species of protected trees to be removed". Chapter 270-8.C.(1)(d) requires a plan showing "The square footage and boundaries of protected woodlands that will be disturbed".
- 3. The Engineer has not provided a mitigation ratio or a tree deficit calculation as required by Chapter 270-4.
- 4. Many of the proposed trees listed on Drawing L-4, PLANTING DETAILS, PLANT LIST & PLANTING NOTES, have sizes listed with heights instead of DBH's. All proposed trees need to be listed with DBH's. Without DBH's, a mitigation ratio cannot be calculated.
- 5. The Engineer has not provided a payment to the Tree Bank Fund calculation as required by Chapter 270-10.D.(4)(f).
- 6. The Wildfire Sourwood and Sourwood trees on the tree list are not native to New York. Chapter 270-10.C.(4) states "Use of native species of trees, understory shrubs and herbaceous ground cover if replanting is required". A native substitute must be chosen.
- 7. The committee has agreed to the planting of Green Giant Arborvitae on other projects even though they are not native. However, planting 85 of these trees is excessive and creates a monoculture. It is recommended that the Developer plant more Eastern Red Cedars, White Spruce and White Pine.

8. The proposed Viburnums are native to NY but are moderately susceptible to leaf beetles. Planting 42 of these shrubs may lead to an infestation. The Viburnum setigerum is less susceptible. Mt. Laurel is a hardy native shrub that could be a partial substitute along with more of the other shrubs listed.

Until the above deficiencies and recommendations are addressed, this proposal should not be allowed to advance further in the Planning Board review process.

Sincerely,

Tree Conservation Advisory Commission Lawrence W. Klein, P.E., Member Keith Schepart, ISA, Member Tom Schmitt, Member



RECEIVED PLANNING DEPARTMENT

Memorandum

То:	Shelby Hang, Ecogy Energy	FEB 2	2	2022
From:	Michael Gagnon, PE, SLR	TOWNOF	YOI	RKTOWN
Date:	February 1, 2022			
Subject:	Kitchwawan Ground Mount Solar – Preliminary Stormwater Res	ults		

Stormwater watershed cover and peak-flow calculations were calculated based on the solar facility layout received from Ecogy Energy on January 27, 2022, for the project located at 716 Kitchawan Road in Ossining, New York. The proposed layout will include tree clearing south of the array and the installation of a new 18-foot-wide gravel access road. The revised layout contained additional tree clearing, which resulted in an increase in proposed peak-flows, as shown in Table 1.

	1-Year (Cpv)	10-Year (Qp)	25-Year	100-Year (Qf)
Existing	7.97	35.42	50.53	75.1
Proposed	8.16	35.65	50.85	75.58
Change	0.19	0.23	0.32	0.48
Percent Change	2%	1%	1%	1%

Table 1. Peak-Flow Rates for Revised Layout Without Stormwater Management Basin Attenuation

Since proposed peak-flow rates exceed existing rates for all storm events, various stormwater management options were reviewed to meet Town requirements for no net increase in peak flows. Consequently, it was determined that the installation of a stormwater management basin would attenuate peak-flow rates and result in an overall reduction for all storm events. For the purposes of this preliminary analysis, the stormwater management basin will be located at the northwest corner of the site to capture runoff from the northern and western parts of the site. This area is best suited for the siting of a stormwater management basin considering the adequate distance from the property line and the presence of an uninhabited wetland area north of the outlet of the basin, and deeper depth to groundwater. The stormwater management basin will have a V-notch weir wall to allow for overflow in higher storm events. It is estimated that 14,000 cubic-feet of storage is required to attenuate peak-flow rates.

February 1, 2022 Page 2

Using a stormwater management basin storage of 14,000 cubic-feet, peak-flow rates under proposed conditions were reduced for all storm events. Results for the preliminary analysis with the stormwater management basin is shown in Table 2.

X	1-Year (Cpv)	10-Year (Qp)	25-Year	100-Year (Qf)
Existing	7.97	35.42	50.53	75.10
Proposed	7.7	34.55	49.4	75.10
Change	-0.27	-0.87	-1.13	0.00
Percent Change	-3%	-2%	-2%	0%

Table 2. Peak-Flow Rates with Stormwater Management Basins

Installation of the solar facility and stormwater management basin will result in some ground disturbances throughout the site. There will be minor grading activities associated with the stormwater management basin, tree clearing, installation of solar panel racking support posts, addition of a new gravel access road, and installation of impervious equipment pads. Total disturbance area is anticipated to be approximately 1.50 acres. Disturbance types and areas are summarized in Table 3 below.

Disturbance Type	Area (SF)
Tree clearing	37,000
Solar Equipment Pads	720
Solar Panel Racking Support Posts	10
New gravel access drive	20,450
Stormwater management basin (approx.)	7,000
Total	65,180

Table 3. Summary of Land Disturbances







it SLR Engineering, Landscape Architecture, and Land Surveying, P.C. Registration No. 08


Γ

Town of Yorktown www.yorktownny.org

Building Department Town Hall, 363 Underhill Avenue, Yorktown Heights, NY 10598

Tel. (914) 962-5722 ext.254 Fax (914) 962-1731

MEMORANDUM

	Edward Kolisz, Fire Ins	pector
Telephone (914) 962 5722 ext. 254	Email: ekolisz@yorktownny.org	Office hours: Weekdays 9:00-10:00 a.m., 3:30-5:00 p.m.

Planning Board, Town of Yorktown TO:

From: Edward Kolisz, Fire Inspector

Kitchawan Farm Solar Farm Access Rd. Revision Re:

Date: January 21, 2022

I have reviewed the proposed changes to the access road to the Kitchawan Farm solar farm plan. I have no objections or concerns to moving the access road. Please contact me with any questions.

Ryder Subdivision

TOWN OF YORKTOWN PLANNING DEPARTMENT

Albert A. Capellini Community and Cultural Center, 1974 Commerce Street, Yorktown Heights, New York 10598, Phone (914) 962-6565, Fax (914) 962-3986

To:Planning BoardFrom:Planning DepartmentDate:February 24, 2022Subject:Ryder Subdivision
SBL: 48.06-1-12

The Planning Department has reviewed the current submission and has the following comments:

- 1. The applicant should submit a new application form and EAF for the current application.
- 2. The applicant should submit a stormwater and wetland permit application and associated fees.
- 3. The wetland delineation and mitigation plan should be reviewed by the Town's environmental consultant.
- 4. The Public Informational Hearing can be scheduled for the March 14, 2022 meeting.

Respectfully submitted,

serg Robyn A. Steinberg, AICP, CPESC

Town Planner

Site Design Consultants

Civil Engineers . Land Planners

RECEIVED PLANNING DEPARTMENT

FEB 1 6 2022

TOWN OF YORKTOWN

February 15, 2022

Ms. Robyn Steinberg, AICP Town Planner Yorktown Planning Department 1974 Commerce Street Yorktown Heights, NY 10598

Re: Ryder Subdivision 532 Underhill Avenue SBL 48.06-1-12

Dear Robyn:

Enclosed please find the following items for placement on the agenda for the Planning Board Meeting of February 28, 2022:

- Five prints of the Mitigation Plan prepared by Steve Marino;
- Five prints of the Site Plan titled "Site Plan Prepared for Ryder," Sheet 1of 1, dated 2-15-2022,

We would also request that the Board set a Public Information Hearing date for this project. We will submit a digital copy of this submission. If you have any questions or need additional information, please contact me. Thank you.

Yours Tr Riina, P.E. Joseph (

Cc: **Town Supervisos Engineering Department** Bureau of Fire Prevention **Building Department** Water Department Ed Lachterman Andrew Ryder

JCR / cm / Enc. / sdc 21-21



251-F Underhill Avenue • Yorktown Heights, New York 10598 60 Walnut Grove Road • Ridgefield, Connecticut 06877 (203) 431-9504 Fax (914) 962-7386

(914) 962-4488



- EXISTING TOWN ZONING: PROPOSED USE: TOWN TAX MAP DATA: SEWAGE FACILITIES:
- WATER FACILITIES:

ANDREW & GEORGE RYDER 23 CREST DRIVE YORKTOWN HEIGHTS, NY 10598 532 UNDERHILL AVENUE TOWN OF YORKTOWN R1-40, SINGLE FAMILY RESIDENTIAL R1-40, SINGLE FAMILY RESIDENTIAL R1-40, SINGLE FAMILY RESIDENTIAL SECTION 48.06, BLOCK 1, LOT 12 6.09 ACRES (325,624.46 SF) SUBSURFACE SEWAGE DISPOSAL PUBLIC WATER FACILITIES

		R1-40, RESIDENTIAL		
ATIONS:	REQUIRED	<u>LOT 1</u>	LOT 2	VARIANCE REQUIRED
T:				
EA:	40,000 SF.	66,458 SF.	198,758 SF.	NONE
)TH:	150 FT.	165 FT.	165 FT.	NONE
PTH:	150 FT.	433 FT.	937 FT.	NONE
RONTAGE:	150 FT.	165 FT.	165 FT.	NONE
NSIONS:				
ING:				
BACK:	50 FT.	175 FT	241 FT	NONE
ACK:	50 FT.	164 FT.	568 FT.	NONE
ETBACK:	20 FT.	30 FT.	28 FT.	NONE
ARD SETBACK:	50 FT.	75 FT.	54 FT.	NONE
DINGS:				
BACK:	50 FT.	N/A	N/A	NONE
ACK:	50 FT.	N/A	N/A	NONE
ETBACK:	20 FT.	N/A	N/A	NONE
ARD SETBACK:	50 FT.	N/A	N/A	NONE
TO BE OCCUPIED:				
ING COVERAGE:	15% OF LOT AREA	3 % OF LOT AREA	1 % OF LOT AREA	NONE

"The

20

SCALE: 1"=40'-0"

SAFE DIG

40





Plant quantities w	vill be held,	but final	locations	will be	determined	in the fie	d following	removal	of invasive	and	dead	plant n
nd preservation of	f existing tr	ees.										

Wetland Mitigation Plan prepared by Steve Marino, PWS Tim Miller Associates 10 North Street, Cold Spering, NY 01516

Grading Details

It is proposed to excavate the mitigation area in order to establish pools and flow paths as shown on the grading plan. These areas will be accessed for purposes of the wetland mitigation construction from the proposed road. If suitable, topsoil removed from excavated area will be used within the new wetlands as replacement of organic material for surface preparation.

Soil erosion and sediment control fencing will be installed at the outer and down slope limits of the proposed wetland expansion. The location of the proposed mitigation will be cleared as necessary, but with an eye toward preserving any trees or shrubs adjacent to the work area; some may be removed and stockpiled for replanting after completion of grading.

Where available, the upper one foot of topsoil will be stripped from the site and set aside from other site grading materials. The temporary storage area will be an upland site either removed from wetlands by 100 feet or separated from same by a soil erosion and sediment control fence.

All excavations will be to finished grade elevations as indicated in the mitigation drawings. Per the above, topsoil will be stripped from the site and stockpiled for use in finishing grading. The stockpiled topsoil will be returned to the site to create a planting surface four to six inches deep for the wetland mitigation plantings as described above. Finished soils at the invert of the mitigation sites will be of landscape quality.

The finished surfaces of the planting area will be smooth within specified tolerances in uniform levels or slopes between points where elevations are indicated or between such points and existing grades. The accepted grading tolerance will be a smooth and even surface, free of voids, and within 0.25 feet of the specified elevation. Leaving the surface rough, crating mounds and kettles for a variable microtopography can be beneficial. During the course of earthwork, inspections will be schedule at a frequency to be determined by the engineer/environmental consultant but no less than weekly. Some changes to the grades may be appropriate to establish flow paths and preserve trees. These determinations will be made by the wetland specialist supervising the grading.

Planting Details

Plant choices for the wetland expansion were made according to existing site conditions and locally common species.

All planting will proceed by hand. Materials will be brought to the site in good condition (see below) and then placed in central drop locations. The materials will then be hand-carried to their planting locations and in turn, planted by hand. Only rounded, shallow planting shovels will be used in this effort.

Criteria for selecting plant material will include (1) the plant's ability to withstand the expected light and saturation conditions; (2) its demonstrated survival on this site and other nearby sites; (3) the plant must be native and non-invasive; and (4) whether the plant material is available at nurseries in the same region as the site. See Table 1 for complete plant species list. Seed mix was chosen based on the species' ability to survive in moist areas adjacent to the road with some sun.

Planting will be done in spring or early summer (between April 1 and July 1). Shrubs may also be planted in the late summer to early fall (September 1 to October 30). In all cases, a hole will be dug twice as deep as the root ball. The only shovels allowed are rounded, shallow spades. The hole will then be backfilled with a thin layer (two to four inches) of rich, organic topsoil, the plant placed inside, the hole backfield to the top and then gently tamped down.

Container-grown plant material delivered to the job site will be inspected to assure moist soil/root masses. Any dry and light weight plants will not be accepted. If not planted immediately the container will be stored out of the sun and wind and kept moist (i.e., a means of watering will be provided and watering will occur daily). When removed from the containers, the plants will be the size of the specified container. If in leaf, the plants will appear healthy with no spots, leaf damage, discoloration, insects or fungus. If not in leaf, the buds will be firm and free of damage, discoloration, insects or fungus. Containers will be a minimum of quart size for shrubs and gallon size for trees.

Plants not having an abundance of well developed terminal buds on the leaders and branches will be rejected. The stems and branches of all plants will be turgid and the cambium healthy or the plants rejected.

Seeding within wetland areas should not be completed when there is more than two inches of standing water, or in areas that are likely to be flooded. Seeds should be broadcast by hand or knapsack seeder using the proper seeding rate (13 pounds per acre), and carefully proportioning seed for the entire area. Cover with a light layer of straw mulch following seeding.

Plan Notes

- Prior to commencement of site work, silt fence is to be placed at limit of disturbance.
- . Regrade area and spread topsoil four to six inches deep using existing stockpiles. Final grading is to be generally completed as shown on this plan. Some field adjustment to achieve desired flow paths is acceptable.
- Trees to remain will be identified prior to the commencement of site grading. These trees will be flagged in the field prior to the commencement of any clearing or excavation. Leave smaller existing trees in assumed area of disturbance to the extent practicable. Field adjustments to the grading plan may be necessary in order to ensure minimal impacts to roots of trees to be saved.
- 4. Hay and seed area of wetland expansion with Pinelands Riparian Buffer Mix or equivalent. Companion seed with annual ryegrass as per grower's recommendations.
- 5. Trees and shrubs will be planted within the proposed wetland creation area as specified on the plan and the table above.

Monitoring and Maintenance

At least one pre-construction meeting will occur between the chosen grading and/or planting contractor/subcontractor and the site environmental systems planner prior to beginning construction on site. The construction monitor will have experience in wetland construction and a Bachelor of Science degree in Natural and/or Physical Resources.

Monitoring and maintenance efforts for the mitigation plantings will take place over a five year period following construction. This will include bi-weekly visits for the first growing season, and then twice a year for the next two years, with additional inspections as required depending on conditions. The applicant's environmental monitor will conduct a survey of the site and site conditions will be noted and adjusted as necessary. An annual report will be provided to the Town of Yorktown at the end of the growing season for each of the three years. These reports will include the following information:

- 1. All plant species, along with their estimated relative frequency and percent cover, shall be identified by using plots measuring 10 feet by 10 feet, with at least one representative plot located in each of the habitat types within the mitigation site. For this proposal, there are two plots identified on the plan view planting plan.
- 2. Vegetation cover maps, at a scale of one inch equals 100 or larger, shall be prepared for each growing season. 3. Photographs showing all representative areas of the mitigation site shall be taken at least once each year
- during the period between 1 June and 15 August. 4. Surface water and groundwater elevations in representative areas of the mitigation site shall be recorded
- twice a month during April through September of each year. The location of the monitoring wells are shown on the plan view grading plan

Plantings will meet or exceed and 85 percent survival rate by the end of the second growing season. If this goal is not met, the site will be re-evaluated, and re-grading and/or replanting will be completed as necessary. Invasive species (i.e., Lythrum salicaria and Phragmites australis) will not constitute more than 10 percent of the vegetative community. If this goal is exceeded, measures will be taken to eradicate the invasive species.







										PROJECT # #####		ILTANTS. ALL RIGHTS RESERVE
				Civil Engineers • Land Planners		251-F Underhill Avenue, Yorktown Heights, NY 10598	(914) 962-4488 - Fax· (914) 962-7386		WWW.SITedesignconsultants.com			COPYRIGHT © 2012 BY SITE DESIGN CONSUL
	Engineer:									Joseph C. Kuna, F.E.	NYS LIC. No. 64431	
	Revisions:	No. Date Comments: ##### #####										
	SCALE:	1" = 40'		DRAWN BY:	CS			DATE:	DAIE.	12/07/21		
	PLAN	RED FOR	DED			11LL AVENUE				Wastchester County NV	Westeriustica Country, M.L.	
ļ	SITE	PREPA				332 UNDERE				Town of Yorktown Heights		
Í	eet	_			-	-	-	-	-	-		

Martino Contracting

TOWN OF YORKTOWN PLANNING DEPARTMENT

Albert A. Capellini Community and Cultural Center, 1974 Commerce Street, Yorktown Heights, New York 10598, Phone (914) 962-6565, Fax (914) 962-3986

To:Planning BoardFrom:Planning DepartmentDate:February 24, 2022Subject:Martino Contracting
SBL: 6.17-2-62

The Planning Department has reviewed the current submission and has the following comments:

- 1. The residential development is proposed with access from Lakeview Road. This road was part of the Osceola Heights subdivision and seems to have the same issue of access over a 10 foot reserve strip as the Hansmann Subdivision that was proposed from Osceola Road.
- 2. If a subdivision is also proposed, a subdivision application must also be submitted. The Planning Department can determine fee schedules for both developments once submitted.
- 3. Applicant should confirm whether the Short EAF submitted in 2020 is accurate for the current proposed plan or submit a revision.
- 4. Stormwater and tree removal must be evaluated for this site.
- 5. Lighting and Landscaping plans should be submitted for the commercial development. Proposed elevations should also be submitted when prepared.

Respectfully submitted,

Robyn (Steinberg, AICP, CPESC

Town Planner



Site Design Consultants

Civil Engineers . Land Planners

February 16, 2022

Rich Fon, Chairman Members of the Yorktown Planning Board 1974 Commerce Street Yorktown Heights, NY 10598

Re: Martino Landscaping 286 East Main Street New Tax Data Section 6.17 Block 2 Lot 62

RECEIVED PLANNING DEPARTMENT

FEB 1 6 2022

TOWN OF YORKTOWN

Dear Chairman Fon and Members of the Yorktown Planning Board:

We have addressed the Fire Inspector's memo to the Planning Board dated December 17, 2021 and have enclosed our responses along with the following revised plans. These plans have been modified in accordance with Ed's memo and discussions with the Planning Board and property owner. Enclosed please find the following plan sets:

- Five sets of prints titled "Site/Subdivision Plan Prepared for Martino Landscaping," Sheets 1-4 or 4, dated 8/25/20, last revised 1/14/22.

Please place this project on the Yorktown Planning Board Agenda for February 28, 2022. A digital copy is being submitted. If you have any questions or need additional information, please contact me. Thank you.

Yours Truly Joseph C. Rima, P.E.

Cc: **Engineering Department** Bureau of Fire Prevention **Building Department** Water Department Ed Lachterman Martino Landscaping

JCR / cm / Enc. / sdc 18-34



251-F Underhill Avenue • Yorktown Heights, New York 10598 60 Walnut Grove Road • Ridgefield, Connecticut 06877 (203) 431-9504 Fax (914) 962-7386

(914) 962-4488

Site Design Consultants

Civil Engineers . Land Planners

February 16, 2022

Rich Fon, Chairman Members of the Yorktown Planning Board 1974 Commerce Street Yorktown Heights, NY 10598

RECEIVED

FEB 1 6 2022

TOWN OF YORKTOWN

Re: Martino Landscaping 286 East Main Street New Tax Data Section 6.17 Block 2 Lot 62

Dear Chairman Fon and Members of the Yorktown Planning Board:

We are in receipt of the review memo from Edward Kolisz, Fire Inspector to the Planning Board dated December 17, 2021 and offer the following responses:

For the commercial site:

- 1. The applicant should be aware that fire sprinklers will be required. **Response: It is noted that** fire suppression sprinklers will be required for the commercial building.
- 2. The applicant shall demonstrate that fire apparatus can maneuver the site. Turning radius and grade need to be shown. Response: A plan has been provided showing fire truck turning movements and driveway grades.
- 3. Since the access road is in excess of 150 feet an approved turnaround is required. See Appendix D of the Fire Code Of New York State. Response: As stated in response #2 the ability for a fire truck to turn around is shown.

For the residential building:

- 1. A turnaround of some sort is needed for not only emergency vehicles but all vehicles. Lakeview Rd. is very narrow and difficult for emergency vehicles to operate on. The turnaround needs to meet code. See Appendix D of the Fire Code of New York State for approved turnarounds. **Response: A plan has been provided showing fire truck turning movements and driveway grades.**
- 2. The Bureau would like to know if there is legal access to this site from Lakeview Rd. Response: I think the proper and only way to address this is to extend the Lakeview public right-ofway into the property.

If you have any questions or need additional information, please contact me. Thank you.

Yours Tr Joseph C. Riina, P.E.

Cc: Martino Landscaping JCR / cm / Enc. / sdc 18-34



251-F Underhill Avenue • Yorktown Heights, New York 10598 60 Walnut Grove Road • Ridgefield, Connecticut 06877

(914) 962-4488

(203) 431-9504

Fax (914) 962-7386

RECEIVED PLANNING DEPARTMENT





Town of Yorktown www.yorktownny.org

TOWN OF YORKTOWN

BUREAU OF FIRE PREVENTION

Town Hall, 363 Underhill Avenue, Yorktown Heights, NY 10598 Tel. (914) 962-5722 ext.254

Tel. (914) 962-5722 ext.254

MEMORANDUM

	Edward Kolisz, Fire	Inspector
Fax (914) 962-1731	Email: ekolisz@yorktownny.org	Office hours: Weekdays 8:00-10:00 a.m., 3:00-4:00 p.m.

TO: Planning Board, Town of Yorktown

From: Edward Kolisz, Fire Inspector

Re: Martino Subdivision

Date: December 17, 2021

On Monday December 13, 2021 the Bureau of Fire Prevention met to discuss the proposed Martino Subdivision at 286 East Main St. Jefferson Valley, NY. The Bureau had the following comments:

- For the commercial site:

- 1. The applicant should be aware that fire sprinklers will be required.
- 2. The applicant shall demonstrate that fire apparatus can maneuver the site. Turning radius and grade need to be shown.
- 3. Since the access road is in excess of 150 feet an approved turnaround is required. See Appendix D of the Fire Code Of New York State.

- For the residential building:

- 1. A turnaround of some sort is needed for not only emergency vehicles but all vehicles. Lakeview Rd. is very narrow and difficult for emergency vehicles to operate on. The turnaround needs to meet code. See Appendix D of the Fire Code of New York State for approved turnarounds.
- 2. The Bureau would like to know if there is legal access to this site from Lakeview Rd.

Please contact me with any questions.



ZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW







SITE DATA:

BULK & DIMENSIONAL RE	EGULATIONS:			
COUNTRY COMMERCIAL	REQUIRED	PROPOSED		
MINIMUM LOT AREA:	None	35,942 S.F.		
MAXIMUM ALLOWABLE	For dwelling units: 1/15,000 sq. ft. of lot area = 2 units	None		
DENSITY:	For commercial or mixed use structures: 0.20 F.A.R. F.A.R. = .20 x 35,942.72 F.A.R. = .7,188 S.F.	5,000 S.F./35,942 S.F. = 0.14		
MAXIMUM BUILDING HEIGHT:	Two stories /or 35 feet	1-1/2 stories /or 25 feet		
MAXIMUM BUILDING COVERAGE: (Principal and Accessory Building)	30% of lot area: 35,942 sf x 0.30 = 10,783 sf	13.9% of lot area		
LENGTH OF BUILDING:	No building shall be greater than 100 feet in length. For every 40 feet of building facade facing a public street the building facade shall be modulated such that the building is stepped back or extended forward.	100 Feet		
BUILDING SETBACKS:				
FRONT YARD:	30'	30'		
REAR YARD:	30'	73'		
SIDE YARD:	15' except 20 when adjacent to	15'		

PARKING: 4 SPACES PER 1000 SF OF OFFICE OR RETA	IL + 1 SPACE PER TWO EMPLOYEES OF WAREHOUSE
AIL /OFFICE:	800 S.F. @ 4 SPACES/1000 S.F. = 3.2 SPACES
LESALE, STORAGE, UTILITY OR OTHER COMMERCIAL:	1 SPACE / TWO PERSONS EMPLOYED (34)= 17 SPACES
UIRED PARKING:	21 SPACES
VIDED PARKING:	28 SPACES
ARIANCE REQUIRED:	0 SPACES



		PROJECT # 18-34
		Sile Design Consultants Sile Design Consultants Civil Engineers • Land Planners 251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 • Fax: (914) 962-7386 www.sitedesignconsultants.com
		Engineer: Joseph C. Riina, P.E. NYS Lic. No. 64431
		evisions: lo. Date Comments: 1 12/8/21 Town Comments 2 1/14/22 Update
		SCALE: SCALE: 1"=40' N JR JR JATE: 10-29-18
		EXISTING CONDITION PLAN
Gravel Dr.		SITE/SUBDIVISION PLAN SITE/SUBDIVISION PLAN REPARED FOR MARTINO LANDSCAPING 286 EAST MAIN STREET Fown of Yorktown Vestchester County
	SCALE. 1 –40 -0 SAFE DIG Before You Dig, Drill or Blast! CALL US TOLL FREE 811 or 1-800-962-796 NY Industrial Code Rule 753 requires no less than two working days notice, but not more than ten days notice. Www.digsafelynewyork.com	Sheet of of 4



			PROJECT # 18-34
		Sile Design Consultants Civil Engineers • Land Planners 251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 • Fax: (914) 962-7386	www.sitedesignconsultants.com
		Engineer:	Joseph C. Riina, P.E. NYS Lic. No. 64431
		Revisions: No. Date Comments: 1 12/8/21 Town Comments 2 1/14/22 Update	
		SCALE: SCALE: 1"=40' JR JR	DATE: 10-29-18
		INTEGRATED PLOT PLAN	
AIN Gravel Dr.	0 20 40 80	SITE/SUBDIVISION PLAN PREPARED FOR MARTINO LANDSCAPING 286 FAST MAIN STRFFT	Town of Yorktown Westchester County
	SCALE: T=4U'-U" SAFE DIG Before You Dig, Drill or Blast! CALL US TOLL FREE 811 or 1-800-962-7962 CALL US TOLL FREE 811 or 1-800-962-7962 NY Industrial Code Rule 753 requires no less than two working days notice, but not more than the days notice. www.digsafelynewyork.com	Sheet 3 of	t t

Grishaj Subdivision

TOWN OF YORKTOWN PLANNING DEPARTMENT

Albert A. Capellini Community and Cultural Center, 1974 Commerce Street, Yorktown Heights, New York 10598, Phone (914) 962-6565, Fax (914) 962-3986

To:Planning BoardFrom:Planning DepartmentDate:February 24, 2022Subject:Grishaj Subdivision
SBL: 16.17-2-77

The Planning Department has reviewed the current submission and has the following comments:

- 1. The Board must determine if this subdivision should go forward with the connection to South Shelley Street. A memo from the Fire Inspector has not been received yet on this issue, but can be discussed at the next Bureau of Fire Prevention meeting.
- 2. The wetland delineation and proposed mitigation plan should be reviewed by the Town's environmental consultant.
- 3. The tree removal and tree mitigation should be reviewed by the Town's environmental consultant.

Respectfully submitted,

sere Robyn A. Steinberg, AICP, CPESC

Town Planner

Site Design Consultants

Civil Engineers . Land Planners

RECEIVED

PLANNING DEPARTMENT .

FEB 1 6 2022

TOWN OF YORKTOWN

February 15, 2022

Ms. Robyn Steinberg, AICP Town Planner - Town of Yorktown 1975 Commerce Street Yorktown Heights, NY 10598

Re: Nikolla Grishaj Subdivision of 3319 Stoney Street Scofield Road and Stoney Street SBL 16.17-2-77

Dear Robyn:

Enclosed please find the following items being submitted for distribution and discussion at the February 28, 2022 Planning Board Meeting:

- Five prints of the Mitigation Plan prepared by Steve Marino;
- Five prints of the Plan Sheet titled "Alternate Site Plan Prepared for Nikolla Grishaj," Sheet 1 of 1, dated 5/7/2021;

We are also forwarding you a digital copy of this submission. Please add this project to the agenda for the Planning Board Meeting of February 28th and contact us if you have any questions. Thank you.

Yours 7 Joseph C. Riina, P.E.

Cc: **Town Supervisor Building Department Engineering Department** Water Department Nikolla Grishaj Ed Lachterman

JCR / cm / Enc. / sdc 21-18

251-F Underhill Avenue • Yorktown Heights, New York 10598 60 Walnut Grove Road • Ridgefield, Connecticut 06877 (203) 431-9504 Fax (914) 962-7386

(914) 962-4488

	·	·		
uantity*	Scientific Name	Common Name	Size	
19	Acer rubrum	Red Maple	5' - 6'	
24	Cornus sericea	Redosierdogwood	3' - 4'	
5 22	Lindera benzoin llex verticillata	Spiceousn Winterberry holly	3 - 4 3' - 4'	
21	Vaccinium corymbosum	Highbush blueberry	4' - 5'	
28	Viburnum dentatum	Arrowwood	4' - 5'	
150	Carexstricta	Tussock sedge	2" plug	
100	Carex crinita	Fringed sedge	2" plug	
100	Juncus effusus	Soft rush	2" plug	
50	Osmunda cinnamomea	Cinnamon fern	quart	
	Pinelands Riparian Buffer Mix	or		
pounces	equivalent	a main and in the field fallowing, we want of	finite in and dead plant materials	
li be neid	, but final locations will be det	ermined in the field following removal o	r invasive and dead plant materials	

Criteria for selecting plant material will include (1) the plant's ability to withstand the expected light and saturation conditions; (2) its demonstrated survival on this site and other nearby sites; (3) the plant must be native and non-invasive; and (4) whether the plant material is available at nurseries in the same region as the site. See Table 1 for complete plant species list. Seed mix was chosen based on the species' ability to survive in moist areas adjacent to the road with some sun.

Planting will be done in spring or early summer (between April 1 and July 1). Shrubs may also be planted in the late summer to early fall (September 1 to October 30). In all cases, a hole will be dug twice as deep as the root ball. The only shovels allowed are rounded, shallow spades. The hole will then be backfilled with a thin layer (two to four inches) of rich, organic topsoil, the plant placed inside, the hole backfield to the top and then gently tamped

Container-grown plant material delivered to the job site will be inspected to assure moist soil/root masses. Any dry and light weight plants will not be accepted. If not planted immediately the container will be stored out of the sun and wind and kept moist (i.e., a means of watering will be provided and watering will occur daily). When removed from the containers, the plants will be the size of the specified container. If in leaf, the plants will appear healthy with no spots, leaf damage, discoloration, insects or fungus. If not in leaf, the buds will be firm and free of damage, discoloration, insects or fungus. Containers will be a minimum of quart size for shrubs and gallon size for trees.

Plants not having an abundance of well developed terminal buds on the leaders and branches will be rejected. The stems and branches of all plants will be turgid and the cambium healthy or the plants rejected.

Seeding within wetland areas should not be completed when there is more than two inches of standing water, or in areas that are likely to be flooded. Seeds should be broadcast by hand or knapsack seeder using the proper seeding rate (13 pounds per acre), and carefully proportioning seed for the entire area. Cover with a light layer of straw mulch following seeding.

Plan Notes

- achieve desired flow paths is acceptable.
- impacts to roots of trees to be saved.
- on the plan and the table above.

Monitoring and Maintenance

At least one pre-construction meeting will occur between the chosen grading and/or planting contractor/subcontractor and the site environmental systems planner prior to beginning construction on site. The construction monitor will have experience in wetland construction and a Bachelor of Science degree in Natural and/or Physical Resources.

Monitoring and maintenance efforts for the mitigation plantings will take place over a five year period following construction. This will include bi-weekly visits for the first growing season, and then twice a year for the next two years, with additional inspections as required depending on conditions. The applicant's environmental monitor will conduct a survey of the site and site conditions will be noted and adjusted as necessary. An annual report will be provided to the Town of Yorktown at the end of the growing season for each of the three years. These reports will include the following information:

- are two plots identified on the plan view planting plan.
- each growing season.
- location of the monitoring wells are shown on the plan view grading plan

Plantings will meet or exceed and 85 percent survival rate by the end of the second growing season. If this goal is not met, the site will be re-evaluated, and re-grading and/or replanting will be completed as necessary. Invasive species (i.e., Lythrum salicaria and Phragmites australis) will not constitute more than 10 percent of the vegetative community. If this goal is exceeded, measures will be taken to eradicate the invasive species.

Wetland Mitigation Pla

It is proposed to excavate the mitigation area in order to establish pools and flow paths as shown on the grading plan. These areas will be accessed for purposes of the wetland mitigation construction from the proposed road. If suitable, topsoil removed from excavated area will be used within the new wetlands as replacement of organic material for surface

Soil erosion and sediment control fencing will be installed at the outer and down slope limits of the proposed wetland expansion. The location of the proposed mitigation will be cleared as necessary, but with an eye toward preserving any trees or shrubs adjacent to the work area; some may be removed and stockpiled for replanting after completion of grading.

Where available, the upper one foot of topsoil will be stripped from the site and set aside from other site grading materials. The temporary storage area will be an upland site either removed from wetlands by 100 feet or separated from same by a soil erosion and sediment

All excavations will be to finished grade elevations as indicated in the mitigation drawings. Per the above, topsoil will be stripped from the site and stockpiled for use in finishing grading. The stockpiled topsoil will be returned to the site to create a planting surface four to six inches deep for the wetland mitigation plantings as described above. Finished soils at the invert of the mitigation sites will be of landscape quality.

The finished surfaces of the planting area will be smooth within specified tolerances in uniform levels or slopes between points where elevations are indicated or between such points and existing grades. The accepted grading tolerance will be a smooth and even surface, free of voids, and within 0.25 feet of the specified elevation. Leaving the surface rough, crating mounds and kettles for a variable microtopography can be beneficial. During the course of earthwork, inspections will be schedule at a frequency to be determined by the engineer/environmental consultant but no less than weekly. Some changes to the grades may be appropriate to establish flow paths and preserve trees. These determinations will be made by the wetland specialist supervising the grading.

Plant choices for the wetland expansion were made according to existing site conditions

All planting will proceed by hand. Materials will be brought to the site in good condition (see below) and then placed in central drop locations. The materials will then be hand-carried to their planting locations and in turn, planted by hand. Only rounded, shallow planting

Prior to commencement of site work, silt fence is to be placed at limit of disturbance. Regrade area and spread topsoil four to six inches deep using existing stockpiles. Final grading is to be generally completed as shown on this plan. Some field adjustment to Trees to remain will be identified prior to the commencement of site grading. These trees

will be flagged in the field prior to the commencement of any clearing or excavation. Leave smaller existing trees in assumed area of disturbance to the extent practicable. Field adjustments to the grading plan may be necessary in order to ensure minimal Hay and seed area of wetland expansion with Pinelands Riparian Buffer Mix or equivalent. Companion seed with annual ryegrass as per grower's recommendations. Trees and shrubs will be planted within the proposed wetland creation area as specified

All plant species, along with their estimated relative frequency and percent cover, shall be identified by using plots measuring 10 feet by 10 feet, with at least one representative plot located in each of the habitat types within the mitigation site. For this proposal, there Vegetation cover maps, at a scale of one inch equals 100 or larger, shall be prepared for

Photographs showing all representative areas of the mitigation site shall be taken at least once each year during the period between 1 June and 15 August. Surface water and groundwater elevations in representative areas of the mitigation site shall be recorded twice a month during April through September of each year. The

<u>3</u>	<u>LOT 4</u>	<u>LOT 5</u>	<u>LOT 6</u>	<u>LOT 7</u>	<u>LOT 8</u>	<u>LOT 9</u>	<u>LOT 10</u>	VARIANCE REQUIRED
SF.	41,363 SF.	32,579 SF.	21,702 SF.	20,805 SF.	21,000 SF.	20,527 SF.	20,479 SF.	NONE
Т.	129.28 FT.	149.4 FT.	113.68 FT.	104.76 FT.	105.02 FT.	198.24 FT.	188.53 FT.	NONE
FT.	188.69 FT.	188.69 FT.	178.92 FT.	178.92 FT.	198.24 FT.	104.99 FT.	103.34 FT.	NONE
Τ.	285.21 FT.	239.16 FT.	81.77 FT.	113.87 FT.	105.02 FT.	293.15 FT.	297.6 FT.	NONE
т	105 4 FT	74 9 FT	48.8 FT	75 9 FT	69 5 FT	46.2 FT	48 FT	NONE
т.	55.8 FT	46.0 FT	40.011. 88.8 FT	96.4 FT	101.2 FT	31.3 FT	31 5 FT	NONE
т.	36.0 FT.	39.4 FT.	22.4 FT.	16.3 FT.	15.1 FT.	58.8 FT.	55.2 FT.	NONE
Τ.	76.4 FT.	94.6 FT.	50.6 FT.	41 FT.	40.7 FT.	131.3 FT.	72 FT.	NONE
F EA	4.5% OF LOT AREA	5.2% OF LOT AREA	7.7% OF LOT AREA	8.0% OF LOT AREA	7.9% OF LOT AREA	8.1% OF LOT AREA	8.1% OF LOT AREA	NONE
ΞT	35 FEET	NONE						
2	2 1/2	2 1/2	2 1/2	2 1/2	2 1/2	2 1/2	2 1/2	NONE
ΞT	35 FEET	NONE						
2	2 1/2	2 1/2	2 1/2	2 1/2	2 1/2	2 1/2	2 1/2	NONE

DISTANCE ALONG BASELINE (FT)

PROPOSED ROAD VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

PROJECT # 21-18
Sile Design Consultants Civil Engineers • Land Planners Civil Engineers • Land Planners 251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 - Fax: (914) 962-7386 www.sitedesignconsultants.com
ScALE: NTS NTS NTS NTS NAWN BY: TK DATE: DATE: S/7/21 DATE: S/7/21
ROADWAY PROFILES
SITE PLAN PREPARED FOR NIKOLLA GRISHAJ 3319 STONY STREET Town of Yorktown Westchester County, New York
Sheet 5 of 17

IOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAV

DISTANCE ALONG BASELINE (FT)

CB-1 TO TREATMENT VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50

NOTE: 1. <u>THIS IS NOT A SURVEY.</u> ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY NAME OF SURVEYOR, DATED XX/XX/XX, LAST REVISED XX/XX/XX. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

DTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

DISTANCE ALONG BASELINE (FT)

DMH-2 TO DETENTION VERT. SCALE: 1" = 5

HORIZ. SCALE: 1" = 50

DISTANCE ALONG BASELINE (FT)

WATERMAIN VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50

NOTE: 1. <u>THIS IS NOT A SURVEY.</u> ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY NAME OF SURVEYOR, DATED XX/XX/XX, LAST REVISED XX/XX/XX. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

			PROJECT # 21-18
Sile Design Consultants	Civil Engineers • Land Planners	221-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 - Fax: (914) 962-7386 www sitedesignconsultants com	
Engineer: Engineer: Engineer: Engineer: Engineer: Engineer:	+ HINA RUNA SOC + LINA + LINA + LINA + LINA	The no bank of the second	Joseph C. Rina, P.E. NYS Lic. No. 64431
Revisions:No.Date110/7/21Plan Revisions			
SCALE: NTS	DRAWN BY: TK	DATE:	5/7/21
	WATERMAIN	FKOFILES	
SITE PLAN PREPARED FOR	NIKOLLA GRISHAJ	3319 STONY STREET	Town of Yorktown Westchester County, New York
Sheet	of	17	

VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50 VERT. SCALE: 1" = 5HORIZ. SCALE: 1" = 50

NOTE: 1. <u>THIS IS NOT A SURVEY</u>. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY NAME OF SURVEYOR, DATED XX/XX/XX, LAST REVISED XX/XX/XX. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

IOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

DISTANCE ALONG BASELINE (FT)

SANITARY SEWER VERT. SCALE: 1" = 5 HORIZ. SCALE: 1" = 50

PROJECT # 21-18	
Sile Design Consultants Civil Engineers • Land Planners 251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 • Fax: (914) 962-7386 www.sitedesignconsultants.com	
Engineer: Engineer: Construction Constructio	
Revisions: No. Date 1 10/7/21 Plan Revisions	
SCALE: NTS DRAWN BY: TK DATE: 5/7/21	
UTILITY PROFILES	
SITE PLAN PREPARED FOR NIKOLLA GRISHAJ 3319 STONY STREET Town of Yorktown Westchester County, New York	
Sheet 9 of 17	

GENERAL NOTES:

- 1. THE ENGINEER WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION, SUBSEQUENTLY, HE IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION
- PRACTICES, PROCEDURES, AND RESULTS THEREFROM. THE ENGINEER SHALL NOT BE HELD RESPONSIBLE OR HELD ACCOUNTABLE FOR THE INTEGRITY OF ANY STRUCTURES CONSTRUCTED OR UNDER CONSTRUCTION PRIOR TO THE APPROVAL OF THE PLANS.
- . THE TOWN ENGINEER'S OFFICE AND WATER DISTRICT OFFICE IS TO BE NOTIFIED 24 HOURS BEFORE COMMENCING SITE CONSTRUCTION OR WATER MAIN CONNECTION.
- ALL WORK IS TO BE IN ACCORDANCE WITH THE TOWN CODE OF PRACTICE AND SPECIFICATIONS.
- ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER WHOSE
- SEALAPPEARS ON THESE DRAWINGS. ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY
- SCALED DIMENSIONS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL IN A "CODE 53" PRIOR TO
- CONSTRUCTION FOR UNDERGROUND UTILITY LOCATIONS. 9. SUBSTRUCTURES AND THEIR ENCROACHMENTS BELOW GRADE, IF ANY, ARE NOT SHOWN. . ANY PROPOSED ELECTRIC AND/OR TELEPHONE SERVICE LINES ARE TO BE PLACED
- UNDERGROUND 10. THE DESIGN ENGINEER DISCLAIMS ANY LIABILITY FOR DAMAGE OR LOSS INCURRED DURING OR AFTER CONSTRUCTION.
- 11. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.

CONTRACTOR RESPONSIBILITIES:

- 1. ALL WORK ON THE PROJECT SHALL BE PERFORMED IN A WORKMAN LIKE MANNER AND SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE INDUSTRY. THE OWNER WILL BE THE SOLE JUDGE OF THE ACCEPTABILITY OF THE WORK. MATERIALS AND WORK DEEMED UNACCEPTABLE WILL BE REMOVED AND REDONE AT THE SOLE COST AND RESPONSIBILITY OF THE CONTRACTOR
- THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGES DUE TO HIS ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEE, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY THE WORK UNDER A SEPARATE CONTRACT WITH THE CONTRACTOR.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROPERLY SHORE EXISTING UTILITIES IF REQUIRED BY CONSTRUCTION.
- . IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE THE BUILDING INSPECTOR IN ADVANCE OF HIS WORK OR AS THE INSPECTOR DEEMS APPROPRIATE. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE
- CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.
- ALL CHANGES MADE TO THIS PLAN SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY UNAUTHORIZED ALTERATION OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THIS CONTRACT.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTRACT WITH THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL VERIFY ALL SUBSTRUCTURES ENCOUNTERED DURING CONSTRUCTION. THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER
- THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.

GENERAL CONSTRUCTION NOTES

- BENCH MARKS USING U.S.G.S. DATUM SHALL BE OF SUCH ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS.
- CONSTRUCTION ACTIVITY SHALL BE LIMITED FROM 8:00 A.M. TO 6 P.M., AND NO CONSTRUCTION ACTIVITY SHALL OCCUR ON SUNDAYS OR LEGAL NEW YORK STATE HOLIDAYS. WHERE BLASTING IS NECESSARY, IT SHALL OCCUR FROM MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 A.M. AND 6:00 P.M. NO BLASTING SHALL OCCUR ON HOLIDAYS, SATURDAY OR SUNDAY. ALL BLASTING SHALL ALSO BE COMPLETED IN ACCORDANCE WITH THE TOWN OF YORKTOWN AND NEW YORK STATE BLASTING ORDINANCES.
- ANY SOIL THAT IS UNSUITABLE FOR DEVELOPMENT OF BUILDINGS OR ROADWAYS SHALL BE REMOVED FROM AREAS TO BE DEVELOPED AND SHALL BE DISPOSED OF WITHIN THE SITE IN NEW EMBANKMENTS WHERE STRUCTURAL LOADING, I.E. A BUILDING OR ROADWAY, WILL NOT TAKE PLACE. WHEN CONSTRUCTION IS PROPOSED TO OCCUR IN SPECIFIC AREAS WHERE SOILS ARE OF QUESTIONABLE SUITABILITY, THE APPLICANT SHALL PROVIDE SOILS ENGINEERING REPORTS AS REQUIRED BY THE PLANNING BOARD ENGINEER, PRIOR TO THE CONSTRUCTION OF ROADWAYS AND, AS REQUIRED BY THE BUILDING INSPECTOR, PRIOR TO THE ISSUANCE OF A BUILDING PERMIT
- NO TOPSOIL SHALL BE REMOVED FROM THE SITE. ROCK CUT STABILITY IS TO BE FIELD VERIFIED BY GEOTECHNICAL ENGINEER AND
- SHALL BE MODIFIED IF REQUIRED. NO CRUSHING/PROCESSING IS PERMITTED ON THE SITE WITHOUT PRIOR APPROVAL BY THE TOWN OF YORKTOWN PLANNING BOARD.

GENERAL STORM DRAINAGE & UTILITY NOTES

- ALL UTILITIES, INCLUDING ELECTRIC LINES, TELEPHONE, WATER, SANITARY SEWER LINES, AND STORM SEWER LINES SHALL BE LOCATED UNDERGROUND AND SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWN OF YORKTOWN AND THE UTILITY COMPANIES HAVING JURISDICTION.
- LOCATION OF GAS AND WATER VALVES, ELECTRIC AND TELEPHONE POLES ARE TO BE DETERMINED BY PROPER AUTHORITIES AND APPROVED, AS TO LOCATION, BY THE TOWN ENGINEER.
- EACH BUILDING CONSTRUCTED HEREON SHALL BE OF SUCH AN ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. IN THE EVENT THAT THIS IS NOT FEASIBLE, THE CONTRACTOR SHALL INSTALL TYPICAL YARD DRAINS AS REQUIRED AND CONNECT THEM TO THE STORM DRAINAGE SYSTEM OR AS DIRECTED BY THE PROJECT FNGINFFR
- ROOF LEADERS AND FOOTING DRAINS SHALL EMPTY INTO THE STORM DRAINAGE SYSTEM OR DISCHARGE DIRECTLY TO STORMWATER MANAGEMENT SYSTEMS IF GRADES PERMIT, AND CONNECTION TO THE STORM SYSTEM IS NOT FEASIBLE, FOOTING DRAINS ONLY MAY DISCHARGE TO DAYLIGHT AT THE REAR OF BUILDINGS. FOOTING DRAINS SHALL EXTEND A MINIMUM OF 30 FT. FROM THE REAR FACE OF THE BUILDING WHEN POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE DISCHARGE OF GROUND WATER OR STORM WATER,
- EITHER BY GRAVITY OR BY PUMPING, BE DISCHARGED TO ANY SANITARY SEWER SYSTEM. ANY REVISIONS AND/OR ADDITIONS TO THE ROAD STORM DRAINAGE SYSTEMS CURRENTLY SHOWN ON THE PLANS WHICH ARE DEEMED NECESSARY DURING CONSTRUCTION MUST BE MADE BY THE CONTRACTOR AS REQUIRED BY THE TOWN AND
- SHALL BE SHOWN ON THE AS-BUILT DRAWINGS. STORM DRAIN PIPING TO BE HIGH DENSITY POLYETHYLENE AS SHOWN ON THE
- CONSTRUCTION DRAWINGS. MINIMUM COVER TO BE 2' UNLESS OTHERWISE NOTED. INTERCEPTOR DRAINS ARE TO BE INSTALLED WHERE REQUIRED BY THE TOWN OR
- PROJECT ENGINEER DURING ROAD CONSTRUCTION ALL EXISTING UNDERGROUND DRAINS ENCOUNTERED DURING CONSTRUCTION OF PROPOSED ROADS ARE TO BE CONNECTED TO PROPOSED DRAINAGE IMPROVEMENTS.
- CONNECTIONS TO BE APPROVED BY THE TOWN ENGINEER. PRIOR TO FINAL APPROVAL AND OPERATION OF DRAINAGE SYSTEM, CONTRACTOR SHALL CLEAR ALL ACCUMULATED SEDIMENT AND/OR DEBRIS FROM DRAINAGE STRUCTURES. MANHOLES, CULVERTS, OUTLETS AND DRAIN INLETS. ENGINEER SHALL BE NOTIFIED FOR FINAL INSPECTION.
- 10. ALL STRUCTURES SHALL BE SET ONE INCH BELOW PAVEMENT. 11. STREET OPENING PERMIT FROM THE TOWN OF YORKTOWN D.P.W. MAY BE REQUIRED FOR INSTALLATIONS IN PUBLIC ROADS.

WATERMAIN NOTES

- **DISTRIBUTION SYSTEM WATERMAIN** A. GENERAL
- THE CONTRACTOR SHALL PERFORM THE NECESSARY EXCAVATION, BACKFILLING, CLEARING, GRUBBING, SHEETING, SHORING, DO ALL SHAPING OF TRENCHES, PUMPING AND BAILING, LAYING AND JOINING OF ALL PIPES, PROTECT AND SUPPORT EXISTING STRUCTURES AND REPAIR THEM, IF DAMAGED, AND ALL ELSE NECESSARY TO COMPLETE THE WORK.

THE CONTRACTOR SHALL FURNISH ALL MATERIALS, EQUIPMENT, LABOR, AND TOOLS NECESSARY TO COMPLETE THE WORK IN A SAFE, NEAT, AND WORKMANLIKE MANNER.

B. SITE AND ACCESS CLEARING (WITHIN EASEMENTS) THE CONTRACTOR SHALL CONFINE ALL CLEARING OPERATIONS TO WITHIN THE IMMEDIATE

AREAS THAT ARE ESSENTIAL FOR CONSTRUCTION OF THE WORK.

C. STOCKPILING OF SUITABLE BACKFILL MATERIAL

THE CONTRACTOR SHALL BE PREPARED WHEN EXCAVATING THE TRENCH TO SEPARATE SUITABLE BACKFILL MATERIAL FROM UNSUITABLE MATERIAL FOR USE AS BACKFILL ADJACENT TO THE PIPE.

D. PROTECTION OF EXISTING STRUCTURES AND UTILITIES

SPECIAL PRECAUTIONS SHALL BE TAKEN BY THE CONTRACTOR TO PROTECT OVERHEAD POWER LINES, WATERMAINS, GAS MAINS, ELECTRIC AND TELEPHONE CONDUITS, STORM AND SANITARY SEWERS, CULVERTS, BUILDINGS AND OTHER EXISTING STRUCTURES IN AND NEAR THE EXCAVATION. IN ALL CASES, WHETHER UNDERGROUND STRUCTURES HAVE OR HAVE NOT BEEN DELINEATED, THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE ACCEPTS NO RESPONSIBILITY FOR THEIR LOCATION. 'UNDERGROUND UTILITIES" LOCATES EXISTING UNDERGROUND UTILITIES FREE OF CHARGE. THE PHONE NUMBER IS 1-800-245-2828.

GUTTERS, SEWERS, DRAINS AND DITCHES SHALL BE KEPT OPEN AT ALL TIMES FOR SURFACE DRAINAGE. NO DAMMING OR PONDING OF WATER IN GUTTERS OR OTHER WATERWAYS WILL BE PERMITTED EXCEPT WHERE STREAM CROSSINGS ARE NECESSARY AND THEN ONLY TO AN EXTENT WHICH THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHALL CONSIDER NECESSARY. THE CONTRACTOR SHALL NOT DIRECT ANY FLOW OF WATER ACROSS OR OVER PAVEMENTS EXCEPT THROUGH APPROVED PIPES OR PROPERLY CONSTRUCTED TROUGHS OF SUCH SIZES AND LENGTHS AS MAY BE REQUIRED, AND PLACE THE SAME AS DIRECTED. THE GRADING IN THE VICINITY OF TRENCHES SHALL BE CONTROLLED SO THAT THE GROUND SURFACE IS PROPERLY PITCHED TO PREVENT WATER RUNNING IN THE TRENCHING. THE CONTRACTOR SHALL NOT COMMENCE OPERATIONS INVOLVING ANY PUBLIC UTILITY BEFORE HAVING GIVEN WRITTEN NOTICE TO THE COMPANY OR OWNER, OR ITS AGENTS, AND SHALL COOPERATE WITH THE COMPANY'S OR OWNER'S FORCES IN PROTECTING AND PREVENTING DAMAGE TO THE PROPERTY.

THE CONTRACTOR WILL, AT HIS OWN EXPENSE, BE RESPONSIBLE FOR DIRECT OR INDIRECT DAMAGE THAT MAY BE DONE TO ANY UTILITY OR STRUCTURE IN THE PROSECUTION OF HIS WORK. THE LIABILITY OF THE CONTRACTOR IS ABSOLUTE AND IS NOT DEPENDENT UPON ANY QUESTIONS OF NEGLIGENCE ON HIS PART OR ON THE PART OF HIS AGENT, OR EMPLOYEES. AND THE NEGLECT OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE TO DIRECT THE CONTRACTOR TO TAKE ANY PARTICULAR PRECAUTION OR TO REFRAIN FROM DOING SUCH DAMAGE.

SHOULD THE POSITION OF ANY PIPE, CONDUIT, POLE OR OTHER STRUCTURES, ABOVE OR BELOW THE GROUND, BE SUCH AS TO REQUIRE ITS REMOVAL, REALIGNMENT, OR CHANGE DUE TO WORK TO BE DONE, REALIGNMENT OR CHANGE WILL BE DONE BY OR UNDER SUPERVISION OF THE OWNER OF THE OBSTRUCTIONS. THE CONTRACTOR SHALL UNCOVER AND SUSTAIN THE STRUCTURES, AFTER SUCH REALIGNMENT OR CHANGE.

THE CONTACTOR SHALL NOT INTERFERE WITH ANY PERSONS, OR WITH THE OWNER IN PROTECTING, REMOVING, CHANGING OR REPLACING THEIR PIPES, CONDUITS, POLES OR OTHER STRUCTURES; BUT HE SHALL SUFFER SAID PERSONS OR THE OWNER TO TAKE ALL SUCH MEASURES AS THEY MAY DEEM NECESSARY OR ADVISABLE FOR THE PURPOSE AFORESAID, AND THE CONTRACTOR SHALL THEREBY BE IN NO WAY RELIEVED OF ANY OF HIS RESPONSIBILITIES.

THE CONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS WITH THE OWNER OF THE RESPECTIVE UTILITY PRIOR TO RELOCATION OR INTERRUPTION OF SERVICE. ALL WORK NECESSARY FOR THE RELOCATION SHALL BE PERFORMED BY THE CONTRACTOR, OR BY THE OWNER AT THE OWNER'S OPTION, AND TO THE SATISFACTION OF THE OWNER. WHERE SERVICE IS INTERRUPTED. THE CONTRACTOR SHALL COOPERATE IN RESTORING SERVICE PROMPTLY. ALL CHARGES FOR DAMAGES DONE TO UTILITIES SHALL BE PAID BY THE CONTRACTOR

E. CONSTRUCTION OF ROAD RIGHT-OF-WAY

CONSTRUCTION IN THE ROAD RIGHT-OF-WAY SHALL AT ALL TIMES BE PERFORMED WITH MINIMUM DISTURBANCE TO TRAFFIC WITH SUFFICIENT BARRICADES AND DIRECTION. DETOURS CAN BE INSTITUTED WITH APPROVAL OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE, OR STATE, COUNTY, OR LOCAL AUTHORITIES. PAVEMENT SHALL BE CUT PRIOR TO REMOVAL. HOLES AND SETTLEMENTS IN THE TRENCHES SHALL BE IMMEDIATELY FILLED TO THE ORIGINAL GRADE ELEVATION WITH THE SPECIFIED MATERIALS.

F. EXCAVATION AND PREPARATION OF TRENCH

THE CONTRACTOR SHALL PROCEED WITH CAUTION IN THE EXCAVATION AND PREPARATION OF THE TRENCH SO THAT THE EXACT LOCATION OF UNDERGROUND STRUCTURES. BOTH KNOWN AND UNKNOWN, MAY BE DETERMINED. THE TRENCH SHALL BE EXCAVATED SO THAT THE PIPE CAN BE LAID TO THE ALIGNMENT AND DEPTH REQUIRED. MINIMUM DEPTH OF COVER FROM SURFACE OF GROUND TO TOP OF PIPE BARREL SHALL BE FOUR FEET (4'). NO TRENCH SHALL BE EXCAVATED MORE THAN FIVE HUNDRED LINEAL FEET (500 LF) IN ADVANCE OF PIPE LAYING UNLESS AUTHORIZED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE TRENCH SHALL BE SO BRACED AND DRAINED THAT THE WORKMEN MAY WORK THEREIN SAFELY AND EFFICIENTLY. IT IS ESSENTIAL THAT THE DISCHARGE OF THE TRENCH DEWATERING PUMPS BE CONDUCTED TO NATURAL DRAINAGE CHANNELS OR DRAINS, AS IN ACCORDANCE WITH OSHA REQUIREMENTS.

THE WIDTH OF THE TRENCH SHALL BE OF ADEQUATE SIZE TO PERMIT THE PIPE TO BE LAID AND JOINTED PROPERLY, BUT SHALL NOT EXCEED THE SUM OF TWENTY-FOUR INCHES(24") PLUS THE PIPE OUTSIDE DIAMETER, AND THE BACKFILL TO BE PLACED AND COMPACTED AS SPECIFIED.

LEDGE ROCK, BOULDERS AND LARGE STONES SHALL BE REMOVED TO PROVIDE A CLEARANCE OF AT LEAST SIX INCHES (6") BELOW AND ON EACH SIDE OF ALL PIPES AND FITTINGS.

THE TRENCH SHALL BE EXCAVATED TO THE DEPTH REQUIRED SO AS TO PROVIDE A UNIFORM AND CONTINUOUS BEARING AND SUPPORT FOR THE PIPE ON SOLID AND UNDISTURBED GROUND AT EVERY POINT. WHERE THE BOTTOM OF THE TRENCH AT A SUBGRADE IS FOUND TO BE UNSTABLE, OR TO INCLUDE ASHES, CINDERS, ALL TYPES OF REFUSE, VEGETABLE OR OTHER ORGANIC MATERIAL OR LARGE PICES OF FRAGMENTS OR INORGANIC MATERIAL WHICH IN THE JUDGEMENT OF THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHOULD BE REMOVED, THE CONTRACTOR SHALL EXCAVATE AND REMOVE SUCH UNSUITABLE MATERIAL TO THE WIDTH AND DEPTH ORDERED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE.

ANY PART OF THE BOTTOM OF THE TRENCH EXCAVATED BELOW THE SPECIFIED GRADE SHALL BE CORRECTED WITH APPROVED BEDDING MATERIAL, SUCH AS THOROUGHLY COMPACTED CRUSHED STONE, GRAVEL, OR CONCRETE AS DIRECTED BY THE TOWN ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE FINISHED SUBGRADE SHALL BE PREPARED ACCURATELY BY MEANS OF HAND TOOLS.

GENERAL WATER MAIN NOTES:

ALL PROPOSED WATERMAIN MATERIALS, CONSTRUCTION AND INSTALLATION SHALL CONFORM TO ALL APPLICABLE RULES AND REGULATIONS OF THE TOWN OF YORKTOWN WATER DEPARTMENT AND THE WESTCHESTER COUNTY HEALTH DEPARTMENT STANDARDS AND SPECIFICATIONS. CONSTRUCTION MUST BE UNDER THE SUPERVISION OF A LICENSED AND REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF NEW YORK WHO SHALL FURNISH A CERTIFICATE OF CONSTRUCTION COMPLIANCE AND TWO (2) SETS OF AS-BUILT PLANS AFTER THE COMPLETION OF THE PROJECT.

THE RECORDS OF THE TOWN OF YORKTOWN INDICATE THAT THERE IS ADEQUATE WATER PRESSURE AND CAPACITY AS REQURIED TO SERVE THIS PROJECT 3. ALL BACKFLOW PREVENTION DEVICES ASSOCIATED WITH THE FIRE AND DOMESTIC SERVICES

FOR EACH OF THE PROPOSED OFFICE SPACES IN THE TYPE "B" UNITS SHALL BE LOCATED INTERNAL TO THE BUILDING AND SHALL REQUIRE SEPARATE APPROVAL BY THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH.

4. ALL FIRE AND DOMESTIC SERVICE CONNECTIONS FROM THE PROPOSED WATER MAIN SHALL BE INSTALLED WITH WET TAPS AFTER THE CONTRACTOR HAS INSTALLED THE MAIN AND IT HAS BEEN APPROVED BY THE TOWN OF YORKTOWN WATER DEPARTMENT AND THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH.

THE CONTRACTOR IS ADVISED THAT BEFORE HE CONNECTS TO THE EXISTING WATER SYSTEM, HE MUST ADVISE AND COORDINATE HIS OPERATIONS WITH THE TOWN OF YORKTOWN WATER DEPARTMENT'S SUPERINTENDENT. MEANS AND METHODS USED TO CONNECT TO THE EXISTING SERVICE SHALL BE APPROVED BY THE TOWN AND SHALL INCLUDE BUT NOT BE LIMITED TO WET TAPS OR OTHERWISE.

THE CONTRACTOR IS TO MAINTAIN CONSTANT FLOW AND PRESSURE IN ALL WATER MAINS AT ALL TIMES. IF THE NEED SHOULD ARISE THAT WATER SERVICE IS TO BE INTERRUPTED FOR A SHORT PERIOD, IT MUST BE COORDINATED WITH AND APPROVED BY THE ENGINEER AND THE TOWN OF YORKTOWN SUPERINTENDENT OF WATER.

WATER MAINS CROSSING HOUSE SEWERS, STORM SEWERS OR SANITARY SEWERS SHALL BE LAID TO PROVIDE A VERTICAL SEPARATION OF A MINIMUM OF 18" BETWEEN THE BOTTOM OF WATER MAIN AND TOP OF SEWER.

WATER MAINS PASSING UNDER HOUSE SEWERS, IN ADDITION, SHALL BE PROTECTED BY 8 PROVIDING A VERTICAL SEPARATION OF 18" MINIMUM FROM THE BOTTOM OF THE SEWER TO THE TOP OF THE WATER MAIN AND ADEQUATE STRUCTURAL SUPPORT FOR THE SEWER TO PREVENT EXCESSIVE DEFLECTION OF THE JOINTS AND THE SEWER SETTLING AND BREAKING THE WATER MAIN. IN ADDITION THE LENGTH OF WATER PIPE IS TO BE CENTERED AT THE POINT OF CROSSING SO THAT THE JOINTS WILL BE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER. NO WATER MAIN SHALL PASS THROUGH OR COME IN CONTACT WITH ANY PART OF A

SEWER OR SEWER MANHOLE. THE COVER OVER THE TOP OF THE WATER MAIN SHALL BE A MINIMUM OF 4 FEET TO A MAXIMUM OF 5.5 FT.

10. WATER MAINS SHALL BE CLASS 52 DUCTILE IRON PIPES (DIP) TYTON JOINT TYPE AND FITTINGS SHALL BE FACTORY CEMENT LINED CLASS 52. ALL FITTINGS SHALL HAVE MECHANICAL JOINTS AND SHALL BE PRESSURE RATED AT 250 PSI. ALL NECESSARY JOINT MATERIALS SHALL BE FURNISHED. WATER MAINS SHALL BE INSTALLED IN ACCORDANCE WITH AWWA STANDARDS, LATEST REVISION.

11. ALL GATE VALVES SHALL BE MUELLER RESILIENT WEDGE (TURN LEFT OPEN) TYPE AND SHALL MEET AWWA STANDARDS, LATEST REVISION.

12. ALL SERVICE CONNECTIONS AND SMALL DIAMETER EXTENSIONS SHALL CONFORM TO AWWA C-151.

13. RETAINER GLANDS AND CONCRETE THRUST BLOCKS OR RODS SHALL BE USED AT ALL LOCATIONS WHERE RESTRAINTS EXIST

14. INSTALLATION AND TESTING OF THE WATER MAIN SHALL BE INSPECTED BY THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH. THE CONTRACTOR SHALL PROVIDE THE HEALTH DEPARTMENT A MINIMUM 48 HOURS NOTICE PRIOR TO ANY PRESSURE/LEAKAGE TESTS AND/OR DISINFECTION AND BACTERIOLOGICAL TESTS PERFORMED ON THE PROPOSED WATER MAIN. THE RESULTS OF THE ABOVE TESTS MUST BE ACCEPTED BY THE WCHD PRIOR TO USE OF THE MAIN.

15. ASBUILT DRAWINGS SHALL SHOW DIMENSIONS BETWEEN ALL VALVE TURNING NUTS AND FINISH GRADE.

16. INSTALLATION, DISINFECTION AND TESTING TO BE WITNESSED AND CERTIFIED BY A LICENSED PROFESSIONAL ENGINEER OR TOWN OF YORKTOWN ENGINEER.

17. ALL HYDRANTS AND VALVES SHALL BE AS MANUFACTURED BY THE MUELLER COMPANY. 18. THE FINAL LOCATIONS OF FIRE HYDRANTS AND SIAMESE CONNECTIONS SHALL BE DETERMINED BY AND COORDINATED WITH THE TOWN OF YORKTOWN FIRE DEPARTMENT.

19. IF, DURING CONSTRUCTION, IT IS FOUND THAT THE REQUIRED SEPARATION OF WATER MAINS, SANITARY SEWERS, STORM SEWERS, AND BUILDING SEWERS CANNOT BE MET, THE DEVELOPER OR HIS AUTHORIZED REPRESENTATIVE SHALL CONTACT THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH. APPROVAL BY THE WCHD IS REQUIRED PRIOR TO ANY FIELD CHANGES THAT WILL AFFECT MINIMUM WATER/SEWER SEPARATION DISTANCES.

20. ALL TYPES OF INSTALLED PIPE SHALL BE PRESSURE TESTED AND LEAKAGE TESTED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-600.

21. ALL NEW, CLEANED OR REPAIRED WATER MAINS SHALL BE DISINFECTED AND BACTERIOLOGICAL TESTING PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-651-05 (EXCEPT FOR SECTION 4.4.2 WHICH IS NOT APPROVABLE). THE SPECIFICATIONS INCLUDE DETAILED PROCEDURES FOR THE ADEQUATE FLUSHING, DISINFECTION, AND MICRO-BIOLOGICAL TESTING OF ALL WATER MAINS.

22. ROAD OPENINGS SHALL BE DONE IN ACCORDANCE WITH CONDITIONS OF PERMIT, AND COORDINATED WITH THE TOWN OF YORKTOWN.

23. UPON COMPLETION AND PRIOR TO USE, TWO (2) SETS OF AS-BUILT PLANS AND ACCEPTABLE BACTERIOLOGICAL SAMPLE AND WATER MAIN HYDROSTATIC TEST RESULTS MUST BE SUBMITTED ALONG WITH THE DESIGN PROFESSIONAL'S CERTIFICATION OF CONSTRUCTION.

SANITARY SEWER NOTES:

1. ALL WORK TO BE DONE IN ACCORDANCE WITH THE CODE OF THE TOWN OF YORKTOWN AND THE REGULATIONS OF THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH. 2. SANITARY MANHOLES/CLEANOUT MANHOLES SHALL BE PRECAST CONCRETE.

3. ALL WORK SHALL BE MANUFACTURED IN ACCORDANCE WITH APPROVED STANDARDS AND SHALL BE SPACED A MAXIMUM DISTANCE OF 300' ON STRAIGHT RUNS AND INSTALLED AT EVERY CHANGE IN ALIGNMENT. MANHOLE POSITIONING SHALL BE AS TO PREVENT THE ENTRANCE OF SURFACE WATER DURING STORMS. MANHOLE RIMS ARE TO BE WATER TIGHT IN AREAS SUBJECT TO POSSIBLE FLOODING CONDITIONS. 4. ALL BUILDING LATERALS TO BE INSTALLED BY PLUMBERS, LICENSED IN THE TOWN OF YORKTOWN ACCORDING

TO THE REQUIREMENTS OF THE TOWN OF YORKTOWN. 5. SANITARY SEWER CONSTRUCTION SHALL MEET ALL SEWER CONSTRUCTION SPECIFICATIONS FOR THE TOWN OF YORKTOWN.

6. THE TOWN ENGINEER SHALL BE NOTIFIED 48 HOURS PRIOR TO THE START OF ANY WORK.

7. A CODE 53 SHALL BE CALLED BEFORE THE START OF ANY EXCAVATION WORK.

8. A STREET OPENING PERMIT SHALL BE OBTAINED BY THE CONTRACTOR PRIOR TO ANY WORK BEING STARTED IN PUBLIC ROADS. 9. ALL SEWERS SHALL BE LAID AT LEAST 10 FT HORIZONTALLY FROM ANY EXISTING OR PROPOSED WATER MAIN.

THE DISTANCE SHALL BE MEASURED EDGE TO EDGE. IN CASES WHERE IT IS IMPRACTICAL TO MAINTAIN A 10 FOOT SEPARATION, THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH MAY ALLOW DEVIATION ON A CASE-BY-CASE BASIS, IF SUPPORTED BY DATA FROM THE DESIGN ENGINEER. 10. MANHOLE STEPS SHALL BE CAST IRON NEENAH NO. R-1981-0 OR CAMPBELL FOUNDRY NO. 2588-1 OR

POLYPROPYLENE COATED STEEL (SEE SPECIFICATIONS) OR APPROVED EQUAL. 11. UNLESS OTHERWISE SPECIFIED, SANITARY SEWER MANHOLES SHALL HAVE THE LETTERS "SEWER" CAST ON THE COVER.

12. MANHOLE COVERS AND STRUCTURES SHALL MEET OR EXCEED A.S.T.M. AND O.S.H.A. REQUIREMENTS AND MUST BE RATED FOR H-20 LOADING. MANHOLES MUST BE MIN. 48" DIAMETER. 13. ALL SANITARY STRUCTURES SHALL RECEIVE 2 MIL COATS OF BITUMINOUS MATERIAL "INERTOL NO. 49" KOPPERS

SUPPER SERVICE BLACK OR APPROVED EQUAL, APPLIED IN ACCORDANCE WITH MANUFACTURE'S SPECIFICATIONS.

14. 0-RING JOINTS TO CONFORM TO A.S.T.M. DESIGNATION C-443 LATEST REVISION. JOINTS TO BE MORTARED INSIDE AND OUT USING NON-SHRINKING MORTAR. 15. PRE-CAST MANHOLE SECTIONS TO BE IN ACCORDANCE WITH "PRE-CAST REINFORCED CONCRETE MANHOLE

SECTIONS" A.S.T.M. DESIGNATION C-478, LATEST REVISION, MINIMUM COMPRESSIVE STRENGTH TO BE 4000 P.S.I. 22. WHERE SEWER MAIN IS TO BE INSTALLED 10' DEEP OR GREATER, PVC SDR-26 SHALL BE USED. 16. WHEN SEWER IS TO BE INSTALLED IN FILL MATERIAL, THE SUPPORTING FILL IS TO BE COMPACTED TO MINIMUM

STANDARD PROCTOR DENSITY OF 95%, AND SHALL BE CERTIFIED TO THE TOWN. 17. WATER MAINS CROSSING HOUSE SEWERS, STORM SEWERS OR SANITARY SEWERS SHALL BE LAID TO PROVIDE A VERTICAL SEPARATION OF A MINIMUM OF 18" BETWEEN THE BOTTOM OF WATER MAIN AND TOP OF SEWER. IN ADDITION, ADEQUATE STRUCTURAL SUPPORT SHALL BE PROVIDED FOR THE SEWER TO PREVENT EXCESSIVE DEFLECTION OF THE JOINTS AND THE SEWER SETTLING AND BREAKING THE WATER MAIN. IN ADDITION THE LENGTH OF WATER PIPE IS TO BE CENTERED AT THE POINT OF CROSSING SO THAT THE JOINTS WILL BE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER. NO WATER MAIN SHALL PASS THROUGH OR COME IN CONTACT WITH ANY PART OF A SEWER OR SEWER MANHOLE.

18. MANHOLES AND SANITARY SEWER LINES SHALL BE TESTED TO CONFORM WITH WESTCHESTER COUNTY DEPARTMENT OF HEALTH RULES AND REGULATIONS AND AS PER SANITARY SEWER TESTING NOTES BELOW. 19. THE WESTCHESTER COUNTY DEPARTMENT OF HEALTH SHALL BE PROVIDED A 48 HOUR NOTICE PRIOR TO THE

TESTING OF THE INSTALLED UTILITIES TO ALLOW WITNESSING OF TESTING BY THE DEPARTMENT 20. ALL INSTALLATIONS AND TESTING SHALL BE IN ACCORDANCE WITH ASTM STANDARDS F-1417, C-1244 AND THE TEN STATES STANDARDS, LATEST VERSION.

SANITARY SEWER TESTING

PROCEDURE AND METHOD OF TESTING - THE TEST LENGTH INTERVALS AND TYPE OF LEAKAGE TEST SHALL BE APPROVED BY THE OWNER'S FIELD REPRESENTATIVE AND SITE ENGINEER. IN THE CASE OF SEWERS LAID ON STEEP GRADES. THE LENGTH OF LINE TO BE TESTED BY EXFILTRATION AT ANY ONE TIME MAY BE LIMITED BY THE MAXIMUM ALLOWABLE INTERNAL PRESSURE ON THE PIPE AND JOINTS AT THE LOWER END OF THE LINE. THE WCHD SHALL BE NOTIFIED 48 HRS IN ADVANCE SO THEY MAY WITHNESS THE TESTING DEPENDING ON FIELD CONDITIONS AND/OR DESIRE OF THE CONTRACTOR, THE FOLLOWING TESTS FOR LEAKAGE MAY BE EMPLOYED:

1. HYDROSTATIC TEST THE TEST PERIOD, WHEREIN THE MEASUREMENTS ARE TAKEN SHALL NOT BE LESS THAN FOUR (4) HOURS IN EITHER TYPE OF TEST. THE TOTAL LEAKAGE OF ANY SECTION TESTED SHALL NOT EXCEED THE RATE OF 100 GALLONS PER MILE OF PIPE PER 24 HOURS PER INCH OF NOMINAL PIPE DIAMETER. FOR PURPOSES OF DETERMINING THE MAXIMUM ALLOWABLE LEAKAGE, MANHOLES SHALL BE CONSIDERED AS SECTIONS OF PIPE AND SHALL BE TESTED AT A LEVEL ABOVE THE HIGHEST JOINT PRIOR TO THE CONCRETE/RIM CONNECTION.

> (I) INFILTRATION TEST THIS TEST MAY BE USED ONLY WHEN GROUND WATER LEVELS ARE AT LEAST TWO (2) FEET ABOVE THE TOP OF THE PIPE FOR THE ENTIRE I ENGTH OF THE SECTION TO BE TESTED DURING THE ENTIRE PERIOD OF THE TEST. GROUND WATER LEVELS MAY BE MEASURED IN AN OPEN TRENCH OR IN STANDPIPES PREVIOUSLY PLACED IN BACKFILLED TRENCHES DURING THE BACKFILLING OPERATIONS. WHEN STANDPIPES ARE INSTALLED IN THE BACKFILL FOR GROUND WATER MEASUREMENT. THE LOWER ENDS OF THESE SHALL BE SATISFACTORILY EMBEDDED IN A MASS OF CRUSHED STONE OR GRAVEL TO MAINTAIN FREE PERCOLATION AND DRAINAGE. INFILTRATION THROUGH JOINTS SHALL BE MEASURED BY USING A WATERTIGHT WEIR OR ANY OTHER APPROVED DEVICE FOR VOLUMETRIC MEASUREMENT INSTALLED AT THE LOWER END OF

THE SECTION UNDER TEST (II) EXFILTRATION TEST

THIS TEST CONSISTS OF FILLING THE PIPE WITH WATER TO PROVIDE A HEAD OF AT LEAST TWO (2) FEET ABOVE THE TOP OF THE PIPE OR TWO (2) FEET ABOVE GROUND WATER, WHICHEVER IS HIGHER. AT THE HIGHEST POINT OF THE PIPE LINE UNDER TEST. AND THEN MEASURING THE LOSS OF WATER FROM THE LINE BY THE AMOUNT WHICH MUST BE ADDED TO MAINTAIN THE ORIGINAL LEVEL. IN THIS TEST THE LINE MUST REMAIN FILLED WITH WATER FOR AT LEAST TWENTY-FOUR (24) HOURS PRIOR TO THE TAKING OF MEASUREMENTS. EXFILTRATION SHALL BE MEASURED BY THE DROP OF WATER LEVEL IN A CLOSED-END STANDPIPE OR IN ONE OF THE SEWER MANHOLES AVAILABLE FOR CONVENIENT MEASURING.

WHEN A STANDPIPE AND PLUG ARRANGEMENT IS USED IN THE UPPER MANHOLE OF A LINE UNDER TEST, THERE MUST BE SOME POSITIVE METHOD OF RELEASING ENTRAPPED AIR IN THE SEWER PRIOR TO TAKING MEASUREMENTS

2. VACUUM TESTING OF MANHOLES - TESTED AS PER ASTM STANDARD - C-1244 THIS TEST METHOD IS ONLY APPLICABLE TO PRECAST CONCRETE MANHOLES. ALL LIFTING HOLES AND EXTERIOR JOINTS SHALL BE FILLED AND POINTED WITH AN APPROVED NON-SHRINKING MORTAR. NO STANDING WATER SHALL BE ALLOWED IN THE MANHOLE EXCAVATION WHICH MAY AFFECT THE ACCURACY OF THE TEST. ALL PIPES AND OTHER OPENINGS INTO THE MANHOLE SHALL BE SUITABLY PLUGGED IN SUCH A MANNER AS TO PREVENT DISPLACEMENT OF THE PLUGS WHILE THE VACUUM IS DRAWN. INSTALLATION AND OPERATION OF THE VACUUM EQUIPMENT AND INDICATING DEVICES SHALL BE IN ACCORDANCE WITH EQUIPMENT SPECIFICATIONS AND INSTRUCTIONS PROVIDED BY THE MANUFACTURER.

THE TEST HEAD MAY BE PLACED IN THE CONE SECTION OF THE MANHOLE. THE RIM-CONE JOINT IS NOT USUALLY TESTED. A VACUUM OF 10 INCHES OF MERCURY SHALL BE DRAWN. THE TIME FOR THE VACUUM TO DROP TO 9 INCHES OF MERCURY SHALL BE RECORDED. ACCEPTANCE FOR 4 FT. DIAMETER MANHOLES SHALL BE DEFINED AS WHEN THE TIME TO DROP TO 9 INCHES OF MERCURY MEETS OR EXCEEDS THE FOLLOWING

> FOR MANHOLES 5 FT. IN DIAMETER. ADD AN ADDITIONAL 15 SECONDS: FOR MANHOLES 6 FT. IN DIAMETER, ADD AN ADDITIONAL 30 SECONDS TO THE TIME REQUIREMENTS FOR FOUR FOOT DIAMETER MANHOLES.

. LOW-PRESSURE AIR TEST OF PIPE LINES - <u>TESTED PER ASTM STANDARD F-1417</u> PLUG ALL OPENINGS IN THE TEST SECTION. ADD AIR UNTIL THE INTERNAL PRESSURE OF THE LINE IS RAISED TO APPROXIMATELY 4.0 PSI. AFTER THIS PRESSURE IS REACHED, ALLOW THE PRESSURE TO STABILIZE. THE PRESSURE WILL NORMALLY DROP AS THE AIR TEMPERATURE STABILIZES. THIS USUALLY TAKES 2 TO 5 MIN. DEPENDING ON THE PIPE SIZE. THE PRESSURE MAY BE REDUCED TO 3.5 PSI BEFORE STARTING THE TEST.

WHEN THE PRESSURE HAS STABILIZED AND IS AT OR ABOVE THE STARTING TEST PRESSURE OF 3.5 PSI. START THE TEST. IF THE PRESSURE DROPS MORE THAN 1.0 PSI DURING THE TEST TIME. THE LINE IS PRESUMED TO HAVE FAILED THE TEST. IF A 1.0-PSI DROP DOES NOT OCCUR WITHIN THE TEST TIME, THE LINE HAS PASSED THE TEST

TEST TIMES ARE FOR A 1.0 PSI PRESSURE DROP FROM 3.5 TO 2.5 PSI. IF THE SECTION OF LINE TO BE TESTED INCLUDES MORE THAN ONE PIPE SIZE. CALCULATE THE TEST TIME FOR EACH SIZE AND ADD THE TEST TIMES TO ARRIVE AT THE TOTAL TEST TIME FOR THE SECTION. MINIMUM TEST TIMES FOR VARIOUS PIPE SIZES IN INCHES ARE AS FOLLOWS:

4. DEFLECTION TESTING OF PIPES-

SECTION 33.85"-LATEST EDITION.

A. DEFLECTION TESTS SHALL BE PERFORMED ON ALL FLEXIBLE PIPE. THE TEST SHALL BE CONDUCTED AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS TO PERMIT STABILIZATION OF THE SOIL-PIPE SYSTEM.

B. NO PIPE SHALL EXCEED A DEFLECTION OF 5 PERCENT. IF DEFLECTION EXCEEDS 5 PERCENT, THE PIPE SHALL BE EXCAVATED. REPLACEMENT OR CORRECTION SHALL BE ACCOMPLISHED IN

ACCORDANCE WITH REQUIREMENTS IN THE APPROVED SPECIFICATIONS. C. THE RIGID BALL OR MANDREL USED FOR THE DEFLECTION TEST SHALL HAVE A DIAMETER NOT LESS THAN 95 PERCENT OF THE BASE INSIDE DIAMETER OR AVERAGE INSIDE DIAMETER OF THE PIPE DEPENDING ON WHICH IS SPECIFIED IN THE ASTM SPECIFICATION, INCLUDING THE APPENDIX, TO WHICH THE PIPE IS MANUFACTURED. THE TEST SHALL BE PERFORMED WITHOUT MECHANICAL PULLING DEVICES.

IN ACCORDANCE WITH THE TEN STATES "RECOMMENDED STANDARDS FOR WASTEWATER FACILITIES

LEGEND

____222 ____ X 222.8

~ 200 _____ _____ _____

------ LPSS-------———— FM ———— _____ SS _____ _____ WS _____

EXISTING GRADING EXISTING SPOT GRADE PROPOSED GRADING PROPERTY LINE / RIGHT OF WAY PROPOSED ROAD CENTERLINE PROPOSED CURB

EDGE OF WETLAND 100' WETLAND BUFFER

EXISTING WATER LINE **EXISTING FIRE HYDRANT** PROPOSED FIRE HYDRANT CONSERVATION EASEMENT LINE APPROX. AREA OF ROCK OUTCROP EXISTING STONE WALL EXISTING STONE WALLS TO BE REMOVED EXISTING DRAINAGE INLET

EXISTING SANITARY LINE **EXISTING HEADWALL**

PROPOSED DRAINAGE LINE

PROPOSED CATCH BASIN

PROPOSED DRAINAGE MANHOLE

PROPOSED OUTLET STRUCTURE PROPOSED HEADWALL WITH RIP RAP PROPOSED FOOTING DRAIN PROPOSED ROOF DRAIN PROPOSED LOW PRESSURE SEWER PROPOSED SEWER FORCE MAIN PROPOSED SEWER SERVICE CONNECTION PROPOSED WATER MAIN PROPOSED WATER SERVICE CONNECTION PROPOSED UNDERGROUND ELECTRIC SERVICE PROPOSED GAS SERVICE PROPOSED UTILITY CROSSING PROPOSED SANITARY MANHOLE AND LINE PROPOSED LIGHT POST AREA OF POTENTIAL BLASTING

PROPOSED HOUSE AND DRIVE

PROPOSED SOIL STOCKPILES PROPOSED SILT FENCE PROPOSED CRUSHED STONE **INLET PROTECTION** PROPOSED STABILIZED

CONSTRUCTION ENTRANCE PROPOSED LIMIT OF DISTURBANCE

- (NYSSESC).

- CEASED.

- THIS PLAN.
- . UPON COMPLETION OF THE DRAINAGE AND UTILITIES, INSTALL THE ASPHALT PAVEMENT BASE COURSE OVER THE ROADWAY AND DRIVEWAY. BACKFILL TO GRADE, PLACE FINAL SOIL TOPPING AND PUT IN PLACE PERMANENT VEGETATIVE COVER OVER ALL DISTURBED AREAS, LANDSCAPE BEDS, SLOPES, ETC.
- 8. DURING SITE CONSTRUCTION MAINTAIN AND RE-ESTABLISH AS REQUIRED EROSION CONTROL AND STABILIZATION MEASURES AS REQUIRED BY THE SITE PLAN AND DETAILS. 9. CONNECT THE INFILTRATION BASIN TO THE UPSTREAM BYPASS STRUCTURE AS SHOWN ON THE PLAN. RUNOFF WILL BE BLOCKED FROM
- ENTERING THE INFILTRATION BASIN UNTIL FINAL STABILIZATION. 10. ONCE ALL AREAS HAVE ACHIEVED FINAL GRADES, ANY REMAINING STOCKPILED MATERIAL SHALL BE REMOVED FROM THE SITE WITHIN 24 HRS.
- MINIMUM UNIFORM 80% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS), REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROLS, UNPLUG THE DRAINAGE SYSTEM TO ALLOW RUNOFF TO ENTER THE STORMWATER MANAGEMENT SYSTEM. THIS SHALL BE DONE DURING OPTIMUM WEATHER CONDITIONS IF POSSIBLE TO AVOID SEDIMENT TRANSPORT. THIS WORK SHALL NOT OCCUR IF PRECIPITATION IS FORECASTED DURING THE WORK. DURING CONSTRUCTION OF LOTS 1-10, THE INFILTRATION SYSTEM FOR THE ROAD SHALL BE INSPECTED MONTHLY AND AFTER MAJOR STORM EVENTS TO ENSURE SEDIMENT FROM CONSTRUCTION DOES NOT ENTER THE SYSTEM. ANY SEDIMENT DEPOSITS WILL BE REMOVED.
- 12.UPON STABILIZATION OF ALL DISTURBED AREAS AND APPROVAL FROM THE TOWN REPRESENTATIVE REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROLS.

PHASE 2: INDIVIDUAL LOTS

EACH LOT WILL BE CONSTRUCTED INDIVIDUALLY. THE LOTS MAY BE CONSTRUCTED IN ANY PARTICULAR ORDER. AT NO ONE TIME SHALL MORE THAN 5 ACRES BE DISTURBED.

- PREPARE THE INDIVIDUAL LOT FOR CONSTRUCTION BY INSTALLING ALL TEMPORARY PERIMETER EROSION AND SEDIMENT CONTROLS (E&SCS) AS SHOWN ON THE APPROVED CONSTRUCTION DRAWINGS.
- 2. ESTABLISH THE DRIVEWAY ENTRANCE AND INSTALL THE STABILIZED CONSTRUCTION ENTRANCE. 3. REMOVE EXISTING VEGETATIVE COVER AND OTHER SURFACE FEATURES IN THE LIMIT OF CONSTRUCTION ONLY FOR WORK TO BE IMMEDIATELY DONE AND WITHIN THE LIMITS OF PHASE 2. APPLY STABILIZATION MEASURES AS DESCRIBED IN THE GENERAL SEQUENCE. SILT FENCING SHOULD BE INSTALLED AT THE BASE OF SLOPES. AND STOCKPILES SHALL BE PLACED IN THE LOCATIONS SHOWN ON THE PLAN.
- 4. ROUGH GRADE DRIVEWAY AND INSTALL EROSION AND SEDIMENT CONTROLS AS NEEDED. SLOPES IN EXCESS OF 3:1 SHALL BE STABILIZED USING EROSION BLANKETS. 5. DURING SITE CONSTRUCTION MAINTAIN AND RE-ESTABLISH AS REQUIRED EROSION CONTROL AND STABILIZATION MEASURES AS REQUIRED BY
- THE SITE PLAN AND DETAILS. REMOVE ANY SEDIMENT TRACK ON ROADWAY FROM CONSTRUCTION VEHICLES AS NEEDED. 6. EXCAVATE FOR AND INSTALL FOUNDATION. UPON COMPLETION OF FOUNDATION WALLS BACKFILL AND GRADE THE REMAINDER OF THE LOT.
- 7. BEGIN CONSTRUCTION OF THE REMAINDER OF THE BUILDING.
- 8. ONCE THE NECESSARY CONNECTIONS HAVE BEEN CONSTRUCTED WITHIN THE BUILDING, BEGIN THE INSTALLATION OF THE SEWER AND WATER CONNECTIONS FOR THE LOTS. THESE SHALL ONLY BE CONSTRUCTED IN THE LOCATIONS SHOWN ON THE PLANS.
- 9. INSTALL ALL UNDERGROUND UTILITIES. INSTALL THE DRAINAGE SYSTEM AND RAIN GARDENS. FOR THE RAIN GARDENS EXCAVATE TO ELEVATION SHOWN ON PLAN AND INSTALL BASE COURSE OF GRAVEL. INSTALL FILTER MEDIA AND OUTLET STRUCTURE AND INSTALL OUTLET PROTECTION AT ALL OUTLETS. BACKFILL AS NEEDED. ENTRY POINTS TO DRAINAGE SYSTEM SHALL BE BLOCKED UNTIL SITE IS STABLE. ALL EROSION CONTROLS SHALL REMAIN IN PLACE.
- 10.INSTALL BASE COURSE MATERIAL FOR DRIVEWAY.
- 11. TOPSOIL. RAKE. SEED AND MULCH ALL DISTURBED AREAS. 12.INSTALL WALKS, FENCES, OTHER SITE IMPROVEMENTS AND FINAL PLANTINGS.
- 13. ONCE SITE STABILIZATION HAS TAKEN PLACE (AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 80% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS), REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROLS, UNPLUG THE DRAINAGE SYSTEM TO ALLOW RUNOFF TO ENTER THE STORMWATER MANAGEMENT SYSTEM. THIS SHALL BE DONE DURING OPTIMUM WEATHER CONDITIONS IF POSSIBLE TO AVOID SEDIMENT TRANSPORT. THIS WORK SHALL NOT OCCUR IF PRECIPITATION IS FORECASTED DURING THE WORK.
- 14.UPON STABILIZATION OF ALL DISTURBED AREAS AND APPROVAL FROM THE TOWN REPRESENTATIVE REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROLS.

WINTER STABILIZATION NOTES:

IF CONSTRUCTION ACTIVITIES ARE EXPECTED TO EXTEND INTO OR OCCUR DURING THE WINTER SEASON THE CONTRACTOR SHALL ANTICIPATE PROPER STABILIZATION AND SEQUENCING. CONSTRUCTION SHALL BE SEQUENCED SUCH THAT WHEREVER POSSIBLE AREAS OF DISTURBANCE THAT CAN BE COMPLETED AND PERMANENTLY STABILIZED SHALL BE DONE BY APPLYING AND ESTABLISHING PERMANENT VEGETATIVE COVER BEFORE THE FIRST FROST. AREAS SUBJECT TO TEMPORARY DISTURBANCE THAT WILL NOT BE WORKED FOR AN EXTENDED PERIOD OF TIME SHALL BE TREATED WITH TEMPORARY SEED, MULCH, AND/OR EROSION BLANKETS.

THE RESPONSIBLE PARTY DURING AND AFTER CONSTRUCTION IS AS FOLLOWS:

TE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAV

JOHN COLANGELO 1133 WESTCHESTER AVE. SUITE N-006 WHITE PLAINS, NY 10604 347-231-6959

SUPPLY ALL EQUIPMENT AND WATER. 16. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION INSPECTIONS AS PER NYSDEC GP-0-15-002 AND TOWN OF YORKTOWN CODE.

N.Y.S.D.E.C. GP-0-15-002 EXPOSURE RESTRICTIONS - STATES THAT ANY EXPOSED EARTHWORK SHALL BE STABILIZED IN ACCORDANCE WITH THE GUIDELINES OF

- SILT FENCE
 - STABILIZED CONST EN SEDIMENT
 - STOCKPILE DEWATERING
 - OUTLET/ INI F STRUCTURE & PROTECTIO

Control Inspec Drain lı Infiltratio Downst

Rain Ga

- Defen Swale and (

CONSTRUCTION SEQUENCE:

GENERAL SEQUENCE: THE GENERAL SEQUENCE APPLIES TO THE START OF ALL PHASES OF THE PROJECT. THE REQUIREMENTS IN SUCH SHALL BE APPLIED AS APPROPRIATE IN THAT PHASE AND SHALL BE ASSUMED IN PLACE PRIOR TO THE START OF THE WORK OUTLINED IN THE SEQUENCE FOR EACH PHASE.

1. PRIOR TO THE BEGINNING OF ANY SITE WORK THE MAJOR FEATURES OF THE CONSTRUCTION MUST BE FIELD STAKED BY A LICENSED SURVEYOR. THESE INCLUDE THE BUILDINGS, LIMITS OF DISTURBANCE, UTILITY LINES, AND STORMWATER PRACTICES. STORMWATER PRACTICES

SHALL BE FENCED OFF TO PREVENT DISTURBANCE TO THE UNDERLYING SOILS. 2. PRIOR TO THE START OF THE PROJECT, AN ON-SITE PRE-CONSTRUCTION MEETING WILL BE HELD. THIS WILL BE ATTENDED BY THE PROJECT OWNER, THE OPERATOR RESPONSIBLE FOR COMPLYING WITH THE APPROVED CONSTRUCTION DRAWINGS INCLUDING THE EROSION AND SEDIMENT CONTROL (E&SC) PLAN AND DETAILS, THE DESIGN ENGINEER, THE ENGINEER RESPONSIBLE FOR E&SC MONITORING DURING

CONSTRUCTION, TOWN REPRESENTATIVES FROM THE ENGINEERING DEPARTMENT AND CODE ENFORCEMENT 3. CUT AND CLEAR TREES WITHIN THE PHASE LIMITS AS NECESSARY FOR THE AREAS TO BE DISTURBED. INSTALL TREE PROTECTIVE MEASURE AT MARKED LOCATIONS ON E&SC PLAN.

4. INSTALL ALL TEMPORARY EROSION CONTROL MEASURES AS SHOWN ON THE EROSION AND SEDIMENT CONTROL PLAN FOR THE PROJECT'S IMMEDIATE DISTURBANCE AREAS. THIS SHALL INCLUDE, BUT NOT LIMITED TO SILT FENCE, STABILIZED CONSTRUCTION ENTRANCES, DIVERSION SWALES, SEDIMENT TRAPS, CONSTRUCTION FENCE, ETC. THIS SEQUENCE MUST BE FOLLOWED TO INSURE PROPER IMPLEMENTATION OF THE

EROSION AND SEDIMENT CONTROL PLAN (E&SC) AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP). TIMBERED TREES AND WOODCHIPS SHALL BE TEMPORARILY STORED IN THE STOCKPILE AND/OR STAGING AREA IF NECESSARY. BEFORE BEING REMOVED OFF-SITE. WOODCHIPS MAY BE USED FOR MULCH TO STABILIZE DISTURBED AREAS. WOODCHIP MULCH SHALL BE APPLIED AT A MINIMUM RATE OF 500 LBS. PER 1000 SF (2" THICK MINIMUM).

3. REMOVE EXISTING VEGETATIVE COVER, CUT AND CLEAR TREES, GRUB, REMOVE STUMPS AND OTHER SURFACE FEATURES IN THE LIMIT OF CONSTRUCTION ONLY. ANY DISTURBANCE THAT RESULTS FROM TREE CLEARING AND GRUBBING SHALL BE IMMEDIATELY STABILIZED WITH WOODCHIPS MULCH, HYDRO-MULCH, OR STRAW AND SEED. TIMBERED TREES, WOOD CHIPS, AND STUMPS SHALL BE REMOVED OFF-SITE UNLESS OTHERWISE DIRECTED. AS STATED WOODCHIPS MAY BE STOCKPILED FOR USE AS STABILIZING GROUND COVER. DEMOLISH AND/OR REMOVE EXISTING FEATURES, I.E.: FENCE, CONCRETE SLAB, ASPHALT ETC., AND DISPOSE OF OR STOCKPILE AS REQUIRED BY THE OWNER. ALL CONSTRUCTION DEBRIS SHALL BE PROPERLY DISPOSED OF IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REQUIREMENTS.

PHASE I: PROJECT INFRASTRUCTURE

1. ESTABLISH MAIN ROAD ENTRANCE AND INSTALL THE STABILIZED CONSTRUCTION ENTRANCE

2. CLEAR THE AREA FOR THE PROPOSED ROAD AND THE TO THE EXTENTS SHOWN ON THE PLAN. INSTALL PERIMETER EROSION CONTROL PRACTICES. SILT FENCING SHALL BE INSTALLED AT THE BASE OF SLOPES PARALLEL TO CONTOURS AS SHOWN ON THE PLAN. 3. BEGIN INSTALLATION OF THE DRAINAGE SYSTEM. DO NOT CONNECT THE OUTLET TO THE INFILTRATION SYSTEM FROM THE BYPASS STRUCTURE.

- 4. BEGIN EXCAVATION FOR THE ROUGH GRADE OF THE PROPOSED ROADWAY AND THE PROPOSED INFILTRATION BASIN TO THE EXTENTS SHOWN ON THE PLANS. CLEARING SHALL ONLY OCCUR WITHIN THE LIMITS OF DISTURBANCE FOR PHASE 1. ESTABLISH THE ELEVATION FOR INSTALLATION OF ROAD BASE. EROSION CONTROL MEASURES SHALL BE INSTALLED SIMULTANEOUSLY WITH CLEARING AND GRADING. WHEN COMPLETED INSTALL EROSION BLANKETS ON SLOPES EXCEEDED 3H:1V. INSTALL WATER BARS ALONG AS SHOWN ON THE PLANS.
- 5. INSTALL WATER MAIN MAIN AND CONNECT TO THE EXISTING MAIN IN STONY STREET AND SOUTH SHELLEY STREET. FOR EACH SERVICE CONNECTION EXTEND SERVICE AT LEAST 5' BEYOND THE EDGE OF PAVEMENT AND INSTALL CURB BOX. SERVICE CONNECTIONS SHALL CONTINUE FROM THE CURB BOX DURING THE INDIVIDUAL LOT CONSTRUCTION.
- 3. INSTALL SEWER MAIN AND CONNECT TO THE MANHOLE STONY STREET. FOR EACH SERVICE CONNECTION EXTEND SERVICE AT LEAST 5' BEYOND THE EDGE OF PAVEMENT AND CAP THE SERVICE LINE. SERVICE CONNECTIONS SHALL CONTINUE FROM THE CAP DURING THE INDIVIDUAL LOT CONSTRUCTION.

11. ONCE SITE STABILIZATION HAS TAKEN PLACE (AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A

GENERAL EROSION CONTROL NOTES

1. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL SEDIMENT AND EROSION CONTROL PRACTICES. THE SEDIMENT AND EROSION CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED. ROAD SURFACE FLOWS FROM THE SITE SHOULD BE DISSIPATED WITH TRACKING PAD OR APPROPRIATE MEASURES DURING ADJACENT ROAD SHOULDER REGRADING. CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL SOIL EROSION AND SEDIMENTATION CONTROL DEVICES

THROUGHOUT THE COURSE OF CONSTRUCTION. 2. CATCH BASIN INLET PROTECTION MUST BE INSTALLED AND OPERATING AT ALL TIMES UNTIL TRIBUTARY AREAS HAVE BEEN STABILIZED. WHEN POSSIBLE FLOWS SHOULD BE STABILIZED BEFORE REACHING INLET PROTECTION STRUCTURE. TIMELY MAINTENANCE OF SEDIMENT CONTROL STRUCTURES IS THE RESPONSIBILITY OF THE CONTRACTOR.

3. ALL STRUCTURES SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. THE SEDIMENT LEVEL IN ALL SEDIMENT TRAPS SHALL BE CLOSELY MONITORED AND SEDIMENT REMOVED PROMPTLY WHEN MAXIMUM LEVELS ARE REACHED OR AS ORDERED BY THE ENGINEER. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED ON A REGULAR BASIS, AND AFTER EACH HEAVY RAIN TO INSURE PROPER OPERATION AS DESIGNED. AN INSPECTION SCHEDULE SHALL BE SET FORTH PRIOR TO THE START OF CONSTRUCTION.

THE LOCATIONS AND THE INSTALLATION TIMES OF THE SEDIMENT CAPTURING STANDARDS SHALL BE AS SPECIFIED IN THESE PLANS, AS ORDERED BY THE ENGINEER, AND IN ACCORDANCE WITH THE LATEST EDITION OF THE "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL"

5. ALL TOPSOIL SHALL BE PLACED IN A STABILIZED STOCKPILE FOR REUSE ON THE SITE. ALL STOCKPILE MATERIAL REQUIRED FOR FINAL GRADING AND STORED ON SITE SHALL BE TEMPORARILY SEEDED AND MULCHED WITHIN 7 DAYS. REFER TO SOIL STOCKPILE DETAILS. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 7 DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, SHALL IMMEDIATELY RECEIVE

TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. DISTURBED AREAS SHALL NOT BE LIMED AND FERTILIZED PRIOR TO TEMPORARY SEEDING. IN AREAS WHERE SOIL DISTURBANCE ACTIVITY HAS TEMPORARILY OR PERMANENTLY CEASED, THE APPLICATION OF SOIL STABILIZATION MEASURES MUST BE

INITIATED BY THE END OF THE NEXT BUSINESS DAY AND COMPLETED WITHIN SEVEN (7) DAYS FROM THE DATE THE CURRENT SOIL DISTURBANCE ACTIVITY

8. ALL DISTURBED AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST CONTROL THE CONTRACTOR SHALL KEEP THE ROADWAYS WITHIN THE PROJECT CLEAR OF SOIL AND DEBRIS AND IS RESPONSIBLE FOR ANY STREET CLEANING NECESSARY DURING THE COURSE OF THE PROJECT. 10. SEDIMENT AND EROSION CONTROL STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY

STABILIZED BY PERMANENT MEASURES. 11. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CURRENT EDITION OF NYSSESC.

12. ALL REGRADED AREAS MUST BE STABILIZED APPROPRIATELY PRIOR TO ANY ROCK BLASTING. CUTTING, AND/OR FILLING OF SOILS. SPECIAL CARE SHOULD BE TAKEN DURING CONSTRUCTION TO INSURE STABILITY DURING MAINTENANCE AND INTEGRITY OF CONTROL STRUCTURES.

13. ANY SLOPES GRADED AT 3:1 OR GREATER SHALL BE STABILIZED WITH EROSION BLANKETS TO BE STAKED INTO PLACE IN ACCORDANCE WITH THE MANUFACTURES REQUIREMENTS. EROSION BLANKETS MAY ALSO BE REQUIRED AT THE DISCRETION OF TOWN OFFICIALS OR PROJECT ENGINEER. WHEN STABILIZED BLANKET IS UTILIZED FOR CHANNEL STABILIZATION, PLACE ALL OF THE VOLUME OF SEED MIX PRIOR TO LAYING NET, OR AS RECOMMENDED BY THE MANUFACTURER.

14. TO PREVENT HEAVY CONSTRUCTION EQUIPMENT AND TRUCKS FROM TRACKING SOIL OFF-SITE, CONSTRUCT A PERVIOUS CRUSHED STONE PAD. LOCATE AND CONSTRUCT PADS AS DETAILED IN THESE PLANS. 15. CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED SOIL AREAS PERIODICALLY WITH WATER AS REQUIRED. CONTRACTOR TO

MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES

1. TREES AND VEGETATION SHALL BE PROTECTED AT ALL TIMES AS SHOWN ON THE DETAIL DRAWING AND AS DIRECTED BY THE ENGINEER. 2. CARE SHOULD BE TAKEN SO AS NOT TO CHANNEL CONCENTRATED RUNOFF THROUGH THE AREAS OF CONSTRUCTION ACTIVITY ON THE SITE. FILL AND SITE DISTURBANCES SHOULD NOT BE CREATED WHICH CAUSES WATER TO POND OFF SITE OR ON ADJACENT PROPERTIES 4. RUNOFF FROM LAND DISTURBANCES SHALL NOT BE DISCHARGED OR HAVE THE POTENTIAL TO DISCHARGE OFF SITE WITHOUT FIRST BEING INTERCEPTED BY A CONTROL STRUCTURE, SUCH AS A SEDIMENT TRAP OR SILT FENCE. SEDIMENT SHALL BE REMOVED BEFORE EXCEEDING 50% OF THE RETENTION STRUCTURE'S CAPACITY.

5. FOR FINISHED GRADING, ADEQUATE GRADE SHALL BE PROVIDED SO THAT WATER WILL NOT POND ON LAWNS FOR MORE THAN 24 HOURS AFTER RAINFALL, EXCEPT IN SWALE FLOW AREAS WHICH MAY DRAIN FOR AS LONG AS 48 HOURS AFTER RAINFALL

ALL SWALES AND OTHER AREAS OF CONCENTRATED FLOW SHALL BE PROPERLY STABILIZED WITH TEMPORARY CONTROL MEASURES TO PREVENT EROSION AND SEDIMENT TRAVEL. SURFACE FLOWS OVER CUT AND FILL AREAS SHALL BE STABILIZED AT ALL TIMES. 7. ALL SITES SHALL BE STABILIZED WITH EROSION CONTROL MATERIALS WITHIN 7 DAYS OF FINAL GRADING.

8. TEMPORARY SEDIMENT TRAPPING DEVICES SHALL BE REMOVED FROM THE SITE WITHIN 30 DAYS OF FINAL STABILIZATION.

MAINTENANCE SCHEDULE

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
			INSP.	INSP.	CLEAN OF SEDIMENT/ REPLACE IF NEEDED	REMOVE
	CLEAN OF SEDIMENT	INSP.			REPLACE	REMOVE
		INSP.	INSP.	INSP.	CLEAN OF SEDIMENT/ REPLACE IF NEEDED	REMOVE
		INSP.	INSP.	INSP.	SEED AS NECESSARY	REMOVE
G		INSP.	INSP.	INSP.	CLEAN OF SEDIMENT/ REPLACE IF NEEDED	REMOVE
ET S ON		INSP.	INSP.	INSP.	CLEAN OF SEDIMENT/ REPLACE IF NEEDED	REMOVE

POST CONSTRUCTION MAINTENANCE SCHEDULE:

l to be cted	Inspection Frequency	Maintenance Threshold Criteria	Maintenance Procedure
nlets	Quarterly	3" + Accumulated Sediment	Remove debris and sediment annually.
on Basin	Bi-annually	Debris Leaves and Sediment at 5%	Cut Grass – Remove debris and leaves
tream nder	Bi-annually	Sediment at 25%	Remove debris and sediment annually; flush and vacuum
arden	Quarterly	Ponding for more than 48 hrs	Remove accumulated sediment and debris; weed and replace plants and mulch as needed.
Channels	Semi-Annually	Debris and Leaves	Remove Debris and Sediment Annually

be free of obstruction. Any sediment build up shall be removed. should also be inspected after major storm events. DEBRIS AND LITTER REMOVAL STRUCTURAL REPAIR/REPLACEMENT **EROSION CONTROL** SEDIMENT REMOVAL

TOPSOIL

	<u> </u>		
Exi	sting topsoil w	ill be removed and	d stored
out	lined on these	plans. The furnisl	ning of
1.	The pH of th	e material shall be	e 5.5 to
2.	The organic	content shall not l	oe less
3.	Gradation:	SIEVE SIZE	<u>%</u> F
		2 INCH	

- 1 INCH
- 1/4 INCH NO. 200 MESH

PERMANENT VEGETATIVE COVER

- 1. Site preparation:
- 1.1. Install erosion control measures.
- 1.2. Scarify compacted soil areas. 1.3. Lime as required to ph 6.5.
- 1.4. Fertilize with 10-6-4 4 lbs/1,000 S.F.
- 1.5. Incorporate amendments into soil with disc harrow. 2. Seed mixtures for use on swales and cut and fill areas.
- MIXTURE

REDTOP

ALT. B

ALT. A

- 3. SEEDING
- 3.2. Apply soil amendments and integrate into soil.
- 3.3.
- 3.4. Stabilize seeded areas in drainage swales. 3.5.
- 3.6.
- 3.7.

TEMPORARY VEGETATIVE COVER

- SITE PREPARATION:
- 1. Install erosion control measures.
- 2. Scarify areas of compacted soil. 3. Fertilize with 10-10-10 at 400/acre.
- 4. Lime as required to ph 6.5.

SEED SPECIES:

MIXTURE

Rapidly germinating annual ryegrass

(or approved equal) Perennial ryegrass

Cereal oats

SEEDING:

Same as permanent vegetative cover

OWNER / OPERATOR CERTIFICATION 210.45 OF THE PENAL LAW."

NAME ((PLEASE	PRINT):	

TITLE:		
DATE:		

ADDRESS:

PHONE:

EQMITRACTOR CERTIFICATION STATEMENT

Individual Contractor:	
Name and Title (please print):	
Signature of Contractor:	
Company / Contracting Firm:	
Name of Company:	
Address of Company:	
Telephone Number / Cell Number:	
Site Information:	
Address of Site:	

Today's Date:

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAV

21/21-18 GRISHAJ - STONY STREET/ENGINEERING/CAD/C3D-21-18 GRISHAJ - STONY STREET/21-18 DETAILS 9

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

W3-17	PROJECT # 21-18
Ation with the following:	Site Design Consultants Civil Engineers • Land Planners 251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 • Fax: (914) 962-7386 www.sitedesignconsultants.com
WUTCD, latest edition.	SITE DETALS ITE DETALS ITE DETALS ITE DETALS DETE: 5/7/21
	TITE PLAN SITE PLAN PREPARED FOR PREPARED FOR 319 STONY STREET Town Of Yorktown Westchester County, New York





Home & Hearth

TOWN OF YORKTOWN PLANNING DEPARTMENT

Albert A. Capellini Community and Cultural Center, 1974 Commerce Street, Yorktown Heights, New York 10598, Phone (914) 962-6565, Fax (914) 962-3986

To:Planning BoardFrom:Planning DepartmentDate:February 24, 2022Subject:Home & Hearth
SBL: 15.12-1-2

The Planning Department has reviewed the current submission and has the following comments:

- 1. The Town's environmental consultant is scheduled to start review of the wetland delineation and proposed mitigation on March 2, 2022.
- 2. The Building Inspector determined the second building to be a second main use on the site and not an accessory structure therefore a height variance is not needed.
- 3. The applicant has indicated landscaping and lighting plans will be submitted at a future date, however this application will not be complete until those plans are submitted.

Respectfully submitted,

sere Robyn A. Steinberg, AICP, CPESC

Town Planner

Site Design Consultants

Civil Engineers • Land Planners

February 15, 2022

Rich Fon, Chairman Members of the Planning Board c/o Town of Yorktown Planning Department 1974 Commerce Street Yorktown Heights, NY 10598

Re: Home and Hearth 1750 East Main Street Mohegan Lake SBL 15.12-1-2

RECEIVED PLANNING DEPARTMENT FEB 1 6 2022 TOWN OF YORKTOWN

Dear Chairman Fon and Members of the Planning Board:

We are in receipt of the memo to the Planning Board from the Planning Department dated October 15, 2021 and offer the following responses:

- All adjacent building should be shown on the site plan. Response: All adjacent properties 1. including buildings parking areas are included on the cover sheet.
- Applicant must develop landscape and lighting plans. Response: These plans will be submitted 2. at a future date.
- The freestanding sign location should be shown on the site plan. Response: The existing free-3. standing sign location is indicated on the site plan.
- Show the existing sidewalk along Route 6 on the site plan. Response: The sidewalk along 4. Route 6 is shown and is noted to be replaced.
- The applicant was to revise the architecture of the accessory building and resubmit to possibly 5. request avariance. No revised plans have been submitted yet. Response: The architecture of the accessory building has been modified with new roof lines. It has been determined that no variance is required for the height of the roof for the accessory building. Revised plans from the architect are included in this submission.
- 6. The wetland delineation and mitigation plan must be reviewed by the town's Environmental consultant. The Planning Department will send the submitted plans to the consultant and request a proposal for this review. Response: Acknowledged.
- 7. In 1986, the then property owner entered into an access easement agreement with the adjacent property to the west to allow ingress and egress across the front of the subject property. The filed easement is attached.





(914) 962-4488

Fax (914) 962-7386

Home and Hearth

Richard Fon, Chairman Members of the Planning Board February 15, 2022 Page 2 of 2

The proposed new building is positioned directly on top of where the adjacent site access crosses the property line and where an existing light pole is also located. It seems the building could be pushed backat least a foot or two to relieve the crowding of site elements between the two sites. Response: **Response to #7 and current: The access easement is shown on the site plan. We have repositioned the new building by sliding it back away from the existing curb line.**

Enclosed please find the following items being submitted for distribution and discussion at the Planning Board Meeting. We would also request that this project be scheduled for Public Hearing:

- Five prints of the Architectural plan;
- Five prints of the Mitigation Plan from Steve Marino;
- Five sets of Plans titled "Site Plan Prepared for Home and Hearth," Title Sheet and Sheets 1-8 of 8, dated 7/28/2021, last revised 2/15/2022.

We are also forwarding you a digital copy of this submission. Please add this project to the agenda for the Planning Board Meeting of February 28th and contact us if you have any questions. Thank you.

Yours Tru iina, P.E. Joseph C

Cc: Hearth and Home Town Supervisor Building Department Engineering Department Water Department Ed Lachterman

JCR / cm / Enc. / sdc 21-19



TOWN OF YORKTOWN PLANNING DEPARTMENT

Albert A. Capellini Community and Cultural Center, 1974 Commerce Street, Yorktown Heights, New York 10598, Phone (914) 962-6565, Fax (914) 962-3986

To:Planning BoardFrom:Planning DepartmentDate:October 15, 2021Subject:Home & Hearth
SBL: 15.12-1-2

The Planning Department reviewed the submitted site plan and has the following comments:

- 1. All adjacent building should be shown on the site plan.
- 2. Applicant must develop landscape and lighting plans.
- 3. The freestanding sign location should be shown on the site plan.
- 4. Show the existing sidewalk along Route 6 on the site plan.
- 5. The applicant was to revise the architecture of the accessory building and resubmit to possibly request a variance. No revised plans have been submitted yet.
- 6. The wetland delineation and mitigation plan must be reviewed by the town's Environmental consultant. The Planning Department will send the submitted plans to the consultant and request a proposal for this review.
- 7. In 1986, the then property owner entered into an access easement agreement with the adjacent property to the west to allow ingress and egress across the front of the subject property. The filed easement is attached.

The proposed new building is positioned directly on top of where the adjacent site access crosses the property line and where an existing light pole is also located. It seems the building could be pushed back at least a foot or two to relieve the crowding of site elements between the two sites.







ZONING SCHEDULE:

ZONING DISTRICT: C-4, BUSINESS (SECT	ION 300-71)		
DIMENSIONAL REGULATIONS:	REQUIRED	PROVIDED	
MINIMUM SIZE OF LOT:			
MINIMUM LOT AREA:	NONE	84,252 SF.	
MINIMUM LOT WIDTH:	25 FT.	124.4 FT.	
MINIMUM LOT DEPTH:	100 FT.	402.6 FT.	
MINIMUM YARD DIMENSIONS:			
PRINCIPAL BUILDING:			
FRONT YARD SETBACK:	15 FT.	47.8 FT.	
REAR YARD: MAIN BUILDING	30 FT.	181.8 FT.	
SIDE YARD: MAIN BUILDING	NONE ★ SEE NOTE	0 FT.	
ACCESSORY BUILDINGS:			
FRONT YARD SETBACK:	15 FT.	145.2 FT.	
REAR YARD SETBACK:	30 FT.	134.3 FT.	
MAXIMUM HEIGHT:			
MAIN BUILDING - FEET:	35 FEET	< 35 FT.	
ACCESSORY BUILDING - FEET:	20 FEET	< 20 FT.	
MAXIMUM % OF LOT COVERAGE:			
TOTAL BUILDING COVERAGE:	30% OF LOT AREA	11.9 % OF LOT AREA	

* NONE, BUT IF PROVIDED SHALL BE 10'; IF USED AS ONE WAY VEHICULAR ACCESS, SHALL BE 17 FT.;TWO WAY VEHICULAR ACCESS, 25 FT.; IF JOINS AN R DISTRICT, SHALL BE 50 FT. ** VARIANCE GRANTED BY ZONING BOARD OF APPEALS FEBRUARY 23, 2012 - REF# 5/12

	REQUIRED PARKING (AS PER TOWN CODE SECTION 300-179)	PROVIDED PARKING
ER §300-182):	4 SPACES / 1,000 SF OF RETAIL SPACE = 10 SPACES	18 PARKING SPACES
ER §300-186):	1 SPACE PER FIRST 10,000 SF. = 1 SPACE	1 PARKING SPACES
	ONE ADDITIONAL SPACE PER EACH 40,000 SF. AFTER. = 2.5 SPACES	3 PARKING SPACES
G:		23 STANDARD SPACES
		1 HANDICAP SPACES
JIRED:	0 SPACES	

WETLAND, MITIGATION AND COVERAGE AREA SUMMARY

LOCATION	AREA (SQUARE FEET)
EXISTING ON-SITE WETLANDS & BUFFER TOTAL AREA OF WETLAND AND BUFFER WETLAND (ON-SITE) WETLAND BUFFER (FROM ON & OFF SITE WETLAND)	76,594 S.F. 56,153 S.F. 20,441 S.F.
PROPOSED BUFFER DISTURBANCE MITIGATION AREA DISTURBANCE OTHER SITE IMPROVEMENT DISTURBANCE TOTAL AREA OF BUFFER DISTURBANCE	- - ±16,200 SF
IMPERVIOUS AREA: EXISTING = 15,963 SF PROPOSED = 109,495 SF	
IMPERVIOUS AREA W/IN 100' OF WETLAND: EXISTING = 0.27 ACRES PROPOSED = 0.35 ACRES	

- SITE PLAN NOTES: 1. WETLAND DELINEATION PERFORMED BY TIM MILLER ASSOCIATES AUGUST 2011 AND SURVEYED BY J. HENRY CARPENTER & CO. REVISED WETLAND LINE LOCATION AS SHOWN BASED ON FIELD CHANGE AS AGREED TO BY TOWN ENVIRONMENTAL CONSULTANT.
- 2. NO LOADING, UNLOADING OR TRANSFER OPERATION SHALL BE PERMITTED ON THE STREET, AT THE CURB OR WITHIN THE REQUIRED FRONT YARD. REF. SECTION300-71 OF THE TOWN CODE OF YORKTOWN.
- 3. NO REPAIR, SERVICE, OR WASHING OF VEHICLES ON-SITE IS PERMITTED.



SCALE:	Revisions:	Engineer: NEW E		
1" = 20'	No.DateComments:1.11/12/21Plan Updates	CARLO OF	Sile Design Consultants	
	2. 2/15/22 PD Memo	+ 1=		
 DRAWN BY:			Civil Engineers • Land Planners	
 TK		INIS NO.	251-F Underhill Avenue. Yorktown Heights, NY 10598	
		AND OF OF OF OF	(914) 962-4488 - Fax: (914) 962-7386	
 DATE:		ROFESSION	www.sitedesignconsultants.com	
7/28/21		Joseph C. Kuna, P.E. NYS Lic. No. 64431		PROJECT # 21-19

D

 $[\mathbf{T}]$

 \mathcal{O}

STREET

AIN

Σ

(II)

50 17

6

NOTE: 1. <u>THIS IS NOT A SURVEY.</u> ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY H. STANLEY JOHNSON AND COMPANY LAND SURVEYORS, P.C., DATED MARCH 24, 2004, LAST REVISED DECEMBER 14, 2020. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY. ALL INFORMATION RELATED TO ADJACENT PROPERTIES SUCH AS PROPERTY LINES, BUILDINGS AND SITE IMPROVEMENTS WERE OBTAINED FROM THE WESTCHESTER COUNTY GIS DATABASE AND SHOULD NOT BE CONSIDERED ACCURATE.

UTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



ZONE R1-20 ROUTE 6 REAL TY

 \geq

|

	PROJECT # 21-19
	Site Design Consultants Civil Engineers • Land Planners 251-F Underhill Avenue, Yorktown Heights, NY 10598 (914) 962-4488 - Fax: (914) 962-7386 www.sitedesignconsultants.com
	Engineer Engine
	Revisions: No. Date I. 11/12/21 Plan Updates 2. 2/15/22 PD Memo
	$\begin{array}{c} \text{SCALE:} \\ 1^{"} = 30^{"} \\ \text{DRAWN BY:} \\ \text{DRAWN BY:} \\ \text{TK} \\ \text{TK} \\ \text{TK} \\ \text{TK} \\ \text{TR} \\ TR$
	EXISTING CONDITIONS
0 15 30 60 0 15 30 00 0	SITE PLAN PREPARED FOR HOME & HEARTH 1750 EAST MAIN STREET Town of Yorktown Westchester County, New York
SAFE DIG Before You Dig, Drill or Blast! CALL US TOLL FREE 811 or 1-800-862-7962 NY Industrial Code Rule 753 requires no less than two working days notice, but not more than ten days notice. www.digsafelynewyork.com	Sheet 2 of 9







GENERAL NOTES:

- THE ENGINEER WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION,
- SUBSEQUENTLY, HE IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION PRACTICES, PROCEDURES, AND RESULTS THEREFROM. THE ENGINEER SHALL NOT BE HELD RESPONSIBLE OR HELD ACCOUNTABLE FOR THE INTEGRITY OF ANY STRUCTURES CONSTRUCTED
- OR UNDER CONSTRUCTION PRIOR TO THE APPROVAL OF THE PLANS. THE VILLAGE ENGINEER'S OFFICE AND WATER DISTRICT OFFICE IS TO BE NOTIFIED 24 HOURS BEFORE COMMENCING SITE
- CONSTRUCTION OR WATER MAIN CONNECTION. 4. ALL WORK IS TO BE IN ACCORDANCE WITH THE VILLAGE CODE OF PRACTICE AND SPECIFICATIONS.
- 5. ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES.
- 6. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER WHOSE SEALAPPEARS ON THESE DRAWINGS. ANY SUCH
- CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT. ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS
- 8. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL IN A "CODE 53" PRIOR TO CONSTRUCTION FOR UNDERGROUND UTILITY
- LOCATIONS. 9. SUBSTRUCTURES AND THEIR ENCROACHMENTS BELOW GRADE. IF ANY, ARE NOT SHOWN.). ANY PROPOSED ELECTRIC AND/OR TELEPHONE SERVICE LINES ARE TO BE PLACED UNDERGROUND.
- 10. THE DESIGN ENGINEER DISCLAIMS ANY LIABILITY FOR DAMAGE OR LOSS INCURRED DURING OR AFTER CONSTRUCTION. 11. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.

CONTRACTOR RESPONSIBILITIES:

- 1. ALL WORK ON THE PROJECT SHALL BE PERFORMED IN A WORKMAN LIKE MANNER AND SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE INDUSTRY. THE OWNER WILL BE THE SOLE JUDGE OF THE ACCEPTABILITY OF THE WORK. MATERIALS AND WORK
- DEEMED UNACCEPTABLE WILL BE REMOVED AND REDONE AT THE SOLE COST AND RESPONSIBILITY OF THE CONTRACTOR. . THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGES DUE TO HIS ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEE, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY THE WORK UNDER A SEPARATE
- CONTRACT WITH THE CONTRACTOR. 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROPERLY SHORE EXISTING UTILITIES IF REQUIRED BY CONSTRUCTION.
- 4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE THE BUILDING INSPECTOR IN ADVANCE OF HIS WORK OR AS THE INSPECTOR DEEMS APPROPRIATE. 5. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED
- IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY. 6. ALL CHANGES MADE TO THIS PLAN SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY
- UNAUTHORIZED ALTERATION OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL
- PORTIONS OF THE WORK UNDER THIS CONTRACT.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTRACT WITH THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL VERIFY ALL SUBSTRUCTURES ENCOUNTERED DURING CONSTRUCTION.
- 10. THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.

GENERAL CONSTRUCTION NOTES:

- 1. BENCH MARKS USING U.S.G.S. DATUM SHALL BE OF SUCH ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. 2. CONSTRUCTION ACTIVITY SHALL BE LIMITED FROM 8:00 A.M. TO 6 P.M., AND NO CONSTRUCTION ACTIVITY SHALL OCCUR ON SUNDAYS OR LEGAL NEW YORK STATE HOLIDAYS. WHERE BLASTING IS NECESSARY, IT SHALL OCCUR FROM MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 A.M. AND 6:00 P.M. NO BLASTING SHALL OCCUR ON HOLIDAYS, SATURDAY OR SUNDAY. ALL BLASTING SHALL ALSO BE COMPLETED IN ACCORDANCE WITH THE VILLAGE OF OSSINING AND NEW YORK STATE BLASTING ORDINANCES.
- . ANY SOIL THAT IS UNSUITABLE FOR DEVELOPMENT OF BUILDINGS OR ROADWAYS SHALL BE REMOVED FROM AREAS TO BE DEVELOPED AND SHALL BE DISPOSED OF WITHIN THE SITE IN NEW EMBANKMENTS WHERE STRUCTURAL LOADING, I.E. A BUILDING OR ROADWAY, WILL NOT TAKE PLACE. WHEN CONSTRUCTION IS PROPOSED TO OCCUR IN SPECIFIC AREAS WHERE SOILS ARE OF QUESTIONABLE SUITABILITY, THE APPLICANT SHALL PROVIDE SOILS ENGINEERING REPORTS AS REQUIRED BY THE PLANNING BOARD ENGINEER, PRIOR TO THE CONSTRUCTION OF ROADWAYS AND, AS REQUIRED BY THE BUILDING INSPECTOR, PRIOR TO THE ISSUANCE OF A BUILDING PERMIT.
- 4. NO TOPSOIL SHALL BE REMOVED FROM THE SITE.
- 5. ROCK CUT STABILITY IS TO BE FIELD VERIFIED BY GEOTECHNICAL ENGINEER AND SHALL BE MODIFIED IF REQUIRED. 6. NO CRUSHING/PROCESSING IS PERMITTED ON THE SITE WITHOUT PRIOR APPROVAL BY THE VILLAGE OF OSSINING PLANNING BOARD.

GENERAL STORM DRAINAGE & UTILITY NOTES

- . ALL UTILITIES, INCLUDING ELECTRIC LINES, TELEPHONE, WATER, SANITARY SEWER LINES, AND STORM SEWER LINES SHALL BE LOCATED UNDERGROUND AND SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE VILLAGE OF OSSINING AND THE UTILITY COMPANIES HAVING JURISDICTION.
- 2. LOCATION OF GAS AND WATER VALVES, ELECTRIC AND TELEPHONE POLES ARE TO BE DETERMINED BY PROPER AUTHORITIES AND APPROVED, AS TO LOCATION, BY THE VILLAGE ENGINEER. 3. EACH BUILDING CONSTRUCTED HEREON SHALL BE OF SUCH AN ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL
- DIRECTIONS. IN THE EVENT THAT THIS IS NOT FEASIBLE, THE CONTRACTOR SHALL INSTALL TYPICAL YARD DRAINS AS REQUIRED AND CONNECT THEM TO THE STORM DRAINAGE SYSTEM OR AS DIRECTED BY THE PROJECT ENGINEER.
- 4. ROOF LEADERS AND FOOTING DRAINS SHALL EMPTY INTO THE STORM DRAINAGE SYSTEM OR DISCHARGE DIRECTLY TO STORMWATER MANAGEMENT SYSTEMS IF GRADES PERMIT, AND CONNECTION TO THE STORM SYSTEM IS NOT FEASIBLE, FOOTING DRAINS ONLY MAY DISCHARGE TO DAYLIGHT AT THE REAR OF BUILDINGS. FOOTING DRAINS SHALL EXTEND A MINIMUM OF 30 FT. FROM THE REAR FACE OF THE BUILDING WHEN POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE DISCHARGE OF GROUND WATER OR STORM WATER, EITHER BY GRAVITY OR BY PUMPING, BE DISCHARGED TO ANY SANITARY SEWER SYSTEM. . ANY REVISIONS AND/OR ADDITIONS TO THE ROAD STORM DRAINAGE SYSTEMS CURRENTLY SHOWN ON THE PLANS WHICH ARE DEEMED NECESSARY DURING CONSTRUCTION MUST BE MADE BY THE CONTRACTOR AS REQUIRED BY THE VILLAGE AND SHALL BE
- SHOWN ON THE AS-BUILT DRAWINGS. 6. STORM DRAIN PIPING TO BE HIGH DENSITY POLYETHYLENE AS SHOWN ON THE CONSTRUCTION DRAWINGS, MINIMUM COVER TO BE
- 2' UNLESS OTHERWISE NOTED. 7. INTERCEPTOR DRAINS ARE TO BE INSTALLED WHERE REQUIRED BY THE VILLAGE OR PROJECT ENGINEER DURING ROAD
- CONSTRUCTION. 8. ALL EXISTING UNDERGROUND DRAINS ENCOUNTERED DURING CONSTRUCTION OF PROPOSED ROADS ARE TO BE CONNECTED TO PROPOSED DRAINAGE IMPROVEMENTS. CONNECTIONS TO BE APPROVED BY THE VILLAGE ENGINEER. 9. PRIOR TO FINAL APPROVAL AND OPERATION OF DRAINAGE SYSTEM, CONTRACTOR SHALL CLEAR ALL ACCUMULATED SEDIMENT
- AND/OR DEBRIS FROM DRAINAGE STRUCTURES, MANHOLES, CULVERTS, OUTLETS AND DRAIN INLETS. ENGINEER SHALL BE NOTIFIED FOR FINAL INSPECTION.
- 10. ALL STRUCTURES SHALL BE SET ONE INCH BELOW PAVEMENT. 11. STREET OPENING PERMIT FROM THE VILLAGE OF OSSINING D.P.W. MAY BE REQUIRED FOR INSTALLATIONS IN PUBLIC ROADS.

CONTRACTOR CERTIFICATION STATEMENT

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-15-002, dated January 12, 2015, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

DTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAV

Individual Contractor:
Name and Title (please print):
Signature of Contractor:

Signature of Contractor.
Company / Contracting Firm:
Name of Company:
Address of Company:
Telephone Number / Cell Numbe

Site Information: Address of Site:

Today's Date:

GENERAL EROSION CONTROL NOTES:

- CONSTRUCTION.
- RESPONSIBILITY OF THE CONTRACTOR.

- PROVIDE DUST CONTROL.

- EDITION OF NYSSESC.
- RECOMMENDED BY THE MANUFACTURER.
- VILLAGE OF OSSINING CODE.

MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES:

N.Y.S.D.E.C. GP-0-15-002 EXPOSURE RESTRICTIONS - STATES THAT ANY EXPOSED EARTHWORK SHALL BE STABILIZED IN ACCORDANCE WITH THE GUIDELINES OF THIS PLAN.

- DIRECTED BY THE ENGINEER.
- CONSTRUCTION ACTIVITY ON THE SITE.
- ADJACENT PROPERTIES.
- HOURS AFTER RAINFALL.
- SHALL BE STABILIZED AT ALL TIMES.
- STABILIZATION.

MAINTENANCE SCHEDULE:

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE			INSP.	INSP.	CLEAN/ REPLACE	REMOVE
WHEEL CLEANER	CLEAN				REPLACE	REMOVE
INLET PROTECTION		INSP.	INSP.	CLEAN	REPLACE	REMOVE

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION:

THE STORMWATER MANAGEMENT SYSTEM AND OUTLET STRUCTURE SHALL BE INSPECTED ON A REGULAR BASIS AND AFTER EVERY RAINFALL EVENT. SEDIMENT BUILD UP SHALL BE REMOVED FROM THE INLET PROTECTION REGULARLY TO INSURE DETENTION CAPACITY AND PROPER DRAINAGE. OUTLET STRUCTURE SHALL BE FREE OF OBSTRUCTIONS. ALL PIPING AND DRAIN INLETS SHALL BE FREE OF OBSTRUCTION. ANY SEDIMENT BUILD UP SHALL BE REMOVED. MAINTENANCE OF CONTROLS AFTER CONSTRUCTION: CONTROLS (INCLUDING RESPECTIVE OUTLET STRUCTURES) SHOULD BE INSPECTED PERIODICALLY FOR THE FIRST FEW MONTHS AFTER CONSTRUCTION AND ON AN ANNUAL BASIS THEREAFTER. THEY SHOULD ALSO BE INSPECTED AFTER

MAJOR STORM EVENTS. DEBRIS AND LITTER REMOVAL:

ACCUMULATIONS DURING EACH MOWING OPERATION. STRUCTURAL REPAIR/REPLACEMENT IMMEDIATELY.

EROSION CONTROL:

APPROPRIATE EROSION CONTROL MEASURES. SEDIMENT REMOVAL

MANAGEMENT SYSTEM FLOOR.

1. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL SEDIMENT AND EROSION CONTROL PRACTICES. THE SEDIMENT AND EROSION CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED. ROAD SURFACE FLOWS FROM THE SITE SHOULD BE DISSIPATED WITH TRACKING PAD OR APPROPRIATE MEASURES DURING ADJACENT ROAD SHOULDER REGRADING. CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL SOIL EROSION AND SEDIMENTATION CONTROL DEVICES THROUGHOUT THE COURSE OF

2. CATCH BASIN INLET PROTECTION MUST BE INSTALLED AND OPERATING AT ALL TIMES UNTIL TRIBUTARY AREAS HAVE BEEN STABILIZED. WHEN POSSIBLE FLOWS SHOULD BE STABILIZED BEFORE REACHING INLET PROTECTION STRUCTURE. TIMELY MAINTENANCE OF SEDIMENT CONTROL STRUCTURES IS THE

3. ALL STRUCTURES SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. THE SEDIMENT LEVEL IN ALL SEDIMENT TRAPS SHALL BE CLOSELY MONITORED AND SEDIMENT REMOVED PROMPTLY WHEN MAXIMUM LEVELS ARE REACHED OR AS ORDERED BY THE ENGINEER. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED ON A REGULAR BASIS. AND AFTER EACH HEAVY RAIN TO INSURE PROPER OPERATION AS DESIGNED. AN INSPECTION SCHEDULE SHALL BE SET FORTH PRIOR TO THE START OF CONSTRUCTION. 4. THE LOCATIONS AND THE INSTALLATION TIMES OF THE SEDIMENT CAPTURING STANDARDS SHALL BE AS SPECIFIED IN THESE PLANS, AS ORDERED BY THE ENGINEER, AND IN ACCORDANCE WITH THE LATEST EDITION OF THE "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL" (NYSSESC).

5. ALL TOPSOIL SHALL BE PLACED IN A STABILIZED STOCKPILE FOR REUSE ON THE SITE. ALL STOCKPILE MATERIAL REQUIRED FOR FINAL GRADING AND STORED ON SITE SHALL BE TEMPORARILY SEEDED AND MULCHED WITHIN 7 DAYS. REFER TO SOIL STOCKPILE DETAILS.

6. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 7 DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, SHALL IMMEDIATELY RECEIVE TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. DISTURBED AREAS SHALL NOT BE LIMED AND FERTILIZED PRIOR TO TEMPORARY SEEDING. 7. ALL DISTURBED AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO

8. THE CONTRACTOR SHALL KEEP THE ROADWAYS WITHIN THE PROJECT CLEAR OF SOIL AND DEBRIS AND IS RESPONSIBLE FOR ANY STREET CLEANING NECESSARY DURING THE COURSE OF THE PROJECT. 9. SEDIMENT AND EROSION CONTROL STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY STABILIZED BY PERMANENT MEASURES.

10. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CURRENT

11. ALL REGRADED AREAS MUST BE STABILIZED APPROPRIATELY PRIOR TO ANY ROCK BLASTING, CUTTING, AND/OR FILLING OF SOILS. SPECIAL CARE SHOULD BE TAKEN DURING CONSTRUCTION TO INSURE STABILITY DURING MAINTENANCE AND INTEGRITY OF CONTROL STRUCTURES.

12. ANY SLOPES GRADED AT 3:1 OR GREATER SHALL BE STABILIZED WITH EROSION BLANKETS TO BE STAKED INTO PLACE IN ACCORDANCE WITH THE MANUFACTURES REQUIREMENTS. EROSION BLANKETS MAY ALSO BE REQUIRED AT THE DISCRETION OF TOWN OFFICIALS OR PROJECT ENGINEER. WHEN STABILIZED BLANKET IS UTILIZED FOR CHANNEL STABILIZATION, PLACE ALL OF THE VOLUME OF SEED MIX PRIOR TO LAYING NET, OR AS

13. TO PREVENT HEAVY CONSTRUCTION EQUIPMENT AND TRUCKS FROM TRACKING SOIL OFF-SITE, CONSTRUCT A PERVIOUS CRUSHED STONE PAD. LOCATE AND CONSTRUCT PADS AS DETAILED IN THESE PLANS.

14. CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED SOIL AREAS PERIODICALLY WITH WATER AS REQUIRED. CONTRACTOR TO SUPPLY ALL EQUIPMENT AND WATER. 15. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION INSPECTIONS AS PER NYSDEC GP-0-15-002 AND

1. TREES AND VEGETATION SHALL BE PROTECTED AT ALL TIMES AS SHOWN ON THE DETAIL DRAWING AND AS

2. CARE SHOULD BE TAKEN SO AS NOT TO CHANNEL CONCENTRATED RUNOFF THROUGH THE AREAS OF

3. FILL AND SITE DISTURBANCES SHOULD NOT BE CREATED WHICH CAUSES WATER TO POND OFF SITE OR ON

4. RUNOFF FROM LAND DISTURBANCES SHALL NOT BE DISCHARGED OR HAVE THE POTENTIAL TO DISCHARGE OFF SITE WITHOUT FIRST BEING INTERCEPTED BY A CONTROL STRUCTURE, SUCH AS A SEDIMENT TRAP OR SILT FENCE. SEDIMENT SHALL BE REMOVED BEFORE EXCEEDING 50% OF THE RETENTION STRUCTURE'S CAPACITY 5. FOR FINISHED GRADING, ADEQUATE GRADE SHALL BE PROVIDED SO THAT WATER WILL NOT POND ON LAWNS FOR MORE THAN 24 HOURS AFTER RAINFALL, EXCEPT IN SWALE FLOW AREAS WHICH MAY DRAIN FOR AS LONG AS 48

6. ALL SWALES AND OTHER AREAS OF CONCENTRATED FLOW SHALL BE PROPERLY STABILIZED WITH TEMPORARY CONTROL MEASURES TO PREVENT EROSION AND SEDIMENT TRAVEL. SURFACE FLOWS OVER CUT AND FILL AREAS

7. ALL SITES SHALL BE STABILIZED WITH EROSION CONTROL MATERIALS WITHIN 7 DAYS OF FINAL GRADING. 8. TEMPORARY SEDIMENT TRAPPING DEVICES SHALL BE REMOVED FROM THE SITE WITHIN 30 DAYS OF FINAL

TWICE A YEAR, INSPECT OUTLET STRUCTURE AND DRAIN INLETS FOR ACCUMULATED DEBRIS. ALSO, REMOVE ANY

OUTLET STRUCTURE MUST BE INSPECTED TWICE A YEAR FOR EVIDENCE OF STRUCTURAL DAMAGE AND REPAIRED

UNSTABLE AREAS TRIBUTARY TO THE BASIN SHALL IMMEDIATELY BE STABILIZED WITH VEGETATION OR OTHER

SEDIMENT SHOULD BE REMOVED AFTER IT HAS REACHED A MAXIMUM DEPTH OF FIVE INCHES ABOVE THE STORMWATER

TOPSOIL

EXISTING TOPSOIL WILL BE REMOVED AND STORED IN PILES SUFFICIENTLY AS TO AVOID MIXING WITH OTHER EXCAVATION. STOCKPILES SHALL BE SURROUNDED BY EROSION CONTROL AS OUTLINED ON THESE PLANS. THE FURNISHING OF NEW TOPSOIL SHALL BE OF A BETTER OR EQUAL TO THE FOLLOWING CRITERIA (SS713.01 NYSDOT):

- 1. THE PH OF THE MATERIAL SHALL BE 5.5 TO 7.6.
- 2. THE ORGANIC CONTENT SHALL NOT BE LESS THAN 2% OR MORE THAN 70%.

3.	GRADATION:	SIEVE SIZE	<u>% PASSING BY WGT.</u>
	2	INCH	100
	1	INCH	85 TO 100
	1.	/4 INCH	65 TO 100
	Ν	O. 200 MESH	20 TO 80

PERMANENT VEGETATIVE COVER:

1.	SITE PREPARATION:

1.1. INSTALL EROSION CONTROL MEASURES

- 1.2. SCARIFY COMPACTED SOIL AREAS. 1.3. LIME AS REQUIRED TO PH 6.5.
- 1.4. FERTILIZE WITH 10-6-4 4 LBS/1,000 S.F.
- 1.5. INCORPORATE AMENDMENTS INTO SOIL WITH DISC HARROW

2.	SEED MIXTURES F	OR USE ON SWALES AND CUT AND FILL A	REAS.
	MIXTURE		LBS./ACRE
	ALT. A	KENTUCKY BLUE GRASS	20
		CREEPING RED FESCUE	28
		RYE GRASS OR REDTOP	5
	ALT. B	CREEPING RED FESCUE	20
		REDTOP	2
		TALL FESCUE/SMOOTH BLOOMGRASS	20

3. SEEDING

- 3.1. PREPARE SEED BED BY RAKING TO REMOVE STONES, TWIGS, ROOTS AND OTHER FOREIGN MATERIAL
- 3.2. APPLY SOIL AMENDMENTS AND INTEGRATE INTO SOIL.
- APPLY SEED UNIFORMLY BY CYCLONE SEEDER CULTI-PACKER OR HYDRO-SEEDER AT RATE 3.3. INDICATED.
- STABILIZE SEEDED AREAS IN DRAINAGE SWALES. 3.4.
- IRRIGATE TO FULLY SATURATE SOIL LAYER, BUT NOT TO DISLODGE PLANTING SOIL 3.5.
- SEED BETWEEN APRIL 1ST AND MAY 15TH OR AUGUST 15TH AND OCTOBER 15TH. 3.6. 3.7. SEEDING MAY OCCUR MAY 15TH AND AUGUST 15TH IF ADEQUATE IRRIGATION IS PROVIDED. **TEMPORARY VEGETATIVE COVER:**

- SITE PREPARATION: 1. INSTALL EROSION CONTROL MEASURES.
- 2. SCARIFY AREAS OF COMPACTED SOIL.
- 3. FERTILIZE WITH 10-10-10 AT 400/ACRE.
- 4. LIME AS REQUIRED TO PH 6.5.

SEED SPECIES

SEEDING

MIXTURE	LBS./ACRE		
RAPIDLY GERMINATING ANNUAL RYEGRAS	S		20
(OR APPROVED EQUAL)			
PERENNIAL RYEGRASS		20	
CEREAL OATS	36		

SAME AS PERMANENT VEGETATIVE COVER

CONSTRUCTION SEQUENCE

Refer to the Plan Set for all plans and details which relate to Construction Sequence.

- 1. Prior to the beginning of any site work the major features of the construction must be field staked by a licensed surveyor. hese include the building, limits of disturbance, utility lines, and stormwater practices. 2. Prior to the start of the project, an on-site pre-construction meeting will be held. this will be attended by the project owner, the operator responsible for complying with the approved construction drawings including the erosion and sediment control (E&SC) plan and details, the design engineer, the engineer responsible for E&SC monitoring during construction,
- town representatives from the engineering department and code enforcement. A licensed surveyor must define infrastructure locations, limits of disturbance, stormwater basin limits, and grades in the field prior to start of any construction. Limits of disturbance shall be marked with the installation of construction fence or
- approved equal. The extents of the stormwater management system shall be cordoned off to minimize the disturbance on this area. 4. Install all perimeter erosion control measures, construction entrance as shown on the Erosion and Sediment Control Plan and the associated Details. Install silt fencing at the bottom of slopes. The standards established in Part 1.B 1.b of the
- GP-015-002 included in appendix B of this SWPPP must be adhered to. 5. Strip site, clear vegetation, and place topsoil in stockpile locations shown on the plan.
- 6. Begin rough grading the site. Contractor to limit exposure of denuded soils by providing temporary stabilization for work areas that will remain undisturbed for over seven (7) days. Chipped rock that is not suitable to remain on site shall be hauled away and properly disposed of. An area has been provided for the stockpiling of removed soil and rock which is to be removed from the site.
- 7. Rough grade building, driveway, and parking area.
- 8. Begin construction of building.
- 9. Begin the excavation and installation of the stormwater management system. Protect trenches and open excavations from erosion. Entry into the system shall be blocked off until site has reached final stabilization. Once system has been installed, backfill, seed where necessary, and reinstall measures to cordon off the system from disturbance.
- 10. Begin installation of drainage system. Drainage shall be installed working downstream to up. 11. During site construction maintain and re-establish as required erosion control and stabilization measures as required by
- the site plan and details. 12. Excavate to the sub-grade level. Scarify the existing soil to a depth of 12-inches by rototilling or other means acceptable
- to the Engineer. Install all courses of stone as per the specifications given on the Plan.
- 13. Install base course of Item 4 in all pavement areas. Stabilize all open areas with seed and mulch. 14. Construct remainder of building, driveway and parking areas. First install curbs, asphalt binder, and concrete sidewalk. Once binder course is installed, drainage outlet may be unblocked.
- 15. Backfill curbs, grade, place final soil topping and put in place permanent vegetative cover over all disturbed areas, landscape beds, slopes, etc.
- 16. Once site stabilization has taken place (An area shall be considered to have achieved final stabilization when it has a minimum uniform 80% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements), remove all temporary erosion and sediment controls, unplug the drainage system to allow runoff to enter the stormwater management system.

Winter Stabilization Notes:

If construction activities are expected to extend into or occur during the winter season the contractor shall anticipate proper stabilization and sequencing. Construction shall be sequenced such that wherever possible areas of disturbance that can be completed and permanently stabilized shall be done by applying and establishing permanent vegetative cover before the first frost. Areas subject to temporary disturbance that will not be worked for an extended period of time shall be treated with temporary seed, mulch, and/or erosion blankets.









EXISTING GRADING **EXISTING SPOT GRADE** PROPOSED GRADING **PROPERTY LINE / RIGHT OF WAY** PROPOSED ROAD CENTERLINE PROPOSED CURB EDGE OF WETLAND

100' WETLAND BUFFER

EXISTING WATER LINE **EXISTING FIRE HYDRANT** PROPOSED FIRE HYDRANT

CONSERVATION EASEMENT LINE APPROX. AREA OF ROCK OUTCROP EXISTING STONE WALL EXISTING STONE WALLS TO BE REMOVED

EXISTING DRAINAGE INLET EXISTING SANITARY LINE EXISTING HEADWALL

PROPOSED DRAINAGE LINE

PROPOSED CATCH BASIN

PROPOSED DRAINAGE MANHOLE PROPOSED HEADWALL WITH RIP RAP PROPOSED FOOTING DRAIN PROPOSED ROOF DRAIN PROPOSED SEWER

PROPOSED WATER SERVICE CONNECTION

SERVICE CONNECTION

PROPOSED HOUSE AND DRIVE

PROPOSED SOIL STOCKPILES PROPOSED SILT FENCE PROPOSED CRUSHED STONE INLET PROTECTION

PROPOSED STABILIZED CONSTRUCTION ENTRANCE PROPOSED LIMIT OF DISTURBANCE

OWNER / OPERATOR CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): Title: Address: Phone: E-mail: Signature:





21-19 HOME & HEARTH\ENGINEERING\CAD\C3D-21-19 HOME & HEARTH\21-19 DETAILS.DWG 10/4/202

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW







SHALL CONSIST OF CLASS I (COMPACTED) OR CLASS II (MINIMUM 95% SPD) MATERIAL, WITH THE EXCEPTION THAT 60 INCH (1500 mm) SYSTEMS SHALL USE CLASS I MATERIAL ONLY. MINIMUM COVER HEIGHTS DO NOT ACCOUNT FOR PIPE BUOYANCY. REFER TO ADS TECHNICAL NOTE 5.05 "PIPE FLOTATION" FOR BUOYANCY DESIGN CONSIDERATIONS. MAXIMUM COVER OVER SYSTEM USING STANDARD BACKFILL IS 8 FT (2.4 m); CONTACT A REPRESENTATIVE WHEN MAXIMUM FILL HEIGHT MAY BE EXCEEDED. ADDITIONAL INSTALLATION REQUIREMENTS ARE PROVIDED IN THE DRAINAGE HANDBOOK SECTION 6 "RETENTION/DETENTION".

ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

18" X 90° MANIFOLD BEND [1898AN] W/ 12" STUB [1206AN] & 8" RISER [0803AN]





Ø12" ECC HIGH HDPE STUB

ITEM #: ITEM QTY: QTY PART

18" X 90° MANIFOLD BEND [1898AN] W/ 8" STUB [Standard_Stub] & 6" RISER [0603AN]

NOTE









Plant choices for the wetland expansion were made according to existing site conditions and locally common species. All planting will proceed by hand. Materials will be brought to the site in good condition (see below) and then placed in central drop locations. The materials will then be hand-carried to their planting locations and in turn, planted by hand. Only rounded, shallow planting shovels will be used in this effort.

Planting Details

Criteria for selecting plant material will include (1) the plant's ability to withstand the expected light and saturation conditions; (2) its demonstrated survival on this site and other nearby sites; (3) the plant must be native and non-invasive; and (4) whether the plant material is available at nurseries in the same region as the site. See Table 1 for complete plant species list. Seed mix was chosen based on the species' ability to survive in moist areas adjacent to the road with some sun.

Planting will be done in spring or early summer (between April 1 and July 1). Shrubs may also be planted in the late summer to early fall (September 1 to October 30). In all cases, a hole will be dug twice as deep as the root ball. The only shovels allowed are rounded, shallow spades. The hole will then be backfilled with a thin layer (two to four inches) of rich, organic topsoil, the plant placed inside, the hole backfilled to the top and then gently tamped down. Container-grown plant material delivered to the job site will be inspected to assure moist soil/root masses. Any dry and light weight plants will not be accepted. If not planted immediately the container will be stored out of the sun and wind and kept moist (i.e., a means of watering will be provided and watering will occur daily).

When removed from the containers, the plants will be the size of the specified container. If in leaf, the plants will appear healthy with no spots, leaf damage, discoloration, insects or fungus. If not in leaf, the buds will be firm and free of damage, discoloration, insects or fungus. Containers will be a minimum of quart size for shrubs and gallon size for trees. Plants not having an abundance of well developed terminal buds on the leaders and branches will be rejected. The stems and branches of all plants will be turgid and the cambium healthy or the plants rejected. Seeding within wetland areas should not be completed when there is more than two inches of standing water, or in areas that are likely to be flooded. Seeds should be broadcast by hand or knapsack seeder using the proper seeding rate (3.5 pounds per acre), and carefully proportioning seed for the entire area. Cover with a light layer of straw mulch following seeding.

		Plant Species Choices for V	Vetland Buffer Enhancement/Restora	ition
Map Symbol	Quantity*	Scientific Name	Common Name	Size
Trees				
Aru	4	Acer rubrum	Red Maple	5' - 6'
Ns	3	Nyssasylvatica	Black tupelo	5' - 6'
TP	6	Thuja plicata "Green Giant'	Western red cedar	6' - 7'
Shrubs				
CSe	23	Cornus sericea	Redosierdogwood	3' - 4'
AC	3	Amelanchier canadensis	Shadblow	4' - 5'
IV	19	llex verticillata	Winterberry holly	3' - 4'
SD	14	Salix discolor	Pussy willow	4' - 5'
VD	14	Viburnum dentatum	Arrowwood	4' - 5'
Herbaceous				
Plants				
CS	50	Carexstricta	Tussock sedge	2" plug
CC	50	Carex crinita	Fringed sedge	2" plug
JE	50	Juncus effusus	Soft rush	2" plug
Seed Mix				
SWM	8 pounds	Riparian Buffer Mix ERNMX-154 Or equivalent		

					PROJECT # 21-19	
	Site Design Consultants	Civil Engineers • Land Planners	251-F Underhill Avenue, Yorktown Heights, NY 10598	www.sitedesignconsultants.com		
Engineer:					Joseph C. Riina, P.E. NYS Lic. No. 64431	
Revisions:						
SCALE:	I = 70.	DRAWN BY: CS		DATE:	7/22/2021	
	Wetland Ruffer	Enhancement Dlan				
SITE PLAN	HOME & HEARTH			1 / JU East Main Street	Town of Yorktown Westchester County, NY	



Buffer Mitigation Plan prepared by Steve Marino, PWS Tim Miller Associates, Inc. 10 North Street, Cold Spring NY 10516 845 265 4400



10 20

SCALE: 1"=20'-0"

SAFE DIG

Before You Dig, Drill or Blast!

CALL US TOLL FREE B11 or 1-800-962-7962 NY Industrial Code Rule 753 requires no less than two working days notice, but not more than ten days notice.

0

40



COPYRIGHT STATEMENT THIS DRAWING AND THE DESIGNS THEREON ARE THE PROPERTY OF ROBERT E. PHELAN AND ARE PROTECTED UNDER FEDERAL COPYRIGHT LAWS, AND THUS ARE COPYRIGHTED. NO REPRODUCTION, COPY, DUPLICATION OR USE WITHOUT PRIOR WRITTEN PERMISSION OF ROBERT E. PHELAN IS ALLOWED. UNAUTHORIZED USE SHALL INVITE A CLAIM FOR COMPENSATION BY ROBERT E. PHELAN AND SUCH MISUSE WILL BE AGRESSIVELY PURSUED.

24)

DRAWING STATUS	BY	DATE
O PRELIMINARY		
O CLIENT APPROVAL		
O CONTRACT DRAWING		
O PERMIT APPLICATION		
O MUNICIPAL APPROVAL		
O NOT FOR CONSTRUCTION		1.00
O CONSTRUCTION ISSUE		
O PRODUCT ORDER		

REVISION		BY	DATE
ELEVATION A	ž,	REP.	12-1-2021
	4		
na na fan an fan San An Anna an		1	
		1	
	9991211219, surgitures		
nan dia mampina dia mampina mpikambana amin'ny fisiana amin'ny fisiana amin'ny fisiana amin'ny fisiana dia mamp	an a		
an ya ayan yan an ay bar ya a angar ay an alan an a sa a an			



.



ROBERT E. PHELAN 755 DELANO ROAD, YORKTOWN HEIGHTS, NEW YORK 10598

REPHELAN@OPTONLINE.NET

914 - 391 - 6925

AUXILLARY BUILDING - STORAGE

HOME & HEARTH

1750 EAST MAIN STREET YORKTOWN HEIGHTS, NEW YORK 10598

DATE: 8/7/2021

Matthew Slater Town Supervisor

RECEIVED

TOWN OF YORKTOWN CONSERVATION BOARD

Town of Yorktown Town Hall, 363 Underhill Avenue, Yorktown Heights, New York 10598, Phone (914) 962-5722

MEMORANDUM

To:	Planning Board	PLANNING DEPARTMENT
From	Conservation Record	OCT 25 2021
riom.	Conservation Board	TOWN OF YORKTOWN
Date:	10/21/2021	
Re:	Home & Hearth 1750 East Main Street	

The Conservation Board at its October 20, 2021 meeting discussed Home & Hearth located at 1750 East Main Street with Joe Riina of Site Designs and Steve Marino of Tim Miller Associates. The Conservation Board has the following comments:

• The Mitigation Plan looks appropriate and the Conservation Board recommends the project moves forward.

Respectfully submitted:

Phyllis Bock

For the Conservation Board

CC: Town Board Planning Board Supervisors Office Engineering Dept. Applicant

TB Referral 1770 East Main St

TOWN OF YORKTOWN TOWN BOARD

FEB 2 3 2022

Resolved, the Town Clerk is authorized to refer out to appropriate agencies for their review and/or recommendation an application for a Special Use Permit for a gas station located at 1770 East Main Street, Mohegan Lake, NY for a site plan amendment.

Further Resolved, the Town Board declares its intent to act as Lead Agency. We are transmitting the following referral for your review and recommendations and ask that you respond back to the Town Clerk by March 11, 2022.

TO:

File Town Clerk ABACA Building Inspector Community Housing Board Conservation Board Fire:	Westchester County Planning Department / Board Dept. of Public Works Dept. of Health Parks & Recreation Environmental Facilities Soil & Water
Lake Mohegan Vorktown Highway Dept. Open Space Committee	New York State DEC Albany DEC New Paltz (Region III) DOT
Planning Dept. / Board (6) Police Dept. Public Safety Committee Recreation Commission School District:	NYC DEP Army Corp. of Engineers
Lakeland Town Attorney Town Board Town Engineer Tree Conservation Advisory Committee	Bordering Municipality Town of Cortlandt Town of Ossining Town of Somers Town of Putnam Valley
Water Department Wetlands Inspector Yorktown Land Trust	Yorktown Chamber of Commerce Other Other – CSC Task Force

FROM: DIANA L. QUAST, YORKTOWN TOWN CLERK, CERTIFIED MUNICIPAL CLERK

SUBJECT: We are transmitting the following: Application and plans for Special Use Permit for gas station located at 1770 East Main Street, Mohegan Lake, NY.

DATE: February 23, 2022

Application/Petition	Repor	rt
🔀 Drawings	Wetla	inds Permit Application
🗌 EAF	SEQF	RA Scope
EAF Addendum	Other	- Proposed Local Law
FOR YOUR: \square Information	Review	Comment

Diana L. Quast, Town Clerk dquast@yorktownny.org



Registrar of Vital Statistics Telephone: (914) 962-5722 x 208 Fax: (914) 962 6591

TOWN OF YORKTOWN 363 Underhill Avenue, P.O. Box 703 Yorktown Heights, NY 10598

This is a resolution adopted by the Town Board of the Town of Yorktown at its regular meeting held on Tuesday, February 22, 2022.

RESOLVED, that the Town Clerk is authorized to refer out the following applications received by BP Gas Station, 1770 East Main Street and 7-Eleven, 3451 Crompond Road to amend their Site Plans - Gasoline Station.

na I. Quast

Diana L. Quast, Town Clerk Certified Municipal Clerk Town of Yorktown

Date: February 23, 2022

To: Diana L. Quast, Town Clerk

cc: Matthew J. Slater, Town Supervisor Patricia Caporale, Town Comptroller Adam Rodriguez, Town Attorney file

APPLICATION FOR SPECIAL USE PERMIT GASOLINE STATIONS

Dated: _____

TO: THE TOWN BOARD c/o TOWN CLERK 363 UNDERHILL AVENUE YORKTOWN HEIGHTS, NEW YORK 10598

	The	undersigned,	as	owner	of	certain	premises	located	on	the	north	S	ide	of
East N	lain St	reet				and k	nown as	Section	15.1	6	, Parcel	1		,
Lot_4	6	on th	ne Ta	ax Map c	of th	e Town o	of Yorktow	rn, does he	ereby	/ make	e application for	r a Spec	ial U	Jse

Permit:

- ____ Canopy
- X Convenience Store
- ____ Truck Rental
- ____ Car Wash
- Sign

In the event the Permit is issued, the applicant will comply with all the requirements of the Zoning Ordinance and the Building Department Ordinance of the Town of Yorktown and with the requirements of any other local laws or ordinances, laws, rules and regulations of any Federal, State and County Government, bureau or department thereof having jurisdiction over said premises and the business to be conducted there at, in addition to such terms or conditions as may be imposed by the Town Board.

Attached hereto are twenty copies of the plot plan of the area prepared by ______ J. Henry Carpenter & Co.

		and dated,
and building plans prepared by Neil Carnow	aia Archi	tect
and dated 02/07/2022		, all of which are made part of this application, together
with the required fee of \$1500.00 .		
Mohegan Lake Gas Mart, Inc.		25 St. Charles Street
Applicant		Address Thornwood, NY
		(914) 438-6125 (Neil Carnow)
		Day Time Telephone No.
Application received on the	_day of _	20
Fee of \$1500.00 received on the	day of	20







TITLE No.: 10-26087

TB Referral 3451 Crompond Rd

Applicant requested to be on next agenda instead.