Dave Paganelli

Superintendent of Highways Town of Yorktown 281 Underhill Avenue Yorktown Heights, NY 10598 Telephone (914) 962-5781 Fax (914) 243-4285

- 1. All excavated material to be replaced with N.Y.S. Item #4 and compacted in one foot lifts. In certain instances K-Crete or equivalent self-levelling aggregate may be required at Highway Superintendent's discretion.
- 2. All excavated areas must be protected, when job is left unattended, with barriers, flashing lights, etc. until the job is completed.
- 3. A temporary patch should be installed over all excavated areas upon completion of backfilling operations and delineate by Bump signs, 75' to 100' on either side of maintained excavation until finish asphalt work has been done.
- 4. Final patching should be made by cutting back a minimum of one (1) foot beyond the trench area. All cuts to be straight with squared off ends. Pavement replacement shall conform to the type and depth of the surrounding pavement.
- 5. Proof of adequate liability insurance must be produced before a Street Opening permit can be issued.
- 6. All finished patches must be seam sealed
- 7. Sweep Road with mechanical Sweeper may be required at the end of each work day.
- 8. Clear all catch basins downstream may be required.
- 9. No Roadway to be opened or unfinished after November 1st and before April 15th.

Signed By:	
Address:	
Telephone#:	

PLEASE NOTE:

A CODE 53 MUST BE CALLED & WORK NUMBER SUBMITTED TO THE HIGHWAY DEPARTMENT BEFORE A STREET OPENING PERMIT CAN BE ISSUED. THE NUMBER TO CALL IS 1-800-962-7962

<u>PLEASE NOTE:</u> IF THE ABOVE REQUIREMENTS ARE NOT MEET, PENALTIES WILL INCUR.