

Plant choices for the wetland expansion were made according to existing site conditions and locally common species. All planting will proceed by hand. Materials will be brought to the site in good condition (see below) and then placed in central drop locations. The materials will then be hand-carried to their planting locations and in turn, planted by hand. Only rounded, shallow planting shovels will be used in this effort.

Criteria for selecting plant material will include (1) the plant's ability to withstand the expected light and saturation conditions; (2) its demonstrated survival on this site and other nearby sites; (3) the plant must be native and non-invasive; and (4) whether the plant material is available at nurseries in the same region as the site. See Table 1 for complete plant species list. Seed mix was chosen based on the species' ability to survive in moist areas adjacent to the road with some sun.

Planting will be done in spring or early summer (between April 1 and July 1). Shrubs may also be planted in the late summer to early fall (September 1 to October 30). In all cases, a hole will be dug twice as deep as the root ball. The only shovels allowed are rounded, shallow spades. The hole will then be backfilled with a thin layer (two to four inches) of rich, organic topsoil, the plant placed inside, the hole backfilled to the top and then gently tamped down. Container-grown plant material delivered to the job site will be inspected to assure moist soil/root masses. Any dry and light weight plants will not be accepted. If not planted immediately the container will be stored out of the sun and wind and kept moist (i.e., a means of watering will be provided and watering will occur daily).

When removed from the containers, the plants will be the size of the specified container. If in leaf, the plants will appear healthy with no spots, leaf damage, discoloration, insects or fungus. If not in leaf, the buds will be firm and free of damage, discoloration, insects or fungus. Containers will be a minimum of quart size for shrubs and gallon size for trees. Plants not having an abundance of well developed terminal buds on the leaders and branches will be rejected. The stems and branches of all plants will be turgid and the cambium healthy or the plants rejected. Seeding within wetland areas should not be completed when there is more than two inches of standing water, or in areas that are likely to be flooded. Seeds should be broadcast by hand or knapsack seeder using the proper seeding rate (3.5 pounds per acre), and carefully proportioning seed for the entire area. Cover with a light layer of straw mulch following seeding.

/lap Symbol	Quantity*	Scientific Name	Common Name	Size
Trees				
Aru	4	Acer rubrum	Red Maple	5' - 6'
Ns	3	Nyssasylvatica	Black tupelo	5' - 6'
TP	6	Thuja plicata "Green Giant'	Western red cedar	6' - 7'
Shrubs				
CSe	23	Cornus sericea	Redosierdogwood	3' - 4'
AC	3	Amelanchier canadensis	Shadblow	4' - 5'
IV	19	llex verticillata	Winterberry holly	3' - 4'
SD	14	Salix discolor	Pussy willow	4' - 5'
VD	14	Viburnum dentatum	Arrowwood	4' - 5'
Herbaceous				
Plants				
CS	50	Carex stricta	Tussock sedge	2" plug
CC	50	Carex crinita	Fringed sedge	2" plug
JE	50	Juncus effusus	Soft rush	2" plug
Seed Mix				1
		Riparian Buffer Mix ERNMX-154		
SWM	8 pounds	Or equivalent		




Steve Marino, PWS

Tim Miller Associates, Inc.
h Street, Cold Spring NY 10
845 265 4400 Buffer


	Date Comments: 11/12/21 Plan Updates	2/15/22 PD Memo 3/14/23 Lighting Update			
Revisions:	Date 11/12/21	2/15/22 3/14/23			
Revi	No.	3,5			
SCALE:	########	YM YOU AND	DKAWN BY:	DATE:	7/28/21

DRAWN BY:	DATE:	7/28/21
		Vew York



Before You Dig, Drill or Blast!

CALL US TOLL FREE 811 or 1-800-962-75



### **GENERAL PLANTING NOTES**

REQUIRED BY THE DRAWINGS, THE LARGER NUMBER SHALL APPLY.

- . ALL PLANTING MATERIAL TO BE NURSERY GROWN STOCK SUBJECT TO APPLICABLE A.N.L.A STANDARDS. 2. THE CONTRACTOR SHALL SUPPLY ALL PLANTS IN QUANTITIES SUFFICIENT TO COMPLETE THE WORK SHOWN ON THE DRAWINGS AND LISTED IN THE PLANT LIST. IN THE EVENT OF A DISCREPANCY BETWEEN QUANTITIES SHOWN IN THE PLANT LIST AND THOSE
- 3. ALL PLANTS SHALL BE APPROVED PRIOR TO INSTALLATION AND SHALL BE LOCATED ON SITE BY THE CONTRACTOR, FOR THE APPROVAL OF THE LANDSCAPE ARCHITECT. ANY INSTALLATIONS WHICH WERE NOT PRE-APPROVED AND WHICH ARE SUBSEQUENTLY REQUESTED TO BE MOVED, WILL BE DONE AT THE CONTRACTORS EXPENSE.
- 4. PRECISE LOCATION OF ITEMS NOT DIMENSIONED ON THE PLAN ARE TO BE FIELD STAKED BY THE CONTRACTOR AND SHALL BE
- SUBJECT TO THE REQUIREMENTS SPECIFIED IN THE PREVIOUS NOTE. 5. THE CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGED VEGETATION AND SHALL REPLACE OR REPAIR ANY DAMAGE AT HIS OWN
- 6. ALL PLANTING AREAS SHALL HAVE A CONTINUOUS BED OF TOPSOIL 18" DEEP.
- 7. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES IN THE FIELD. WHERE PLANT MATERIAL MAY INTERFERE WITH UTILITIES, THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT TO COORDINATE THEIR INSTALLATION.
- 8. PLANTINGS INSTALLED IN THE DRY SUMMER MONTHS AND /OR LAWN SEEDED OUT OF SPRING OR FALL PERIODS, IF ALLOWED BY OWNER, WILL REQUIRE AGGRESSIVE IRRIGATION PROGRAMS AT THE CONTRACTOR'S EXPENSE, UNLESS OTHERWISE DIRECTED BY THE OWNER.
- 9. SUBSTITUTIONS PERMITTED ONLY UPON WRITTEN APPROVAL OF THE OWNER'S REPRESENTATIVE. 10. PLANT TAGS TO REMAIN ON ALL PLANT MATERIAL UNTIL FINAL ACCEPTANCE. CONTRACTOR TO THEN REMOVE ALL PLANT TAGS. 11. WHERE A SIZE RANGE IS GIVEN IN THE PLANT SCHEDULE, AT LEAST 50% OF THE PLANTS PROVIDED SHALL BE OF THE LARGER SIZE.
- 12. CONTRACTOR TO GUARANTEE ALL PLANT MATERIAL FOR ONE YEAR AFTER DATE OF FINAL ACCEPTANCE. 13. CONTRACTOR TO MAINTAIN ALL PLANT MATERIAL UNTIL 60 DAYS AFTER FINAL ACCEPTANCE.
- 14. ALL SHRUB AND TREE PITS SHALL BE MULCHED TO A DEPTH OF 3" WITH SHREDDED PINE BARK MULCH.
- 15. TOPSOIL AND SEED ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES AND NOT COVERED BY OTHER SITE IMPROVEMENTS. 16. CONTRACTOR TO VERIFY ALL SITE CONDITIONS IN FIELD PRIOR TO THE START OF CONSTRUCTION.
- 17. FIELD REVISIONS TO PLANT MATERIAL LOCATION AND MATERIAL SUBSTITUTIONS WILL BE PERMITTED IF CONFLICTS ARISE. CONTRACTOR TO NOTIFY LANDSCAPE ARCHITECT IF CHANGE IS REQUIRED.
- 18. LANDSCAPE ARCHITECT TO CERTIFY THAT THE WORK ON THE SITE HAS BEEN IN ACCORDANCE WITH THE APPROVED PLAN ON FILE WITH THE TOWN PRIOR TO THE ISSUANCE OF C.O.

#### RAIN GARDEN TOPSOIL NOTES

- 1. MANMADE TOPSOIL SHALL CONSIST OF A MIXTURE OF 40% SAND AND 60% EQUAL VOLUMES OF ORGANIC AND MINERAL MATERIALS. WELL-DECOMPOSED CLEAN LEAF COMPOST IS THE PREFERRED SOIL AMENDMENT TO ACHIEVE THESE STANDARDS. NOTE THE "CLEAN" REFERS BOTH TO THE LACK OF PHYSICAL CONTAMINANTS SUCH AS PLASTIC AND TO THE LACK OF CHEMICAL CONTAMINANTS.
- 2. TOPSOIL CAN BE A SOURCE OF INVASIVE SPECIES SEEDS. PROVIDE INFORMATION ON THE SOURCE AND THE LIKELIHOOD THAT SUCH SEEDS ARE
- 3. TWELVE OR MORE INCHES OF NATURAL OR MANMADE TOPSOIL SHOULD BE USED. MANMADE TOPSOIL USED FOR THE BASINS SHOULD CONSIST OF A MIXTURE OF EQUAL VOLUMES OF ORGANIC AND MINERAL MATERIALS. THIS MAY BE ACCOMPLISHED BY ADDING A SPECIFIC DEPTH OF ORGANIC MATERIAL AND DISKING IT IN TO TWICE THAT DEPTH.

### SEED MIXES:

**GENERAL SEED MIX: (OTION TO SOD)** 

WATER STAR ULTRA MIXTURE AS SUPPLIED BY PLANTER CHOICE NURSERY, OR APPROVED EQ.

30% Razor Creeping Red Fescue 20% Interga Perennial Ryegrass 20% APR 2015 Perennial Ryegrass 10% Survivor Chewings Fescue 10% Soprano Perennial Ryegrass 10% Blue Bonnet Kentucky Blue

#### **EROSION CONTROL MIX:**

50# per 12,500 sq. ft.

NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR DRY SITES AS SUPPLIED BY NEW ENGLAND WETLAND PLANTS, INC., OR APPROVED EQ.

SPECIES: Creeping Red Fescue, (Festuca rubra), Canada Wild Rye, (Elymus canadensis), Annual Ryegrass, (Lolium multiflorum), Perrenial Ryegrass, (Lolium perenne), Blue Grama, (Bouteloua gracilis), Little Bluestem, (Schizachyrium scoparium), Indian Grass, (Sorghastrum nutans), Rough Bentgrass, (Agrostis scabra), Upland Bentgrass, (Agrostis perennans).

APPLICATION RATE: 35 lbs/acre 1250 sq. ft/lb

## WET MIX:

ERNMX 180 - RAIN GARDEN MIX AS SUPPLIED BY ERNST SEED, OR APPROVED EQ.

33.4% SCHIZACHYRIUM SCOPARIUM, 'ITASCA' LITTLE BLUESTEM, 'ITASCA' 20.0% ELYMUS VIRGINICUS VIRGINIA WILDRYE 7.0% CAREX VULPINOIDEA FOX SEDGE 5.6% CHASMANTHIUM LATIFOLIUM RIVER OATS 5.5% ECHINACEA PURPUREA PURPLE CONEFLOWER 3.0% CHAMAECRISTA FASCICULATA PARTRIDGE PEA 3.0% COREOPSIS LANCEOLATA LANCELEAF COREOPSIS 3.0% PANICUM CLANDESTINUM, TIOGA DEERTONGUE, TIOGA 3.0% PANICUM RIGIDULUM REDTOP PANICGRASS 3.0% RUDBECKIA HIRTA BLACKEYED SUSAN 3.0% VERBENA HASTATA **BLUE VERVAIN** 2.0% HELIOPSIS HELIANTHOIDES OXEYE SUNFLOWER 1.8% ASCLEPIAS INCARNATA SWAMP MILKWEED BLUNT BROOM SEDGE 1.0% CAREX SCOPARIA 1.0% SENNA HEBECARPA WILD SENNA 0.7% PYCNANTHEMUM TENUIFOLIUM NARROWLEAF MOUNTAINMINT 0.5% ASTER NOVAE-ANGLIAE NEW ENGLAND ASTER 0.5% ASTER PRENANTHOIDES ZIGZAG ASTER 0.5% BAPTISIA AUSTRALIS BLUE FALSE INDIGO 0.5% ZIZIA AUREA GOLDEN ALEXANDERS 0.4% MONARDA FISTULOSA WILD BERGAMOT COMMON SNEEZEWEED 0.3% HELENIUM AUTUMNALE 0.3% JUNCUS TENUIS PATH RUSH

0.2% EUPATORIUM PERFOLIATUM BONESET SOFT RUSH 0.2% JUNCUS EFFUSUS 0.2% OENOTHERA FRUTICOSA SUNDROPS GRAY GOLDENROD 0.2% SOLIDAGO NEMORALIS 0.2% SOLIDAGO RUGOSA WRINKLELEAF GOLDENROD

SEEDING RATE: 20 LB PER ACRE WITH A COVER CROP OF GRAIN RYE AT 30 LB PER ACRE

THE NATIVE PERENNIAL FORBS AND GRASSES PROVIDE FOOD AND COVER FOR RAIN GARDEN BIODIVERSITY.

PLANT SCHEDULE							
CATEGORY	SYM.	NO.	BOTANICAL NAME	COMMON NAME	SIZE	COND.	
04NODY TDEE0	ARB	1	ACER RUBRUM 'BOWHALL	BOWHALL MAPLE	3" CAL.	B&B	
CANOPY TREES	NS	2	NYSSA SYLVATICA 'WILDFIRE'	WILDFIRE SOUR GUM	3" CAL.	B&B	
ORNAMENTAL	cc	1	CERCIS CANADENSIS	EASTERN REDBUD	2.5" CAL.	B&B	
TREES	MV	1	MAGNOLIAVIRGINIANA 'JIM WILSON'	MOONGLOW MAGNOLIA	12'-14' HT.	B&B	
	AV	13	AZALEA VISCOSUM	SWAMP AZALEA	3 GAL.	CONT.	
	AG	2	AMELANCHIER X. GRANDIFLORA 'AUTUMN BRILLIANCE'	AUTUMN BRILLIANCE SERVICEBERRY	5'-6' HT.	B&B	
	co	2	CEPHALANTHOS OCCIDENTALIS	BUTTONBUSH	6 GAL.	CONT.	
	CA	5	CLETHRA ALNIFOLIA	SUMMERSWEET	3 GAL.	CONT.	
	HA	7	HYDRANGEA ARBORESCENS 'INCREDIBALL BLUSH'	INCERDIBALL BLUSH HYDRANGEA	3 GAL.	CONT.	
SHRUBS	HQ	1	HYDRANGEA QUERCIFOLIA 'ALICE'	ALICE OAKLEAF HYDRANGEA	6 GAL.	CONT.	
	HQM	11	HYDRANGEA QUERCIFOLIA "MUNCHKIN"	MUNCHKIN OAKLEAF HYDRANGEA	3 GAL.	CONT.	
	IC	6	ILEX CRENATA 'SCHWOEBEL EXCELSA'	SCHWOEBEL EX. HOLLY	3'-4' HT.	CONT.	
	IG	14	ILEX GLABRA 'DENSA'	DENSA INKBERRY	3 GAL.	CONT.	
	IGS	14	ILEX GLABRA 'STRONG BOX'	STRONG BOX DWARF INKBERRY	3 GAL.	CONT.	
	PF	29	POTENTILLA FRUITICOSA 'PINK BEAUTY'	PINK BEAUTY POTENTILLA	3 GAL.	CONT.	
	VP	1	VIBURNUM PLICATUM F. TOMENTOSUM 'SHASTA'	SHASTA VIBURNUM	5'-6' HT.	CONT.	
	An	8	ASTER NOVAE-ANGLIAE 'VIBRANT DOME'	VIBRANT DOME ASTER	1 GAL.	CONT.	
	Ср	255	CAREX PENNSYLVANICA	PENNSYLVANIA SEDGE	4" POT.	CONT.	
HERBACEOUS	Es	18	ERAGROTIS SPECTABALIS	PURPLE LOVEGRASS	1 GAL.	CONT.	
	He	3	HEMOROCALLIS 'ALWAYS AFTERNOON'	ALWAYS AFTERNOON DAYLILY	1 GAL.	CONT.	
	Hes	3	HEMEROCALLIS 'STRAWBERRY CANDY'	STRAWBERRY CANDY DAYLILY	1 GAL.	CONT.	

## GENERAL MAINTENANCE PLAN

- 1. ALL TREES TO BE PRUNED AND MAINTAINED TO A BRANCHING HEIGHT OF 8' ABOVE FINISH GRADE.
- PRUNE SHRUB MATERIAL SEASONALLY AS REQUIRED.
- 3. REMOVE DEAD OR BROKEN BRANCHES TO MAINTAIN HEALTH AND AESTHETICS OF MATERIAL ON AN AS NEEDED BASIS.

MULCH ANNUALLY IN SPRING AS SPECIFIED IN GENERAL PLANTING 5. REPLACE ANY DEAD PLANT MATERIAL ON AN AS NEEDED BASIS TO

- MAINTAIN AESTHETICS.
- 6. WEEDING SHOULD HAPPEN ON A CONSISTENT BI-WEEKLY BASIS.

SEE PLANS PREPARED BY SITE DESIGN CONSULTANTS UTILITIES, EASEMENTS, SITE, GRADING & DRAINAGE DESIGN.

NEW PLANT MATERIAL TO BE LAID OUT IN FIELD BY LANDSCAPE ARCHITECT.

SEED ALL DISTURBED AREAS WITH GENERAL SEED MIX UNLESS OTHERWISE NOTED.

PER ABACA MEMO DATED 2.13.23 REVISION:

30 Rocky Hill Rd.



New Fairfield, CT

P: 845.531.1504 E: abigail@a2land.com W: www.a2land.com

A2 Land Consulting, LLC

SCALE:

SHEET:

PROJ #: 2226

WG FILE: 2226LA

LI

3.14.22

l" = 20'

# PLANTING PLAN

1750 E. MAIN ST.

TOWN OF YORKTOWN WESTCHESTER COUNTY



MOHEGAN LAKE **NEW YORK** 


DESIGN CONSULTANTS ON MARCH 14, 2022.

1 inch = 20 ft.

CONTRACTOR TO VERIFY ALL SITE CONDITIONS IN FIELD PRIOR TO THE START OF CONSTRUCTION. 3. FIELD REVISIONS TO PLANT MATERIAL LOCATION AND MATERIAL SUBSTITUTIONS WILL BE PERMITTED IF CONFLICTS ARISE. CONTRACTOR

TO NOTIFY LANDSCAPE ARCHITECT IF CHANGE IS REQUIRED.


BASE INFORMATION TAKEN FROM AUTOCAD BASE FILE SENT FROM SITE



Schedule								
Symbol La	bel Manufac	turer	Catalog	Description	Number Lamps	Lamp Output	LLF	Input Power
	L1	Lithonia Lighting	DSX0 LED P1 40K BLC MVOLT	DSX0 LED P1 40K BLC MVOLT	1	3862	0.9	38
	W1	Lithonia Lighting	DSXW1 LED 10C 700 40K TFTM MVOLT	DSXW1 LED WITH (1) 10 LED LIGHT ENGINES, TYPE TFTM OPTIC, 4000K, @ 700mA.	1	2808	0.9	26.2
$\bigcirc$	L2			PHOTOPIA - LMH2 - DOMED LENS - WHS	1	3000	0.9	38
	L3	Lithonia Lighting	QTE LED P1 40K 120 THK DDB	Flood 2500lm	48	2475	0.9	24.2
$\bigcirc$	L4	Gotham Architectural Lighting	EVO4 35/35 AR MWD LD EV	O 4IN ROUND DOWNLIGHT, 80 CRI, 3500K, 3500LM, MED WIDE DIST, CLEAR MATTE DIFFUSE	1	3071	0.9	38.4

Statistics						
Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
Property Line Trespass	+	0.2 fc	4.5 fc	0.0 fc	N/A	N/A
Parking Area	+	2.1 fc	10.3 fc	0.0 fc	N/A	N/A

- 1. THESE LIGHTING CALCULATIONS ARE NOT A SUBSTITUTE FOR INDEPENDENT ENGINEERING ANALYSIS OF LIGHTING SUITABILITY AND SAFETY.
- 2. THIS PHOTOMETRICS LAYOUT WAS CALCULATED USING SPECIFIC CRITERIA, ANY DEVIATION FROM STATED PARAMETERS WILL AFFECT ACTUAL PERFORMANCE. 3. ALL QUANTITIES ARE BASED ON FIXTURES SHOWN IN THE LIGHTING CALCULATIONS ONLY.
- 4. THESE CALCULATIONS ARE BASED ON LISTED FIXTURES ONLY. SUBSTITUTION OF THESE FIXTURES VOIDS ALL CALCULATIONS.
- 5. ALL SUBSTITUTIONS REQUIRE NEW CALCULATIONS BASED ON THE FIXTURES SUPPLIED. 6. ACTUAL LIGHT LEVELS MAY VARY DUE TO ACTUAL FIXTURE LOCATIONS AND FIELD CONDITIONS.
- 7. FJC RESERVES THE RIGHT TO WITHDRAW THESE CALCLATIONS FROM THE PUBLIC RECORD IF THE PRODUCT SPECIFIED ON THESE PLANS IS SUBSTITUTED.





QTE LED			120		
Sarias	Performance Package	Color Temperature	Voltage	Mounting	Finish (requires)
QTE LED	P1 2,500 lumens, 25W1	40K 4000K* 50K 5000K	<b>120</b> 120 Volts	YK Yoke mount <sup>2</sup>	DDB Dark bronze
OTE LED P1 version, can be used for submission to Title 24 applications     Voke mount is not available with P1.					
FEATURES & SPI	ECIFICATIONS				

FEATURES & SPECIFICATIONS	
INTENDED USE  OTE LED is suitable for replacing up to 500W Quartz Halogen. It is ideal for landscape, signage, and general purpose lighting in commercial and residential applications.	INSTALLATION Mounts easily to junction
CONSTRUCTION	UL Certified to US and
Die-cast aluminum housing has integral heat sink fins to optimize thermal management. Rated for - 40°C to 40°C ambient temperature. Tempered glass lens is fully gasketed.	DesignLights Consortiugualified.Please check
Available with knuckle and yoke mount.	which versions are qual LED light Source Requi
FINISH Durable powder coat finish for protection from corrosion and weathering. Available in dark bronze.	WARRANTY 5-year limited warranty. specification sheet creater
ELECTRICAL Chip-on-board (COB) LEDs are directly coupled to the housing to maximize heat dissipation	are disclaimed. Comple terms-and-conditions
and lifespan (L70 / 50,000 hrs). 6kV surge protection.	<b>Note:</b> Actual performa All values are design or Specifications subject t

LITHONIA
COMMERCIAL OUTDOOR
One Lithonia Way • Conyers, Georgia 30012 • Phone: 800-705-SERV (7378) • www.lithonia.com
© 2018-2022 Acuity Brands Lighting, Inc. All rights reserved

General Illumination Layer I EVO High Center Beam Layer I Incito Downlight Adjustable Open Leased Cylinder Pinhole Bevel Hyperbolic

Available with 10% dimming, 1% dimming, or dim to dark

ENERGY STAR® certified product

Catalog Number:

BAA CONTROL CO

**②** gotham° | E ∨ ○°

Bounding Ray™ optical design

\*Based on 3500K AR LSS MWD 80CRI

45° cutoff to source and source image

 2.5 MacAdam Ellipse; 85 CRI typical, 90+ CRI optional Fixtures are wet location, covered ceiling


Multiple Layers of Light


General Illumination Round Downlight 4"


Unitized optics mechanically attach the light engine to the lower reflector for complete optical alignment.
 Batwing distribution with feathered edges provides even illumination on horizontal and vertical surfaces

Fully serviceable and upgradeable lensed LED light engine
 70% lumen maintenance at 60,000 hours
 2.5 Mar-Afran Filinse- 95 CRI thorical QNL CRI orbitonal
 UGR of zero for fixtures aimed at nadir with a cut-off equal to or less than 60deg per CIE 117-1995 Discomfort Glare in Interior Lighting. UGR FAQ

Designer AMG, LC Date 03/08/2023







JIGHTIN( PLAN

1750

Before You Dig, Drill or Blast!

CALL US TOLL FREE 811 or 1-800-962-7962

NY Industrial Code Rule 753 requires no less than two working days notice, but not more than ten days notice.

www.diosafelynew.ork.com

10 SCALE: 1"=20'-0"

#### **GENERAL NOTES:**

- . THE ENGINEER WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION SUBSEQUENTLY, HE IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION
- PRACTICES, PROCEDURES, AND RESULTS THEREFROM. THE ENGINEER SHALL NOT BE HELD RESPONSIBLE OR HELD ACCOUNTABLE FOR THE INTEGRITY OF ANY STRUCTURES CONSTRUCTED
- OR UNDER CONSTRUCTION PRIOR TO THE APPROVAL OF THE PLANS. THE VILLAGE ENGINEER'S OFFICE AND WATER DISTRICT OFFICE IS TO BE NOTIFIED 24 HOURS BEFORE COMMENCING SITE
- CONSTRUCTION OR WATER MAIN CONNECTION. 4.  $\,$  ALL WORK IS TO BE IN ACCORDANCE WITH THE VILLAGE CODE OF PRACTICE AND SPECIFICATIONS.
- 5. ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES
- ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER WHOSE SEALAPPEARS ON THESE DRAWINGS. ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT.
- 7.  $\,$  ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS
- 8. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL IN A "CODE 53" PRIOR TO CONSTRUCTION FOR UNDERGROUND UTILITY
- LOCATIONS. 9. SUBSTRUCTURES AND THEIR ENCROACHMENTS BELOW GRADE. IF ANY, ARE NOT SHOWN.
- ). ANY PROPOSED ELECTRIC AND/OR TELEPHONE SERVICE LINES ARE TO BE PLACED UNDERGROUND.
- 10. THE DESIGN ENGINEER DISCLAIMS ANY LIABILITY FOR DAMAGE OR LOSS INCURRED DURING OR AFTER CONSTRUCTION. 11. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE

#### CONTRACTOR RESPONSIBILITIES:

SITUATION AND MODIFY THE PLAN AS NECESSARY.

- 1. ALL WORK ON THE PROJECT SHALL BE PERFORMED IN A WORKMAN LIKE  $\,$  MANNER AND SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE INDUSTRY. THE OWNER WILL BE THE SOLE JUDGE OF THE ACCEPTABILITY OF THE WORK. MATERIALS AND WORK DEEMED UNACCEPTABLE WILL BE REMOVED AND REDONE AT THE SOLE COST AND RESPONSIBILITY OF THE CONTRACTOR.
- . THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGES DUE TO HIS ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEE, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY THE WORK UNDER A SEPARATE CONTRACT WITH THE CONTRACTOR.
- 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROPERLY SHORE EXISTING UTILITIES IF REQUIRED BY CONSTRUCTION.
- 4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE THE BUILDING INSPECTOR IN ADVANCE OF HIS WORK OR AS THE
- 5. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY
- 6. ALL CHANGES MADE TO THIS PLAN SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY UNAUTHORIZED ALTERATION OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE
- . THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS,
- TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THIS CONTRACT
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE  $\,$  ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTRACT WITH THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL VERIFY ALL SUBSTRUCTURES ENCOUNTERED DURING CONSTRUCTION.
- $10.\,$  THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER &OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S

#### **GENERAL CONSTRUCTION NOTES:**

- 1. BENCH MARKS USING U.S.G.S. DATUM SHALL BE OF SUCH ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS 2. CONSTRUCTION ACTIVITY SHALL BE LIMITED FROM 8:00 A.M. TO 6 P.M., AND NO CONSTRUCTION ACTIVITY SHALL OCCUR ON SUNDAYS OR LEGAL NEW YORK STATE HOLIDAYS. WHERE BLASTING IS NECESSARY, IT SHALL OCCUR FROM MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 A.M. AND 6:00 P.M. NO BLASTING SHALL OCCUR ON HOLIDAYS, SATURDAY OR SUNDAY. ALL BLASTING SHALL ALSO BE COMPLETED IN ACCORDANCE WITH THE VILLAGE OF OSSINING AND NEW YORK STATE BLASTING ORDINANCES.
- . ANY SOIL THAT IS UNSUITABLE FOR DEVELOPMENT OF BUILDINGS OR ROADWAYS SHALL BE REMOVED FROM AREAS TO BE DEVELOPED AND SHALL BE DISPOSED OF WITHIN THE SITE IN NEW EMBANKMENTS WHERE STRUCTURAL LOADING, I.E. A BUILDING OR ROADWAY, WILL NOT TAKE PLACE. WHEN CONSTRUCTION IS PROPOSED TO OCCUR IN SPECIFIC AREAS WHERE SOILS ARE OF QUESTIONABLE SUITABILITY, THE APPLICANT SHALL PROVIDE SOILS ENGINEERING REPORTS AS REQUIRED BY THE PLANNING BOARD ENGINEER, PRIOR TO THE CONSTRUCTION OF ROADWAYS AND, AS REQUIRED BY THE BUILDING INSPECTOR, PRIOR TO THE ISSUANCE OF A BUILDING PERMIT.
- 4. NO TOPSOIL SHALL BE REMOVED FROM THE SITE.
- 5. ROCK CUT STABILITY IS TO BE FIELD VERIFIED BY GEOTECHNICAL ENGINEER AND SHALL BE MODIFIED IF REQUIRED.
- 6. NO CRUSHING/PROCESSING IS PERMITTED ON THE SITE WITHOUT PRIOR APPROVAL BY THE VILLAGE OF OSSINING PLANNING BOARD.

# **GENERAL STORM DRAINAGE & UTILITY NOTES**

- I. ALL UTILITIES, INCLUDING ELECTRIC LINES. TELEPHONE, WATER, SANITARY SEWER LINES, AND STORM SEWER LINES SHALL BE LOCATED UNDERGROUND AND SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE VILLAGE OF OSSINING AND THE UTILITY COMPANIES HAVING JURISDICTION.
- 2. LOCATION OF GAS AND WATER VALVES, ELECTRIC AND TELEPHONE POLES ARE TO BE DETERMINED BY PROPER AUTHORITIES AND
- APPROVED. AS TO LOCATION, BY THE VILLAGE ENGINEER. E. EACH BUILDING CONSTRUCTED HEREON SHALL BE OF SUCH AN ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. IN THE EVENT THAT THIS IS NOT FEASIBLE, THE CONTRACTOR SHALL INSTALL TYPICAL YARD DRAINS AS REQUIRED AND
- CONNECT THEM TO THE STORM DRAINAGE SYSTEM OR AS DIRECTED BY THE PROJECT ENGINEER. 4. ROOF LEADERS AND FOOTING DRAINS SHALL EMPTY INTO THE STORM DRAINAGE SYSTEM OR DISCHARGE DIRECTLY TO STORMWATER MANAGEMENT SYSTEMS IF GRADES PERMIT, AND CONNECTION TO THE STORM SYSTEM IS NOT FEASIBLE, FOOTING DRAINS ONLY MAY DISCHARGE TO DAYLIGHT AT THE REAR OF BUILDINGS. FOOTING DRAINS SHALL EXTEND A MINIMUM OF 30 FT. FROM THE REAR FACE OF THE BUILDING WHEN POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE DISCHARGE OF GROUND WATER
- OR STORM WATER, EITHER BY GRAVITY OR BY PUMPING, BE DISCHARGED TO ANY SANITARY SEWER SYSTEM. . ANY REVISIONS AND/OR ADDITIONS TO THE ROAD STORM DRAINAGE SYSTEMS CURRENTLY SHOWN ON THE PLANS WHICH ARE DEEMED NECESSARY DURING CONSTRUCTION MUST BE MADE BY THE CONTRACTOR AS REQUIRED BY THE VILLAGE AND SHALL BE
- 6. STORM DRAIN PIPING TO BE HIGH DENSITY POLYETHYLENE AS SHOWN ON THE CONSTRUCTION DRAWINGS. MINIMUM COVER TO BE
- 2' UNLESS OTHERWISE NOTED. 7. INTERCEPTOR DRAINS ARE TO BE INSTALLED WHERE REQUIRED BY THE VILLAGE OR PROJECT ENGINEER DURING ROAD
- CONSTRUCTION. 8. ALL EXISTING UNDERGROUND DRAINS ENCOUNTERED DURING CONSTRUCTION OF PROPOSED ROADS ARE TO BE CONNECTED TO
- PROPOSED DRAINAGE IMPROVEMENTS. CONNECTIONS TO BE APPROVED BY THE VILLAGE ENGINEER. 9. PRIOR TO FINAL APPROVAL AND OPERATION OF DRAINAGE SYSTEM, CONTRACTOR SHALL CLEAR ALL ACCUMULATED SEDIMENT AND/OR DEBRIS FROM DRAINAGE STRUCTURES, MANHOLES, CULVERTS, OUTLETS AND DRAIN INLETS. ENGINEER SHALL BE
- NOTIFIED FOR FINAL INSPECTION. 10. ALL STRUCTURES SHALL BE SET ONE INCH BELOW PAVEMENT.
- 11. STREET OPENING PERMIT FROM THE VILLAGE OF OSSINING D.P.W. MAY BE REQUIRED FOR INSTALLATIONS IN PUBLIC ROADS.

# CONTRACTOR CERTIFICATION STATEMENT

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-20-001, dated January 2020, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the ould subject me to criminal, civil and/or administrative proceedings."

referenced permit and the laws of the	
Individual Contractor:	
Name and Title (please print):	
Signature of Contractor:	
Company / Contracting Firm:	
Name of Company:	
Address of Company:	
Telephone Number / Cell Number:	
Site Information:	
Address of Site:	
1	

Today's Date:

## **GENERAL EROSION CONTROL NOTES:**

- CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL SEDIMENT AND EROSION CONTROL PRACTICES. THE SEDIMENT AND EROSION CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED. ROAD SURFACE FLOWS FROM THE SITE SHOULD BE DISSIPATED WITH TRACKING PAD OR APPROPRIATE MEASURES DURING ADJACENT ROAD SHOULDER REGRADING. CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL SOIL EROSION AND SEDIMENTATION CONTROL DEVICES THROUGHOUT THE COURSE OF CONSTRUCTION.
- 2. CATCH BASIN INLET PROTECTION MUST BE INSTALLED AND OPERATING AT ALL TIMES UNTIL TRIBUTARY AREAS HAVE BEEN STABILIZED. WHEN POSSIBLE FLOWS SHOULD BE STABILIZED BEFORE REACHING INLET PROTECTION STRUCTURE. TIMELY MAINTENANCE OF SEDIMENT CONTROL STRUCTURES IS THE RESPONSIBILITY OF THE CONTRACTOR
- 3. ALL STRUCTURES SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. THE SEDIMENT LEVEL IN ALL SEDIMENT TRAPS SHALL BE CLOSELY MONITORED AND SEDIMENT REMOVED PROMPTLY WHEN MAXIMUM LEVELS ARE REACHED OR AS ORDERED BY THE ENGINEER. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED ON A REGULAR BASIS. AND AFTER EACH HEAVY RAIN TO INSURE PROPER OPERATION AS DESIGNED. AN INSPECTION SCHEDULE SHALL BE SET FORTH PRIOR TO THE START OF CONSTRUCTION.
- 4. THE LOCATIONS AND THE INSTALLATION TIMES OF THE SEDIMENT CAPTURING STANDARDS SHALL BE AS SPECIFIED IN THESE PLANS, AS ORDERED BY THE ENGINEER, AND IN ACCORDANCE WITH THE LATEST EDITION
- OF THE "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL" (NYSSESC). 5. ALL TOPSOIL SHALL BE PLACED IN A STABILIZED STOCKPILE FOR REUSE ON THE SITE. ALL STOCKPILE
- MATERIAL REQUIRED FOR FINAL GRADING AND STORED ON SITE SHALL BE TEMPORARILY SEEDED AND MULCHED WITHIN 7 DAYS. REFER TO SOIL STOCKPILE DETAILS. 6. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 7 DAYS AND NOT SUBJECT TO
- CONSTRUCTION TRAFFIC, SHALL IMMEDIATELY RECEIVE TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. DISTURBED AREAS SHALL NOT BE LIMED AND FERTILIZED PRIOR TO TEMPORARY SEEDING.
- 7. ALL DISTURBED AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST CONTROL.
- 8. THE CONTRACTOR SHALL KEEP THE ROADWAYS WITHIN THE PROJECT CLEAR OF SOIL AND DEBRIS AND IS RESPONSIBLE FOR ANY STREET CLEANING NECESSARY DURING THE COURSE OF THE PROJECT.
- 9. SEDIMENT AND EROSION CONTROL STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY STABILIZED BY PERMANENT MEASURES.
- 10. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CURRENT
- 11. ALL REGRADED AREAS MUST BE STABILIZED APPROPRIATELY PRIOR TO ANY ROCK BLASTING, CUTTING, AND/OR FILLING OF SOILS. SPECIAL CARE SHOULD BE TAKEN DURING CONSTRUCTION TO INSURE STABILITY DURING MAINTENANCE AND INTEGRITY OF CONTROL STRUCTURES.
- 12. ANY SLOPES GRADED AT 3:1 OR GREATER SHALL BE STABILIZED WITH EROSION BLANKETS TO BE STAKED INTO PLACE IN ACCORDANCE WITH THE MANUFACTURES REQUIREMENTS. EROSION BLANKETS MAY ALSO BE REQUIRED AT THE DISCRETION OF TOWN OFFICIALS OR PROJECT ENGINEER. WHEN STABILIZED BLANKET IS UTILIZED FOR CHANNEL STABILIZATION, PLACE ALL OF THE VOLUME OF SEED MIX PRIOR TO LAYING NET, OR AS RECOMMENDED BY THE MANUFACTURER.
- 13. TO PREVENT HEAVY CONSTRUCTION EQUIPMENT AND TRUCKS FROM TRACKING SOIL OFF-SITE, CONSTRUCT A PERVIOUS CRUSHED STONE PAD. LOCATE AND CONSTRUCT PADS AS DETAILED IN THESE PLANS. 14. CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST BY SPRINKLING EXPOSED SOIL AREAS PERIODICALLY
- WITH WATER AS REQUIRED. CONTRACTOR TO SUPPLY ALL EQUIPMENT AND WATER. 15. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION INSPECTIONS AS PER NYSDEC GP-0-20-001 AND TOWN OF YORKTOWN CODE.

# MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL

## STRUCTURES:

- N.Y.S.D.E.C. GP-0-20-001 EXPOSURE RESTRICTIONS STATES THAT ANY EXPOSED EARTHWORK SHALL BE STABILIZED IN ACCORDANCE WITH THE GUIDELINES OF THIS PLAN.
- 1. TREES AND VEGETATION SHALL BE PROTECTED AT ALL TIMES AS SHOWN ON THE DETAIL DRAWING AND AS DIRECTED BY THE ENGINEER.
- 2. CARE SHOULD BE TAKEN SO AS NOT TO CHANNEL CONCENTRATED RUNOFF THROUGH THE AREAS OF CONSTRUCTION ACTIVITY ON THE SITE.
- 3. FILL AND SITE DISTURBANCES SHOULD NOT BE CREATED WHICH CAUSES WATER TO POND OFF SITE OR ON
- ADJACENT PROPERTIES. 4. RUNOFF FROM LAND DISTURBANCES SHALL NOT BE DISCHARGED OR HAVE THE POTENTIAL TO DISCHARGE OFF SITE WITHOUT FIRST BEING INTERCEPTED BY A CONTROL STRUCTURE, SUCH AS A SEDIMENT TRAP OR SILT FENCE.
- SEDIMENT SHALL BE REMOVED BEFORE EXCEEDING 50% OF THE RETENTION STRUCTURE'S CAPACITY 5. FOR FINISHED GRADING, ADEQUATE GRADE SHALL BE PROVIDED SO THAT WATER WILL NOT POND ON LAWNS FOR MORE THAN 24 HOURS AFTER RAINFALL. EXCEPT IN SWALE FLOW AREAS WHICH MAY DRAIN FOR AS LONG AS 48 HOURS AFTER RAINFALL.
- 6. ALL SWALES AND OTHER AREAS OF CONCENTRATED FLOW SHALL BE PROPERLY STABILIZED WITH TEMPORARY CONTROL MEASURES TO PREVENT EROSION AND SEDIMENT TRAVEL. SURFACE FLOWS OVER CUT AND FILL AREAS
- SHALL BE STABILIZED AT ALL TIMES. 7. ALL SITES SHALL BE STABILIZED WITH EROSION CONTROL MATERIALS WITHIN 7 DAYS OF FINAL GRADING.
- 8. TEMPORARY SEDIMENT TRAPPING DEVICES SHALL BE REMOVED FROM THE SITE WITHIN 30 DAYS OF FINAL STABILIZATION.

# MAINTENANCE SCHEDULE:

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE			INSP.	INSP.	CLEAN/ REPLACE	REMOVE
WHEEL CLEANER	CLEAN				REPLACE	REMOVE
INLET PROTECTION		INSP.	INSP.	CLEAN	REPLACE	REMOVE

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION: THE STORMWATER MANAGEMENT SYSTEM AND OUTLET STRUCTURE SHALL BE INSPECTED ON A REGULAR BASIS AND AFTER EVERY RAINFALL EVENT. SEDIMENT BUILD UP SHALL BE REMOVED FROM THE INLET PROTECTION REGULARLY TO INSURE DETENTION CAPACITY AND PROPER DRAINAGE. OUTLET STRUCTURE SHALL BE FREE OF OBSTRUCTIONS. ALL PIPING AND DRAIN INLETS SHALL BE FREE OF OBSTRUCTION. ANY SEDIMENT BUILD UP SHALL BE REMOVED. MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:

CONTROLS (INCLUDING RESPECTIVE OUTLET STRUCTURES) SHOULD BE INSPECTED PERIODICALLY FOR THE FIRST FEW MONTHS AFTER CONSTRUCTION AND ON AN ANNUAL BASIS THEREAFTER. THEY SHOULD ALSO BE INSPECTED AFTER MAJOR STORM EVENTS.

# DEBRIS AND LITTER REMOVAL:

TWICE A YEAR, INSPECT OUTLET STRUCTURE AND DRAIN INLETS FOR ACCUMULATED DEBRIS. ALSO, REMOVE ANY ACCUMULATIONS DURING EACH MOWING OPERATION. STRUCTURAL REPAIR/REPLACEMENT

OUTLET STRUCTURE MUST BE INSPECTED TWICE A YEAR FOR EVIDENCE OF STRUCTURAL DAMAGE AND REPAIRED IMMEDIATELY. **EROSION CONTROL:** 

UNSTABLE AREAS TRIBUTARY TO THE BASIN SHALL IMMEDIATELY BE STABILIZED WITH VEGETATION OR OTHER APPROPRIATE EROSION CONTROL MEASURES.

# SEDIMENT REMOVAL

SEDIMENT SHOULD BE REMOVED AFTER IT HAS REACHED A MAXIMUM DEPTH OF FIVE INCHES ABOVE THE STORMWATER MANAGEMENT SYSTEM FLOOR.

### **TOPSOIL**

EXISTING TOPSOIL WILL BE REMOVED AND STORED IN PILES SUFFICIENTLY AS TO AVOID MIXING WITH OTHER EXCAVATION. STOCKPILES SHALL BE SURROUNDED BY EROSION CONTROL AS OUTLINED ON THESE PLANS. THE FURNISHING OF NEW TOPSOIL SHALL BE OF A BETTER OR EQUAL TO THE FOLLOWING CRITERIA (SS713.01

- 1. THE PH OF THE MATERIAL SHALL BE 5.5 TO 7.6.
- 2. THE ORGANIC CONTENT SHALL NOT BE LESS THAN 2% OR MORE THAN 70%. 3. GRADATION: SIEVE SIZE % PASSING BY WGT.
  - 2 INCH 1 INCH 85 TO 100 1/4 INCH 65 TO 100 NO. 200 MESH 20 TO 80

## PERMANENT VEGETATIVE COVER

- SITE PREPARATION:
- 1.1. INSTALL EROSION CONTROL MEASURES
- SCARIFY COMPACTED SOIL AREAS. 1.3.
- LIME AS REQUIRED TO PH 6.5.
- 1.4. FERTILIZE WITH 10-6-4 4 LBS/1,000 S.F.
- INCORPORATE AMENDMENTS INTO SOIL WITH DISC HARROW 2. SEED MIXTURES FOR USE ON SWALES AND CUT AND FILL AREAS

SEED MIXTURES I	SEED MIXTURES FOR USE ON SWALES AND CUT AND FILL AREAS.						
<u>MIXTURE</u>		LBS./ACRE					
ALT. A	KENTUCKY BLUE GRASS	20					
	CREEPING RED FESCUE	28					
	RYE GRASS OR REDTOP	5					
ALT. B	CREEPING RED FESCUE	20					
	REDTOP	2					

### SEEDING

3.1. PREPARE SEED BED BY RAKING TO REMOVE STONES, TWIGS, ROOTS AND OTHER FOREIGN

TALL FESCUE/SMOOTH BLOOMGRASS 20

- MATERIAL APPLY SOIL AMENDMENTS AND INTEGRATE INTO SOIL.
- APPLY SEED UNIFORMLY BY CYCLONE SEEDER CULTI-PACKER OR HYDRO-SEEDER AT RATE
- STABILIZE SEEDED AREAS IN DRAINAGE SWALES.
- IRRIGATE TO FULLY SATURATE SOIL LAYER. BUT NOT TO DISLODGE PLANTING SOIL
- SEED BETWEEN APRIL 1ST AND MAY 15TH OR AUGUST 15TH AND OCTOBER 15TH.
- SEEDING MAY OCCUR MAY 15TH AND AUGUST 15TH IF ADEQUATE IRRIGATION IS PROVIDED. TEMPORARY VEGETATIVE COVER:

# SITE PREPARATION:

- INSTALL EROSION CONTROL MEASURES.
- 2. SCARIFY AREAS OF COMPACTED SOIL.
- 3. FERTILIZE WITH 10-10-10 AT 400/ACRE. 4. LIME AS REQUIRED TO PH 6.5.

## SEED SPECIES:

RAPIDLY GERMINATING ANNUAL RYEGRASS (OR APPROVED EQUAL) PERENNIAL RYEGRASS CEREAL OATS

SAME AS PERMANENT VEGETATIVE COVER

# CONSTRUCTION SEQUENCE

# Refer to the Plan Set for all plans and details which relate to Construction Sequence.

- 1. Prior to the beginning of any site work the major features of the construction must be field staked by a licensed surveyor. hese include the building. limits of disturbance, utility lines, and stormwater practices.
- 2. Prior to the start of the project, an on-site pre-construction meeting will be held, this will be attended by the project owner, the operator responsible for complying with the approved construction drawings including the erosion and sediment control (E&SC) plan and details, the design engineer, the engineer responsible for E&SC monitoring during construction,
- town representatives from the engineering department and code enforcement. A licensed surveyor must define infrastructure locations, limits of disturbance, stormwater basin limits, and grades in the field prior to start of any construction. Limits of disturbance shall be marked with the installation of construction fence or approved equal. The extents of the stormwater management system shall be cordoned off to minimize the disturbance
- 4. Install all perimeter erosion control measures, construction entrance as shown on the Erosion and Sediment Control Plan and the associated Details. Install silt fencing at the bottom of slopes. The standards established in Part 1.B 1.b of the

6. Begin rough grading the site. Contractor to limit exposure of denuded soils by providing temporary stabilization for work

areas that will remain undisturbed for over seven (7) days. Chipped rock that is not suitable to remain on site shall be

- GP-020-001 included in appendix B of this SWPPP must be adhered to. 5. Strip site, clear vegetation, and place topsoil in stockpile locations shown on the plan.
- hauled away and properly disposed of. An area has been provided for the stockpiling of removed soil and rock which is to be removed from the site.
- 7. Rough grade building, driveway, and parking area.
- 8. Begin construction of building. 9. Begin the excavation and installation of the stormwater management system. Protect trenches and open excavations from erosion. Entry into the system shall be blocked off until site has reached final stabilization. Once system has been installed, backfill, seed where necessary, and reinstall measures to cordon off the system from disturbance.
- 10. Begin installation of drainage system. Drainage shall be installed working downstream to up. 11. During site construction maintain and re-establish as required erosion control and stabilization measures as required by the site plan and details.
- 12. Excavate to the sub-grade level. Scarify the existing soil to a depth of 12-inches by rototilling or other means acceptable to the Engineer. Install all courses of stone as per the specifications given on the Plan.
- 13. Install base course of Item 4 in all pavement areas. Stabilize all open areas with seed and mulch.
- 14. Construct remainder of building, driveway and parking areas. First install curbs, asphalt binder, and concrete sidewalk. Once binder course is installed, drainage outlet may be unblocked. 15. Backfill curbs, grade, place final soil topping and put in place permanent vegetative cover over all disturbed areas,
- landscape beds, slopes, etc. 16. Once site stabilization has taken place (An area shall be considered to have achieved final stabilization when it has a minimum uniform 80% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements),

remove all temporary erosion and sediment controls, unplug the drainage system to allow runoff to enter the stormwater

# Winter Stabilization Notes:

management system.

If construction activities are expected to extend into or occur during the winter season the contractor shall anticipate proper stabilization and sequencing. Construction shall be sequenced such that wherever possible areas of disturbance that can be completed and permanently stabilized shall be done by applying and establishing permanent vegetative cover before the first frost. Areas subject to temporary disturbance that will not be worked for an extended period of time shall be treated with temporary seed, mulch, and/or erosion blankets.

# ---222 --- EXISTING GRADING $\times$ 222.8 **EXISTING SPOT GRADE** PROPOSED GRADING PROPERTY LINE / RIGHT OF WAY PROPOSED ROAD CENTERLINE PROPOSED CURB 100' WETLAND BUFFER **EXISTING WATER LINE** EXISTING FIRE HYDRANT PROPOSED FIRE HYDRANT CONSERVATION EASEMENT LINE APPROX. AREA OF ROCK OUTCROP **EXISTING STONE WALL** $\infty$ EXISTING STONE WALLS TO BE REMOVED **EXISTING DRAINAGE INLET EXISTING SANITARY LINE EXISTING HEADWALL** PROPOSED DRAINAGE LINE ======= PROPOSED CATCH BASIN #====== PROPOSED DRAINAGE MANHOLE PROPOSED HEADWALL WITH RIP RAP PROPOSED FOOTING DRAIN PROPOSED ROOF DRAIN PROPOSED SEWER SERVICE CONNECTION PROPOSED WATER SERVICE CONNECTION PROPOSED HOUSE AND DRIVE

**LEGEND** 

# OWNER / OPERATOR CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor purcuant to Section 210 45 of the Bonal Law "

PROPOSED SOIL STOCKPILES

PROPOSED CRUSHED STONE

PROPOSED SILT FENCE


PROPOSED STABILIZED

CONSTRUCTION ENTRANCE

PROPOSED LIMIT OF DISTURBANCE


INLET PROTECTION

pursuant to Section 2 i	10.43 Of the Fehal Law.
Name (please print):	
Title:	
Date:	
Address:	
Phone:	
E-mail:	
Signature:	



ð

**IE** 



NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW

Ĭ

