



STORMWATER POLLUTION PREVENTION PLAN

For

NY FUEL DISTRIBUTORS

3700 Barger Street, Town of Yorktown, New York

September 3, 2020

Owner / Applicant Information:

NY Fuel Distributors
235 Mamaroneck Avenue
White Plains, NY 10605

Note: This report in conjunction with the project plans make up the complete Stormwater Pollution Prevention Plan.

Prepared by:
Insite Engineering, Surveying & Landscape Architecture, P.C.
3 Garrett Place
Carmel, New York 10512

CONTENTS

	PAGE
1.0 INTRODUCTION	1
1.1 Project Description.....	1
1.2 Existing Site Conditions	1
1.3 Proposed Site Conditions	1
2.0 TOWN OF YORKTOWN STORMWATER MANAGEMENT REQUIREMENTS.....	2
2.1 Water Quality Treatment.....	3
2.2 Water Quantity Control	3
3.0 STORMWATER CONVEYANCE SYSTEM	4
4.0 EROSION AND SEDIMENT CONTROL	4
4.1 Temporary Erosion and Sediment Control Facilities	4
4.2 Permanent Erosion and Sediment Control Facilities.....	5
5.0 IMPLEMENTATION, MAINTENANCE & GENERAL HOUSEKEEPING	5
5.1 Construction Phase	5
5.2 Long Term Maintenance Plan	6

APPENDICES

- Appendix A WQ_v Calculations
- Appendix B Pre-development HydroCAD Output
- Appendix C Post-development HydroCAD Output
- Appendix D Project and Owner Information
- Appendix E Hydrodynamic Separator Sizing Information (HDS)

FIGURES

- Figure 1: Location Map
- Figure 2: Pre-development Drainage Map
- Figure 3: Post-Development Drainage Map

1.0 INTRODUCTION

1.1 Project Description

NY Fuel Distributors is proposing to redevelop an existing Getty Gas Station located at 3700 Barger Street in the Town of Yorktown. The property is identified as Tax Map #16.07-1-44, approximately 0.49 acres in size, and is located in zone C-4.

It is proposed to develop an entirely new gas station canopy and associated convenience store. The gas service canopy is proposed to be approximately 2,200 sq-ft in size, and the convenience store is proposed to be approximately 2,000 sq-ft in size. The proposed convenience store will be approximately 400 s.f. smaller than the existing gas / service station. It is also proposed to replace the existing underground storage tanks and add 4 fuel pump islands.

This SWPPP will address erosion and sediment control (E&SC) measures to be implemented through construction as well as the post-construction stormwater management practices (SMP's) to be provided for the project. As the proposed disturbance associated with this project is under one acre and located outside of the NYC East of Hudson Watershed, compliance under the New York State Department of Environmental Conservation (NYSDEC) *SPDES General Permit for Stormwater Discharges from Construction Activities, General Permit GP-0-15-002* (General Permit) is not required.

This SWPPP has been designed to meet the requirements of Chapter 247, *Illicit Discharges*, and Chapter 248, *Stormwater Management and Erosion and Sediment Control*, of the Town of Yorktown code. The *New York State Standards and Specifications for Erosion and Sediment Control* (Blue Book) has been referenced for the design of E&SC measures for the project. The *New York State Stormwater Management Design Manual* has been referenced for the design of the post-construction SMP's provided for the project. This includes both water quality and quantity SMP's.

1.2 Existing Site Conditions

The existing site is predominately developed with impervious surface. Onsite soils have been identified as Urban Land on the *Web Soil Survey*. Based on the surrounding soil categories the onsite soils were assigned to a Hydrologic Soil Group of D.

A pre-development drainage map, identified as Figure 2, has been provided herein. One design point is identified on the pre-development drainage map. Design Point 1 is located along Barger Brook which runs along the eastern edge of the subject property. The site is located in the Peekskill and Haverstraw Bay Basin. Runoff from the site generally discharges east into Barger Brook as well as west onto Barger Street.

A FEMA Special Flood Hazard Area has been identified on the eastern portion of the property and shown on the project drawings.

1.3 Proposed Site Conditions

This SWPPP addresses the onsite redevelopment of the existing Getty Gas Station located at 3700 Barger Street, just south of US-Route 6. The design for the redevelopment of the existing station includes a new gas station canopy, convenience store, and associated appurtenances.

A HydroStorm Hydrodynamic Separator is proposed for water quality treatment and an underground pipe detention system will be provided to attenuate peak flows. In accordance with *Chapter 9*, of the Design Manual, 100% of the Water Quality Volume from the new impervious surfaces, and 25% of the WQv from the existing redeveloped impervious surfaces will be treated by the HydroStorm Hydrodynamic Separator.

To the maximum extent practicable the existing subcatchment areas will be maintained. Refer to Figure 3, the Post-development Drainage Map for the post-development drainage areas.

2.0 TOWN OF YORKTOWN STORMWATER MANAGEMENT REQUIREMENTS

The proposed stormwater management system for this SWPPP has been designed to meet the requirements of local stormwater ordinances and guidelines, including those of the Town of Yorktown. Specifically, the follow codes / regulations have been used to design this SWPPP:

- *Town of Yorktown, Chapter 247 – Illicit Discharges*
- *Town of Yorktown, Chapter 248 – Stormwater Management and Erosion and Sediment Control*

Even through not required, preliminary discussions with the Town indicated stormwater quality and quantity treatment will be required. The *New York State Stormwater Management Design Manual* (Design Manual) was referenced with respect to Water Quality Volume (WQ_v), and Overbank Flood Control (Q_f), and Extreme Flood Control (Q_p). The first requirement relates to treating water quality, while the later pertain to stormwater quantity (peak flow) attenuation.

To provide the required water quality treatment and peak flow attenuation, the following post construction stormwater management practices are proposed for the project.

Table 2.0.1 – Proposed SMP Design Criteria Summary Table

Proposed SMP ID	Design Manual Design Designation	SMP Objective
SMP 1.1P	Underground Detention System	Peak Flow Attenuation
HydroStorm HS3	Hydrodynamic Separator	Water Quality Treatment

To address stormwater quantity requirements, the “HydroCAD” Stormwater Modeling System,” by HydroCAD Software Solutions LLC in Tamworth, New Hampshire, was used to model and assess the peak stormwater flows for the subject project. HydroCAD is a computer aided design program for modeling the hydrology and hydraulics of stormwater runoff. It is based primarily on hydrology techniques developed by the United States Department of Agriculture, Soil Conservation Service (USDA, SCS) TR-20 method combined with standard hydraulic calculations. For details on the input data for the subcatchments and design storms, refer to Appendices C and D:

The input requirements for the HydroCAD computer program are as follows:

Subcatchments (contributing watershed/sub-watersheds)

- Design storm rainfall in inches
- CN (runoff curve number) values which are based on soil type and land use/ground cover
- Tc (time of concentration) flow path information

Stormwater Management Practices

- Surface area at appropriate elevations
- Flood elevation
- Outlet structure information

The precipitation values and intensity duration frequency (IDF) curves for the 1-Year, 10-Year and 100-Year 24-hour design storm events, and rainfall distribution curves, were obtained from the information provided by Northeast Regional Climate Center (NRCC) and the Natural Resources Conservation

Service (NRCS) which is available online at www.precip.eas.cornell.edu. The values provided for all design storms analyzed have been listed below.

Design Storm	24-Hour Rainfall
10-Year	5.05"
100-Year	9.15"

2.1 Water Quality Treatment

As stated in the Design Manual, “The Water Quality Volume (denoted as the WQ_v) is intended to improve water quality by capturing and treating runoff from small, frequent storm events that tend to contain higher pollutant levels. New York has defined the WQ_v as the volume of runoff generated from the entire 90th percentile rain event. Essentially what this means is that a practice sized using the WQ_v will capture and treat 90% of all 24-hour rain events.” The 90% storm event from the project site as determined from Chapter 4 of the Design Manual is 1.4”.

Two subcatchments contain the proposed development. They are 1.1S and 1.2S. Appendix A contains the WQ_v calculations for these subcatchments. In accordance with Chapter 9 of the Design Manual, the project is required to treat 25% of the WQ_v from the existing impervious surfaces being redeveloped and 100% of the WQ_v from the new impervious surfaces. The proposed HydroStorm Hydrodynamic Separator will be required to treat the calculated volume from the WQ_v event, while the underground detention system will be required to treat peak flows. Sizing calculations for the proposed Hydrodynamic Separator are contained in Appendix E.

The hydrodynamic separator is located upstream of the proposed underground detention system and downstream of the flow splitter FS 4. The flow splitter will allow larger storm events to bypass the treatment unit in accordance with manufacturers recommendations. All flow will pass through the underground pipe detention system.

2.2 Water Quantity Control

For peak flow attenuation the Overbank Flood Control and Extreme Flood Control as defined in the Design Manual were used for a pre to post-development comparison of peak flows.

The Overbank Flood Control (Q_p) requirement is intended to prevent an increase in the frequency and magnitude of out-of-bank flooding events generated by urban development. Overbank Flood Control requires storage to attenuate the post-development 10-year, 24-hour peak discharge to pre-development rates. The Extreme Flood Control (Q_p) requirement is intended to prevent the increased risk of flood damage from large storm events, maintain the boundaries of the pre-development 100-year flood plain, and protect the physical integrity of SMP’s. Extreme Flood Control requires storage to attenuate the post-development 100-year, 24-hour peak discharge to pre-development rates.

The pre- versus post-development analysis is contained in Appendix C and D, and compares the pre- versus post-development peak flows at Design Point 1:

Table 2.5.1 Pre-and Post-Development Peak Flows at Design Point 1

24-HOUR DESIGN STORM PEAK FLOWS (c.f.s.)				
	10-YEAR (Overbank Flood Control)		100-YEAR (Extreme Flood Control)	
	Pre	Post	Pre	Post
Design Point 1	3.35	2.67	5.26	4.85

3.0 STORMWATER CONVEYANCE SYSTEM

The stormwater collection and conveyance systems for the project will primarily consist of HDPE pipe, catch basins, drain inlets, drainage manholes, and roof leader drain piping. The final project SWPPP will include pipe sizing calculations in accordance with Town of Yorktown standards.

4.0 EROSION AND SEDIMENT CONTROL

Erosion and sediment control should be accomplished by four basic principles: diversion of clean water, containment of sediment, treatment of dirty water, and stabilization of disturbed areas. Diversion of clean water should be accomplished with swales, and dewatering points. If groundwater or other clean water is encountered, the diverted water should be safely conveyed around the construction area as necessary and discharged downstream of the disturbed areas. Sediment should be contained with the use of silt fence at the toe of disturbed slopes. Disturbed areas should be permanently stabilized within 14 days of final grading to limit the required length of time that the temporary facilities must be utilized. The owner will be responsible for the maintenance of the temporary erosion control facilities. Refer to the Project Drawings for further information implementation of the Erosion Control Plan and Construction Sequence.

All erosion and sediment controls have been designed in accordance with the *New York Standards and Specifications for Erosion and Sediment Control* (Blue Book).

4.1 Temporary Erosion and Sediment Control Facilities

Temporary erosion and sediment control facilities should be installed and maintained as required to reduce the impacts to off-site properties. The owner will be required to provide maintenance for the temporary erosion and sediment control facilities. In general, the following temporary methods and materials should be used to control erosion and sedimentation from the project site:

- Stabilized Construction Entrance
- Dust Control
- Silt Fence Barriers
- Storm Drain Inlet Protection
- Temporary Soil Stabilization

All temporary erosion control measures shall be maintained as discussed below. In accordance with the General Permit a NYSDEC trained contractor shall be onsite at all times soil disturbing activities are commencing. In addition, the owner shall retain a Qualified Professional to perform weekly inspections of the erosion control facilities.

A stabilized construction entrance should be installed at the entrance to the site as shown on the plan. The design drawings will include details to guide the contractor in the construction of this entrance. The intent of the stabilized construction entrance is to prevent the “tracking” of soil from the site.

Dust control should be accomplished with water sprinkling trucks if required. During dry periods, sprinkler trucks should wet all exposed earth surfaces as required to prevent the transport of air-borne particles to adjoining areas.

Siltation barriers constructed of geosynthetic filter cloth should be installed at the toe of all disturbed slopes. The intent of these barriers is to contain silt and sediment at the source and inhibit its transport by stormwater runoff. The siltation barriers will also help reduce the rate of runoff by creating filters through which the stormwater must pass. During construction, the siltation barriers shall be inspected weekly and after a rainfall event and shall be cleaned/replaced when needed.

Storm drain inlet protection in the form of stone drop inlet protection will be installed around all proposed inlets. The stone drop inlet protection will serve to filter stormwater runoff before it enters the collection system. Throughout construction the concrete drainage structures, associated piping and inlet protections shall be

inspected weekly and after a rainfall event. These items shall be cleaned, repaired and/or replaced when needed.

When land is exposed during development, the exposure shall be kept to the shortest practical period, but in no case more than 14 days. Temporary grass seed and mulch shall be applied to any construction area idle for seven days. The temporary seeding and mulching shall be performed in accordance with the seeding notes illustrated the Project Drawings. Disturbance shall be minimized in the areas required to perform construction. Upon completion of final grading, topsoil, permanent seeding and mulch shall be applied in accordance the Project Drawings.

The stormwater runoff will be managed by the temporary erosion and sediment control facilities during construction. The stabilized construction entrance coupled with silt fence installed along the down hill perimeter of where soil disturbing activities will occur, stormwater runoff will be contained on-site.

4.2 Permanent Erosion and Sediment Control Facilities

Permanent erosion and sediment control will be accomplished by vegetative and structural surface stabilization. All of the permanent facilities are relatively maintenance free and only require periodic inspections. The owner will provide maintenance for all the permanent erosion and sediment control facilities.

Other than the buildings and paved surfaces, disturbed surfaces will be stabilized with vegetation within 10 days of final grading. Permanent seed mix and mulch shall be applied to idle areas to minimize the amount of exposed soil. Types and application rates for the seed and mulch are provided on the Project Drawings. The vegetation will control stormwater runoff by preventing soil erosion, reducing runoff volume and velocities, and providing a filter medium. Permanent seeding should optimally be undertaken in the spring from March 21st through May 20th and in late summer from August 15th to October 15th.

5.0 IMPLEMENTATION, MAINTENANCE & GENERAL HOUSEKEEPING

5.1 Construction Phase

Details associated with the implementation and maintenance of the proposed stormwater facilities and erosion control measures during construction are shown on the Project Drawings. The erosion control plan will include associated details and notes to aid the contractor in implementing the plan. Construction is anticipated to begin in the spring of 2020 and anticipated to be completed by end of 2020.

In addition to the proposed erosion and sediment control facilities, the following good housekeeping best management practices shall be implemented to mitigate potential pollution during the construction phase of the project. The general contractor overseeing the day-to-day site operation shall be responsible for the good housekeeping best management practices included in the following general categories:

- Material Handling and Waste Management
- Establishment of Building Material Staging Areas
- Establishment of Washout Areas
- Proper Equipment Fueling and Maintenance Practices
- Spill Prevention and Control Plan

All construction waste materials shall be collected and removed from the site regularly by the general contractor. The general contractor shall supply waste barrels for proper disposal of waste materials. All personnel working on the site shall be instructed of the proper procedures for construction waste disposal.

Although it is not anticipated any hazardous waste materials will be utilized during construction, any hazardous waste materials shall be disposed of in accordance with federal, state, and local regulations. No hazardous waste shall be disposed of on-site. Hazardous waste materials shall be stored in appropriate and clearly marked containers and segregated from the other non-waste materials. All hazardous waste shall be

stored in structurally sound and sealed shipping containers located in the staging areas. Material safety data sheets, material inventory, and emergency contact numbers will be maintained in the office trailer. All personnel working on the site shall be instructed of the proper procedures for hazardous waste disposal.

Temporary sanitary facilities (portable toilets) shall be provided on site during the entire length of construction. The sanitary facilities shall be located in the staging areas, or in an alternate area away from the construction activities on the site. The portable toilets shall be inspected weekly for evidence of leaking holding tanks.

All recyclables, including wood pallets, cardboard boxes, and all other recyclable construction scraps shall be disposed of in a designated recycling barrel provided by the contractor and removed from the site regularly. All personnel working on the site shall be instructed of the proper procedures for construction waste recycling.

All construction equipment and maintenance materials shall be stored in a designated staging area. Silt fence shall be installed down gradient of the construction staging area. Shipping containers shall be utilized to store hand tools, small parts, and other construction materials, not taken off site daily. Construction waste barrels, recycling barrels and if necessary hazardous waste containers shall be located within the limits of the construction staging area.

Throughout the construction of the project several types of vehicles and equipment will be used on-site. Fueling of the equipment shall occur within the limits of the construction staging area. Fuel will be delivered to the site as needed, by the general contractor, or a party chosen by the general contractor. Only minor vehicle equipment maintenance shall occur on-site, all major maintenance shall be performed off-site. All equipment fluids generated from minor maintenance activities shall be disposed of into designated drums and stored in accordance with the hazardous waste storage as previously discussed.

Vehicles and equipment shall be inspected on each day of use. Any leak discovered shall be repaired immediately. All leaking equipment unable to be repaired shall be removed from the site. Ample supplies of absorbent, spill-cleanup materials, and spill kits shall be located in the construction staging area. All spills shall be cleaned up immediately upon discovery. Spent absorbent materials and rags shall be hauled off-site immediately after the spill is cleaned for disposal at a local landfill. All personnel working on the site shall be instructed of the proper procedures for spill prevention and control. Any spill large enough to discharge to surface water will be immediately reported to the local fire / police departments, and the National Response Center 1-800-424-8802.

Initially the green roofs and underground pipe detention system will require regular maintenance until the permanent vegetation is established. Vegetation should be inspected every 30 days and after every major storm event until established, after which inspections should take place in accordance with the inspection checklists contained the Appendix. Damaged areas should be immediately re-seeded and re-mulched.

5.2 Long Term Maintenance Plan

The owner will be responsible for the maintenance of the permanent erosion control and stormwater facilities. Each spring the paved areas should be cleaned to remove the winter's accumulation of traction sand. After this is completed, all drain inlets sumps and the stormwater management practices should be cleaned. All pipes should be checked for debris and blockages and cleaned as required. During the cleaning process, the drain inlets and pipes should be inspected for structural integrity and overall condition; repairs and/or replacement will be made as required.

The hydrodynamic separator and underground pipe detention system should be inspected after major storm events and semi-annually. During the inspections, the following should be checked:

- Evidence of clogging of outlet structure.
- Draindown after storm events is occurring.
- Erosion of the flow path through the basin.
- Subsidence, erosion, cracking or tree growth on the embankment/berm.
- Condition of the emergency spillway.

- Accumulation of sediment around the outlet structure.
- Adequacy of upstream/downstream channel erosion control measures.
- Erosion of the basin bed and banks.
- Sources of erosion in the contributory drainage, which should be stabilized.

In addition to guidelines discussed above all maintenance requirements outlined in the Design Manual shall be followed.

APPENDIX A
WQ_v Calculations

WQv Flow Calculation Worksheet

Project: NY Fuel Distributors
 Project #: 19195.100
 Date: 10/8/2019



The following calculation determines the water quality flow rate for the 90% Water Quality Event using the Small Storm Hydrology Method specified in Appendix B of the New York State Stormwater Management Design Manual.

Subcatchment ID: 1.2

$$1. \text{Water Quality Volume} = WQ_v = \frac{P * R_{v,e} * A_e}{12} * 25\% + \frac{P * R_{v,p} * A_p}{12}$$

P = WQv 24-hour Rainfall Amount = 1.4 in.
 R_{v,e} = 0.05 + 0.009(100%) = 0.95
 A = Subcatchment Area = 19700 SF
 A_e = Existing Impervious Area to be Redeveloped = 18700 SF
 A_p = Proposed Impervious Area = 0
 A_i = Total Impervious Area = 18700
 I = (A_p)/(A-A_e) = 0.0 %
 R_{v,p} = 0.05 + 0.009 (I%) = 0.05
 WQv = Water Quality Volume = 524 CF

2. Peak Discharge (Q_p) = $q_u * A * WQV$ where...

Q_a = Water Quality Volume, in watershed in. = WQv/A = 0.32 in.
 CN = curve number = 83
 S = potential maximum retention after runoff begins = 1000/CN - 10 = 2.07 in.
 I_a = initial abstraction = 0.2*S = 0.413 in.
 I_a/P = 0.30
 q_u, From TR-55 Chapter 4 = 638 cfs/mi²/in.
 Q_p = Peak Discharge = 0.1 cfs

WQv Flow Calculation Worksheet

Project: NY Fuel Distributors
 Project #: 19195.100
 Date: 9/19/2019



The following calculation determines the water quality flow rate for the 90% Water Quality Event using the Small Storm Hydrology Method specified in Appendix B of the New York State Stormwater Management Design Manual.

Subcatchment ID: 1.1

$$1. \text{Water Quality Volume} = WQ_v = \frac{P * R_{v,e} * A_e}{12} * 25\% + \frac{P * R_{v,p} * A_p}{12}$$





P = WQv 24-hour Rainfall Amount = 1.4 in.
 R_{v,e} = 0.05 + 0.009(100%) = 0.95
 A = Subcatchment Area = 9000 SF
 A_e = Existing Impervious Area to be Redeveloped = 0 SF
 A_p = Proposed Impervious Area = 0
 A_i = Total Impervious Area = 6000
 I = (A_p)/(A-A_e) = 66.7 %
 R_{v,p} = 0.05 + 0.009 (I%) = 0.65
 WQv = Water Quality Volume = 683 CF

2. Peak Discharge (Q_p) = $q_u * A * WQV$ where...

Q_a = Water Quality Volume, in watershed in. = WQv/A = 0.91 in.
 CN = curve number = 95
 $1000/[10+5P+10Q-10(Q^2+1.25*Q*P)^{1/2}]$
 S = potential maximum retention after runoff begins = 1000/CN - 10 = 0.54 in.
 I_a = initial abstraction = 0.2*S = 0.108 in.
 I_a/P = 0.08
 q_u, From TR-55 Chapter 4 = 638 cfs/mi²/in.
 Q_p = Peak Discharge = 0.2 cfs

APPENDIX B

Pre-development HydroCAD Output



Routing Diagram for Predevelopment

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C., Printed 9/2/2020
HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Predevelopment

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 2

Summary for Subcatchment 1.0S:

Runoff = 3.35 cfs @ 11.99 hrs, Volume= 0.229 af, Depth= 4.58"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Area (ac)	CN	Description
0.530	98	Paved parking, HSG D
0.070	80	>75% Grass cover, Good, HSG D
0.600	96	Weighted Average
0.070		11.67% Pervious Area
0.530		88.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	100	0.0250	1.54		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
0.2	77	0.0740	5.52		Shallow Concentrated Flow, Paved Kv= 20.3 fps
0.0	7	0.5000	4.95		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
0.9	145	0.0050	2.80	15.41	Trap/Vee/Rect Channel Flow, Bot.W=10.00' D=0.50' Z= 2.0 '/' Top.W=12.00' n= 0.022 Earth, clean & straight
2.2	329	Total			

Subcatchment 1.0S:

Hydrograph



Predevelopment

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 3


Summary for Reach DP 1:

Inflow Area = 0.600 ac, 88.33% Impervious, Inflow Depth = 4.58" for 10-yr event
Inflow = 3.35 cfs @ 11.99 hrs, Volume= 0.229 af
Outflow = 3.35 cfs @ 11.99 hrs, Volume= 0.229 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach DP 1:

Hydrograph



Predevelopment

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 4

Summary for Subcatchment 1.0S:

Runoff = 0.15 cfs @ 11.99 hrs, Volume= 0.011 af, Depth= 0.22"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Area (ac)	CN	Description
0.530	98	Paved parking, HSG D
0.070	80	>75% Grass cover, Good, HSG D
0.600	96	Weighted Average
0.070		11.67% Pervious Area
0.530		88.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	100	0.0250	1.54		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
0.2	77	0.0740	5.52		Shallow Concentrated Flow, Paved Kv= 20.3 fps
0.0	7	0.5000	4.95		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
0.9	145	0.0050	2.80	15.41	Trap/Vee/Rect Channel Flow, Bot.W=10.00' D=0.50' Z= 2.0 '/' Top.W=12.00' n= 0.022 Earth, clean & straight
2.2	329	Total			

Subcatchment 1.0S:

Hydrograph



Predevelopment

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 5


Summary for Reach DP 1:

Inflow Area = 0.600 ac, 88.33% Impervious, Inflow Depth = 0.22" for 90% WQv event
Inflow = 0.15 cfs @ 11.99 hrs, Volume= 0.011 af
Outflow = 0.15 cfs @ 11.99 hrs, Volume= 0.011 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach DP 1:

Hydrograph



Predevelopment

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 6

Summary for Subcatchment 1.0S:

Runoff = 5.26 cfs @ 11.99 hrs, Volume= 0.433 af, Depth= 8.67"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Area (ac)	CN	Description
0.530	98	Paved parking, HSG D
0.070	80	>75% Grass cover, Good, HSG D
0.600	96	Weighted Average
0.070		11.67% Pervious Area
0.530		88.33% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	100	0.0250	1.54		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
0.2	77	0.0740	5.52		Shallow Concentrated Flow, Paved Kv= 20.3 fps
0.0	7	0.5000	4.95		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
0.9	145	0.0050	2.80	15.41	Trap/Vee/Rect Channel Flow, Bot.W=10.00' D=0.50' Z= 2.0 '/' Top.W=12.00' n= 0.022 Earth, clean & straight
2.2	329	Total			

Subcatchment 1.0S:

Hydrograph



Predevelopment

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 7


Summary for Reach DP 1:

Inflow Area = 0.600 ac, 88.33% Impervious, Inflow Depth = 8.67" for 100-yr event
Inflow = 5.26 cfs @ 11.99 hrs, Volume= 0.433 af
Outflow = 5.26 cfs @ 11.99 hrs, Volume= 0.433 af, Atten= 0%, Lag= 0.0 min




Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach DP 1:

Hydrograph



APPENDIX C
Post-development HydroCAD Output



Routing Diagram for Post Development

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C., Printed 9/2/2020
 HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Post Development

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 2

Summary for Subcatchment 1.1S:

Runoff = 1.14 cfs @ 11.99 hrs, Volume= 0.074 af, Depth= 4.03"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Area (ac)	CN	Description
0.140	98	Paved parking, HSG D
0.080	80	>75% Grass cover, Good, HSG D
0.220	91	Weighted Average
0.080		36.36% Pervious Area
0.140		63.64% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	100	0.0250	1.54		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
0.2	77	0.0740	5.52		Shallow Concentrated Flow, Paved Kv= 20.3 fps
0.0	7	0.5000	4.95		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
0.9	145	0.0050	2.80	15.41	Trap/Vee/Rect Channel Flow, Bot.W=10.00' D=0.50' Z= 2.0 '/' Top.W=12.00' n= 0.022
2.2	329	Total			

Subcatchment 1.1S:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 3

Summary for Subcatchment 1.2S:

Runoff = 2.44 cfs @ 11.99 hrs, Volume= 0.176 af, Depth= 4.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Area (ac)	CN	Description
0.440	98	Paved parking, HSG D
0.440		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	100	0.0130	1.18		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
1.4	260	0.0050	3.21	2.52	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
2.8	360	Total			

Subcatchment 1.2S:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 4


Summary for Reach DP 1:

Inflow Area = 0.660 ac, 87.88% Impervious, Inflow Depth = 4.55" for 10-yr event
Inflow = 2.67 cfs @ 12.01 hrs, Volume= 0.250 af
Outflow = 2.67 cfs @ 12.01 hrs, Volume= 0.250 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach DP 1:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 5


Summary for Reach HDS:

Inflow Area = 0.440 ac, 100.00% Impervious, Inflow Depth = 3.38" for 10-yr event
Inflow = 0.20 cfs @ 11.99 hrs, Volume= 0.124 af
Outflow = 0.20 cfs @ 11.99 hrs, Volume= 0.124 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach HDS:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 6

Summary for Pond 1.2P:

Inflow = 2.25 cfs @ 11.99 hrs, Volume= 0.052 af
 Outflow = 1.59 cfs @ 12.05 hrs, Volume= 0.052 af, Atten= 29%, Lag= 3.4 min
 Primary = 1.45 cfs @ 12.05 hrs, Volume= 0.052 af
 Secondary = 0.14 cfs @ 12.05 hrs, Volume= 0.001 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 Peak Elev= 421.98' @ 12.05 hrs Surf.Area= 0.011 ac Storage= 0.010 af

Plug-Flow detention time= 4.2 min calculated for 0.052 af (100% of inflow)
 Center-of-Mass det. time= 4.2 min (725.5 - 721.2)

Volume	Invert	Avail.Storage	Storage Description
#1	420.90'	0.017 af	24.0" Round Pipe Storage x 4 L= 60.0'


Device	Routing	Invert	Outlet Devices
#1	Secondary	421.80'	12.0" Round Culvert L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.80' / 420.70' S= 0.1100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Primary	420.90'	8.0" Round Culvert L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 420.90' / 420.70' S= 0.0200 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

Primary OutFlow Max=1.45 cfs @ 12.05 hrs HW=421.98' TW=0.00' (Dynamic Tailwater)
 ↳ **2=Culvert** (Inlet Controls 1.45 cfs @ 4.16 fps)

Secondary OutFlow Max=0.14 cfs @ 12.05 hrs HW=421.98' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Inlet Controls 0.14 cfs @ 1.45 fps)

Pond 1.2P:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 10-yr Rainfall=5.05"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 8

Summary for Pond FS:

Inflow Area = 0.440 ac, 100.00% Impervious, Inflow Depth = 4.81" for 10-yr event
 Inflow = 2.44 cfs @ 11.99 hrs, Volume= 0.176 af
 Outflow = 2.44 cfs @ 11.99 hrs, Volume= 0.176 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.20 cfs @ 11.99 hrs, Volume= 0.124 af
 Secondary = 2.25 cfs @ 11.99 hrs, Volume= 0.052 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 Peak Elev= 422.84' @ 11.99 hrs
 Flood Elev= 423.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	421.30'	4.0" Round Culvert L= 13.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.30' / 420.80' S= 0.0385 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	421.30'	12.0" Round Culvert L= 18.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.30' / 420.80' S= 0.0278 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 1	421.30'	2.5" Vert. Orifice/Grate C= 0.600
#4	Device 2	422.50'	4.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=0.20 cfs @ 11.99 hrs HW=422.83' TW=0.00' (Dynamic Tailwater)


- ↑1=Culvert (Passes 0.20 cfs of 0.49 cfs potential flow)
- ↑3=Orifice/Grate (Orifice Controls 0.20 cfs @ 5.75 fps)

Secondary OutFlow Max=2.17 cfs @ 11.99 hrs HW=422.83' TW=421.81' (Dynamic Tailwater)

- ↑2=Culvert (Passes 2.17 cfs of 3.81 cfs potential flow)
- ↑4=Broad-Crested Rectangular Weir (Weir Controls 2.17 cfs @ 1.65 fps)

Pond FS:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 10

Summary for Subcatchment 1.1S:

Runoff = 0.01 cfs @ 12.01 hrs, Volume= 0.001 af, Depth= 0.07"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Area (ac)	CN	Description
0.140	98	Paved parking, HSG D
0.080	80	>75% Grass cover, Good, HSG D
0.220	91	Weighted Average
0.080		36.36% Pervious Area
0.140		63.64% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	100	0.0250	1.54		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
0.2	77	0.0740	5.52		Shallow Concentrated Flow, Paved Kv= 20.3 fps
0.0	7	0.5000	4.95		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
0.9	145	0.0050	2.80	15.41	Trap/Vee/Rect Channel Flow, Bot.W=10.00' D=0.50' Z= 2.0 '/' Top.W=12.00' n= 0.022
2.2	329	Total			

Subcatchment 1.1S:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 11

Summary for Subcatchment 1.2S:

Runoff = 0.16 cfs @ 12.00 hrs, Volume= 0.012 af, Depth= 0.33"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Area (ac)	CN	Description
0.440	98	Paved parking, HSG D
0.440		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	100	0.0130	1.18		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
1.4	260	0.0050	3.21	2.52	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
2.8	360	Total			

Subcatchment 1.2S:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 12


Summary for Reach DP 1:

Inflow Area = 0.660 ac, 87.88% Impervious, Inflow Depth = 0.24" for 90% WQv event
Inflow = 0.17 cfs @ 12.00 hrs, Volume= 0.013 af
Outflow = 0.17 cfs @ 12.00 hrs, Volume= 0.013 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach DP 1:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 13


Summary for Reach HDS:

Inflow Area = 0.440 ac, 100.00% Impervious, Inflow Depth = 0.33" for 90% WQv event
Inflow = 0.16 cfs @ 12.00 hrs, Volume= 0.012 af
Outflow = 0.16 cfs @ 12.00 hrs, Volume= 0.012 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach HDS:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 14

Summary for Pond 1.2P:

Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Outflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 Peak Elev= 420.90' @ 0.00 hrs Surf.Area= 0.000 ac Storage= 0.000 af

Plug-Flow detention time= (not calculated: initial storage exceeds outflow)
 Center-of-Mass det. time= (not calculated: no inflow)

Volume	Invert	Avail.Storage	Storage Description
#1	420.90'	0.017 af	24.0" Round Pipe Storage x 4 L= 60.0'


Device	Routing	Invert	Outlet Devices
#1	Secondary	421.80'	12.0" Round Culvert L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.80' / 420.70' S= 0.1100 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Primary	420.90'	8.0" Round Culvert L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 420.90' / 420.70' S= 0.0200 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=420.90' TW=0.00' (Dynamic Tailwater)
 ↳2=Culvert (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=420.90' TW=0.00' (Dynamic Tailwater)
 ↳1=Culvert (Controls 0.00 cfs)

Pond 1.2P:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr 90% WQv Rainfall=0.51"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 16

Summary for Pond FS:

Inflow Area = 0.440 ac, 100.00% Impervious, Inflow Depth = 0.33" for 90% WQv event
 Inflow = 0.16 cfs @ 12.00 hrs, Volume= 0.012 af
 Outflow = 0.16 cfs @ 12.00 hrs, Volume= 0.012 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.16 cfs @ 12.00 hrs, Volume= 0.012 af
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Peak Elev= 422.36' @ 12.00 hrs

Flood Elev= 423.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	421.30'	4.0" Round Culvert L= 13.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.30' / 420.80' S= 0.0385 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	421.30'	12.0" Round Culvert L= 18.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.30' / 420.80' S= 0.0278 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 1	421.30'	2.5" Vert. Orifice/Grate C= 0.600
#4	Device 2	422.50'	4.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=0.16 cfs @ 12.00 hrs HW=422.33' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Passes 0.16 cfs of 0.39 cfs potential flow)

↑3=Orifice/Grate (Orifice Controls 0.16 cfs @ 4.63 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=421.30' TW=420.90' (Dynamic Tailwater)

↑2=Culvert (Controls 0.00 cfs)

↑4=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond FS:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 18

Summary for Subcatchment 1.1S:

Runoff = 1.87 cfs @ 11.99 hrs, Volume= 0.148 af, Depth= 8.06"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Area (ac)	CN	Description
0.140	98	Paved parking, HSG D
0.080	80	>75% Grass cover, Good, HSG D
0.220	91	Weighted Average
0.080		36.36% Pervious Area
0.140		63.64% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	100	0.0250	1.54		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
0.2	77	0.0740	5.52		Shallow Concentrated Flow, Paved Kv= 20.3 fps
0.0	7	0.5000	4.95		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
0.9	145	0.0050	2.80	15.41	Trap/Vee/Rect Channel Flow, Bot.W=10.00' D=0.50' Z= 2.0 '/' Top.W=12.00' n= 0.022
2.2	329	Total			

Subcatchment 1.1S:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 19

Summary for Subcatchment 1.2S:

Runoff = 3.80 cfs @ 11.99 hrs, Volume= 0.327 af, Depth= 8.91"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
 NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Area (ac)	CN	Description
0.440	98	Paved parking, HSG D
0.440		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.4	100	0.0130	1.18		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.35"
1.4	260	0.0050	3.21	2.52	Pipe Channel, 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
2.8	360	Total			

Subcatchment 1.2S:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 20


Summary for Reach DP 1:

Inflow Area = 0.660 ac, 87.88% Impervious, Inflow Depth = 8.63" for 100-yr event
Inflow = 4.85 cfs @ 12.01 hrs, Volume= 0.474 af
Outflow = 4.85 cfs @ 12.01 hrs, Volume= 0.474 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach DP 1:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 21


Summary for Reach HDS:

Inflow Area = 0.440 ac, 100.00% Impervious, Inflow Depth = 5.65" for 100-yr event
Inflow = 0.20 cfs @ 11.99 hrs, Volume= 0.207 af
Outflow = 0.20 cfs @ 11.99 hrs, Volume= 0.207 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Reach HDS:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 22

Summary for Pond 1.2P:

Inflow = 3.60 cfs @ 11.99 hrs, Volume= 0.120 af
Outflow = 2.99 cfs @ 12.03 hrs, Volume= 0.120 af, Atten= 17%, Lag= 2.4 min
Primary = 1.80 cfs @ 12.03 hrs, Volume= 0.108 af
Secondary = 1.20 cfs @ 12.03 hrs, Volume= 0.012 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs
Peak Elev= 422.38' @ 12.03 hrs Surf.Area= 0.010 ac Storage= 0.014 af

Plug-Flow detention time= 4.1 min calculated for 0.120 af (100% of inflow)
Center-of-Mass det. time= 4.1 min (725.4 - 721.3)

Volume	Invert	Avail.Storage	Storage Description
#1	420.90'	0.017 af	24.0" Round Pipe Storage x 4 L= 60.0'


Device	Routing	Invert	Outlet Devices
#1	Secondary	421.80'	12.0" Round Culvert L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.80' / 420.70' S= 0.1100 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Primary	420.90'	8.0" Round Culvert L= 10.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 420.90' / 420.70' S= 0.0200 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

Primary OutFlow Max=1.77 cfs @ 12.03 hrs HW=422.35' TW=0.00' (Dynamic Tailwater)
↑**2=Culvert** (Inlet Controls 1.77 cfs @ 5.08 fps)

Secondary OutFlow Max=1.11 cfs @ 12.03 hrs HW=422.35' TW=0.00' (Dynamic Tailwater)
↑**1=Culvert** (Inlet Controls 1.11 cfs @ 2.52 fps)

Pond 1.2P:

Hydrograph



Post Development

NY - 3700 Barger Street 24-hr S1 100-yr Rainfall=9.15"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 9/2/2020

HydroCAD® 10.00-15 s/n 00891 © 2015 HydroCAD Software Solutions LLC

Page 24

Summary for Pond FS:

Inflow Area = 0.440 ac, 100.00% Impervious, Inflow Depth = 8.91" for 100-yr event
 Inflow = 3.80 cfs @ 11.99 hrs, Volume= 0.327 af
 Outflow = 3.80 cfs @ 11.99 hrs, Volume= 0.327 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.20 cfs @ 11.99 hrs, Volume= 0.207 af
 Secondary = 3.60 cfs @ 11.99 hrs, Volume= 0.120 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-40.00 hrs, dt= 0.05 hrs

Peak Elev= 422.95' @ 11.99 hrs

Flood Elev= 423.30'

Device	Routing	Invert	Outlet Devices
#1	Primary	421.30'	4.0" Round Culvert L= 13.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.30' / 420.80' S= 0.0385 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	421.30'	12.0" Round Culvert L= 18.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 421.30' / 420.80' S= 0.0278 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 1	421.30'	2.5" Vert. Orifice/Grate C= 0.600
#4	Device 2	422.50'	4.0' long x 0.5' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

Primary OutFlow Max=0.20 cfs @ 11.99 hrs HW=422.94' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Passes 0.20 cfs of 0.51 cfs potential flow)

↑3=Orifice/Grate (Orifice Controls 0.20 cfs @ 5.97 fps)


Secondary OutFlow Max=3.11 cfs @ 11.99 hrs HW=422.94' TW=422.27' (Dynamic Tailwater)

↑2=Culvert (Inlet Controls 3.11 cfs @ 3.95 fps)

↑4=Broad-Crested Rectangular Weir (Passes 3.11 cfs of 3.49 cfs potential flow)

Pond FS:

Hydrograph



APPENDIX D

Project and Owner Information

Site Data:

3700 Barger Street
Town of Yorktown
New York
Area: 0.49 acres ±

Owner / Applicant Information:

NY Fuel Distributors
235 Mamaroneck Avenue
White Plains, NY 10605

Party Responsible for implementation of the Short and Long-Term Maintenance Plan:

NY Fuel Distributors
235 Mamaroneck Avenue
White Plains, NY 10605

Qualified Professional Responsible for Inspection of the Stormwater Pollution Prevention Plan:

Insite Engineering, Surveying, and Landscape Architecture, P.C.
3 Garrett Place
Carmel, NY 10512

APPENDIX E
Hydrodynamic Separator Sizing Information

NJCAT TECHNOLOGY VERIFICATION

HydroStorm Hydrodynamic Separator

Hydroworks, LLC

February 2018

TABLE OF CONTENTS

List of Figures.....	ii
List of Tables.....	iii
1. Description of Technology.....	1
2. Laboratory Testing.....	3
2.1 Test Setup.....	3
2.2 Hydraulic Testing.....	5
2.3 Removal Efficiency Testing.....	5
2.4 Scour Testing.....	7
2.5 Instrumentation and Measuring Techniques.....	7
2.6 Data Management and Acquisition.....	10
2.7 Quality Assurance and Control.....	11
3. Performance Claims.....	11
4. Supporting Documentation.....	12
4.1 Test Sediment PSD Analysis.....	12
4.2 Removal Efficiency Testing.....	14
4.3 Scour Test.....	26
4.4 Hydraulics.....	29
5. Design Limitations.....	31
6. Maintenance.....	33
7. Statements.....	34
8. References.....	39
Verification Appendix.....	40

LIST OF FIGURES

Figure 1	Hydroworks HydroStorm Operation – Plan View	1
Figure 2	Hydroworks HydroStorm Operation – Profile View	2
Figure 3	Photograph of HS 4 Test Unit Installed in Alden Flow Loop	3
Figure 4	Plan View of Alden Flow Loop	4
Figure 5	Photograph Showing Laboratory Flow Meters	8
Figure 6	Pressure Measurement Instrumentation	8
Figure 7	Photograph Showing Variable-Speed Auger Feeder	9
Figure 8	Photograph Showing the Background Isokinetic Sampler	10
Figure 9	Comparison of PSD Curves of NJDEP and Alden Test Specimens	13
Figure 10	Hydroworks HS 4 Removal Efficiency Curve	15
Figure 11	25% MTFR Measured Flow and Influent Concentrations	17
Figure 12	25% MTFR Measured Background Concentrations	17
Figure 13	50% MTFR Measured Flow and Influent Concentrations	19
Figure 14	50% MTFR Measured Background Concentrations	19
Figure 15	75% MTFR Measured Flow and Influent Concentrations	21
Figure 16	75% MTFR Measured Background Concentrations	21
Figure 17	100% MTFR Measured Flow and Influent Concentrations	23
Figure 18	100% MTFR Measured Background Concentrations	23
Figure 19	125% MTFR Measured Flow and Influent Concentrations	25
Figure 20	125% MTFR Measured Background Concentrations	25
Figure 21	PSD Curves of AGSCO Batch Analysis and NJDEP Specifications	27
Figure 22	Scour Test Recorded Flow Data	27
Figure 23	Scour Test Measured Background and Effluent Concentrations	28
Figure 24	Measured Flow vs Water Elevations	30
Figure 25	Calculated Losses and Insert Outlet Cd	30

LIST OF TABLES

Table 1	NJDEP Target Test Sediment Particle Size Distribution.....	6
Table 2	PSD Analyses of Alden NJDEP 1-1000 Micron Test Sediment	13
Table 3	Test Flow and Temperature Summary.....	14
Table 4	Injected Sediment Summary.....	14
Table 5	Removal Efficiency Summary	15
Table 6	25% MTFR Background and Effluent Concentration Data.....	16
Table 7	50% MTFR Background and Effluent Concentration Data.....	18
Table 8	75% MTFR Background and Effluent Concentration Data.....	20
Table 9	100% MTFR Background and Effluent Concentration Data.....	22
Table 10	125% MTFR Background and Effluent Concentration Data.....	24
Table 11	PSD Analyses of AGSCO NJDEP 50-1000 Batch Mix	26
Table 12	Scour Test Background and Effluent Concentration Data.....	28
Table 13	Recorded Flow and Elevation Data	29
Table A-1	MTFRs and Sediment Removal Intervals for HydroStorm Models.....	42
Table A-2	Standard Dimensions for HydroStorm Models.....	43

1. Description of Technology

The Hydroworks HydroStorm (HS) separator is a unique hydrodynamic by-pass separator. It incorporates a protected submerged pretreatment zone to collect larger solids, a treatment tank to remove finer solids, and a dual set of weirs to create a high flow bypass. High flows are conveyed directly to the outlet and do not enter the treatment area; however, the submerged pretreatment area still allows removal of coarse solids during high flows.

Under normal or low flows, water enters an inlet area with a horizontal grate. The area underneath the grate is submerged with openings to the main treatment area of the separator. Coarse solids fall through the grate and are either trapped in the pretreatment area or conveyed into the main treatment area depending on the flow rate (**Figure 1**). Fines are transported into the main treatment area. Openings and weirs in the pretreatment area allow entry of water and solids into the main treatment area and cause water to rotate in the main treatment area creating a vortex motion. Water in the main treatment area is forced to rise along the walls of the separator to discharge from the treatment area to the downstream pipe.




Figure 1 Hydroworks HydroStorm Operation – Plan View

The vortex motion forces solids and floatables to the middle of the inner chamber. Floatables are trapped since the inlet to the treatment area is submerged. The design maximizes the retention of settled solids since solids are forced to the center of the inner chamber by the vortex motion of water while water must flow up the walls of the separator to discharge into the downstream pipe.

A set of high flow weirs near the outlet pipe create a high flow bypass over both the pretreatment area and main treatment chamber. The rate of flow into the treatment area is regulated by the number and size of openings into the treatment chamber and the height of by-pass weirs. High flows flow over the weirs directly to the outlet pipe preventing the scour and resuspension of any fines collected in the treatment chamber.

A central tube is located in the structure to provide access for cleaning. The arrangement of the inlet area and bypass weirs near the outlet pipe facilitate the use of multiple inlet pipes. **Figure 2** is a profile view of the HydroStorm separator showing the flow patterns for low and high flows.




Figure 2 Hydroworks HydroStorm Operation – Profile View

2. Laboratory Testing

The test program was conducted at the Alden Research Laboratory, Inc. (Alden), Holden, Massachusetts, under the direct supervision of Alden's senior stormwater engineer, James Mailloux. Alden has performed verification testing on approximately twenty Hydrodynamic Separator and Filtration Manufactured Treatment Devices (MTDs) for multiple manufacturers under various state and federal testing protocols. Particle size distribution (PSD) analysis was conducted by GeoTesting Express, Inc., Acton, Massachusetts. GeoTesting is an AALA ISO/IEC 17025 accredited independent laboratory. Water quality samples collected during this testing process were analyzed in Alden's Calibration Laboratory, which is ISO 17025 accredited.

Laboratory testing was done in accordance with the New Jersey Department of Environmental Protection "Laboratory Protocol to Assess Total Suspended Solids Removal by a Hydrodynamic Sedimentation Manufactured Treatment Device" (January 2013a) (NJDEP Hydrodynamic Protocol). Prior to starting the performance testing program, a quality assurance project plan (QAPP) was submitted to, and approved by, the New Jersey Corporation for Advanced Technology (NJCAT).

2.1 Test Setup

The laboratory test used a full-scale Hydroworks HydroStorm separator (model HS 4) installed in a four (4) foot diameter concrete cylindrical test device. The HS 4 had a sump depth of 4 ft and a sump area of 12.57 ft². Aluminum inlet and outlet pipes, 14-inch in diameter, were oriented along the centerline of the unit, with the invert heights located 49 and 47 inches above the sump floor, respectively. The pipes were set with 0.25% slopes. A photograph of the installed unit is shown on **Figure 3**.



Figure 3 Photograph of HS 4 Test Unit Installed in Alden Test Loop

The HS 4 test unit was installed in the Alden test loop, shown on **Figure 4**, which is set up as a recirculation system. The loop is designed to provide metered flow up to approximately 17 cfs, using a calibrated orifice plate and venturi differential-pressure meters. Flow was supplied to the unit using either a 20HP or 50HP laboratory pump (flow dependent), drawing water from a 50,000-gallon supply sump. The test flow was set and measured using a differential-pressure meter and control valve. A Differential Pressure (DP) cell and computer Data Acquisition (DA) program was used to record the test flow. Thirty (30) feet of straight 14-inch influent pipe conveyed the metered flow to the unit. Eight (8) feet of 14-inch piping returned the test flow back to the supply sump. The influent and effluent pipes were set at 0.25% slopes. A 14-inch tee was located 4 pipe-diameters upstream of the test unit for injecting sediment into the crown of the influent pipe, using a variable-speed auger feeder. Filtration of the supply sump, to reduce background concentration, was performed with an in-line filter wall containing 1-micron bag filters.




Figure 4 Plan View of Alden Flow Loop

2.2 Hydraulic Testing

The HS 4 was tested with clean water to determine its hydraulic characteristic curves, including loss coefficients (Cd's) and/or K factors, as well as the maximum flow prior to bypass. Flow and water level measurements were recorded for 15 steady-state flow conditions using the computer DA system, which included a data collection program, a 0-250" Rosemount DP cell, and a Druck 0-2 psi Absolute Pressure (AP) cell. Flows were set and measured using calibrated differential-pressure flow meters and control valves. Each test flow was set and operated at steady state for approximately 10 minutes, after which time a minimum of 60 seconds of flow and pressure data were averaged and recorded for each pressure tap location. Water elevations were measured within the treatment unit in the pretreatment channel, inner chamber, and upstream of the outlet area. Measurements within the influent and effluent pipes were taken one pipe-diameter upstream and downstream of the unit.

2.3 Removal Efficiency Testing

Removal testing was conducted on a clean unit utilizing the end-of-pipe grab sampling methodology. Five sediment removal efficiency tests were conducted at flows corresponding to 25%, 50%, 75%, 100% and 125% of the Maximum Treatment Flow Rate (MTFR). A false floor was installed at the 50% collection sump sediment storage depth of 6", as stated by Hydroworks. All tests were run with clean water containing a sediment solids concentration (SSC) of less than 20 mg/L.

A minimum of 25 lbs of test sediment was introduced into the influent pipe for each test. The moisture content of the test sediment was determined using ASTM D4959-07 for each test conducted. In addition, the criterion of the supply water temperature below 80 degrees F was met for all tests conducted.

The test sediment was prepared by Alden to meet the PSD gradation of 1-1000 microns in accordance with the distribution shown in **Table 1** (NJDEP, 2013a). The sediment is silica based, with a specific gravity of 2.65. Random samples of the test batch were analyzed for PSD compliance by GeoTesting Express, Inc., an independent certified analytical laboratory, using the ASTM D422-63 (2007) analytical method. The average of all the samples was used for compliance with the protocol specification.

The target influent sediment concentration was 200 mg/L (+/-20 mg/L) for all tests. The concentration was verified by collecting a minimum of six timed dry samples at the injector and correlating the data with the measured flow rate. Each sample volume was a minimum of 0.1 liters, with the collection time not exceeding one minute. The allowed Coefficient of Variance (COV) for the measured samples is 0.10. The reported concentration was calculated based on the total mass injected during the test and total volume of water introduced during sediment dosing.

Table 1 NJDEP Target Test Sediment Particle Size Distribution

	TSS Removal Test PSD	Scour Test Pre-load PSD
Particle Size (Microns)	Target Minimum % Less Than²	Target Minimum % Less Than³
1,000	100	100
500	95	90
250	90	55
150	75	40
100	60	25
75	50	10
50	45	0
20	35	0
8	20	0
5	10	0
2	5	0

1. The material shall be hard, firm, and inorganic with a specific gravity of 2.65. The various particle sizes shall be uniformly distributed throughout the material prior to use.

2. A measured value may be lower than a target minimum % less than value by up to two percentage points, provided the measured d₅₀ value does not exceed 75 microns.

3. This distribution is to be used to pre-load the MTD's sedimentation chamber for off-line and on-line scour testing.

Eight (8) background samples of the supply water were collected using an isokinetic sampler at evenly-spaced intervals throughout each test. Collected samples were analyzed for Suspended Solids Concentration (SSC) using ASTM D3977-97 (2013). A 3rd-order curve and corresponding equation was developed for calculating the adjusted effluent concentrations. A correction was made to each timestamp to account for the detention time between the background and effluent sampling locations. The sampler was allowed to flow for the duration of all tests except 25% MTFR, for which the sampler valve was closed after the collection of each sample. The average recorded inflow was adjusted to account for the sampler flow.

Fifteen (15) effluent samples were collected from the end of the effluent pipe at evenly-spaced intervals, using 1-L wide-mouth bottles. Sampling was started after a minimum of three (3) detention times following the initiation of sediment injection, as well as after the interruption of sediment feed for injection verification.

2.4 Scour Testing

A sediment scour test was conducted to evaluate the ability of the HydroStorm to retain captured material during high flows. The 50% capacity (6 inches) false floor was left installed in the collection sump and 4-inches of 50-1000-micron sediment were pre-loaded on the floor. This resulted in preloading to the 83% (10 inches) storage capacity level. All test sediment was evenly distributed and levelled prior to testing.

The unit was filled with clean water (< 20 mg/L background) to the invert of the outlet pipe prior to testing. Testing was conducted at a temperature not exceeding 80 degrees F. The test was initiated within 96 hours of filling the unit.

The test was conducted at 200% MTFR for on-line certification. Testing consisted of conveying the selected target flow through the unit and collecting 15 time-stamped effluent samples (every 2 minutes) for SSC analysis, and a minimum of eight (8) time-stamped background samples evenly spaced throughout the test. The target flow was reached within 5 minutes of commencement of the test. Flow data was continuously recorded every 5 seconds throughout the test and correlated with the samples.

Effluent samples for sediment concentration were collected from the end of the outlet pipe with the use of 1-L bottles.

2.5 Instrumentation and Measuring Techniques

Flow

The inflow to the test unit was measured using one of five (5) calibrated differential-pressure flow meters (2", 4", 6", 8" or 12"). Each meter is fabricated per ASME guidelines and calibrated in Alden's Calibration Department prior to the start of testing. Flows were set with a butterfly valve and the differential head from the meter was measured using the Rosemount® 0 to 250-inch DP cell, also calibrated at Alden prior to testing. The test flow was averaged and recorded every 5-30 seconds (flow dependent) throughout the duration of the test using the in-house computerized DA program. The accuracy of the flow measurement is $\pm 2\%$. A photograph of the flow meters is shown on **Figure 5**.

Temperature

Water temperature measurements within the supply sump were obtained using a calibrated Omega® DP25 temperature probe and readout device. The calibration was performed at the Alden laboratory prior to testing. The temperature reading was documented at the start and end of each test, to ensure an acceptable testing temperature of less than 80 degrees F.



Figure 5 Photograph Showing Laboratory Flow Meters

Pressure Head

Pressure head measurements were recorded at multiple locations using piezometer taps and a Druck[®], Model PTX510, 0 - 2.0 psi cell. The pressure cell was calibrated at Alden prior to testing. Accuracy of the readings is ± 0.001 ft. The cell was installed at a known datum in relation to the tank floor, allowing for elevation readings through the full range of flows. A minimum of 60 seconds of pressure data was averaged and recorded for each pressure tap during steady-state hydraulic testing, using the computerized DA program. A photograph of the pressure measurement instrumentation is shown on **Figure 6**




Figure 6 Pressure Measurement Instrumentation

Sediment Injection

The test sediment was injected into the crown of the influent pipe using an Auger® volumetric screw feeder, model VF-1, shown on **Figure 7**. The feed screws used in testing ranged in size from 0.5-inch to 1.0 inch, depending on the test flow. Each auger screw, driven with a variable-speed drive, was calibrated with the test sediment prior to testing, to establish a relationship between the auger speed (0-100%) and feed rate in mg/minute. The calibration, as well as test verification of the sediment feed was accomplished by collecting 1-minute timed dry samples and weighing them on an Ohaus® 4000g x 0.1g, model SCD-010 digital scale. The feeder has a hopper at the upper end of the auger to provide a constant supply of dry test sand.



Figure 7 Photograph Showing Variable-Speed Auger Feeder

Sample Collection

Effluent samples were collected in 1-L bottles from the end of the pipe for sediment concentration analyses. Background concentration samples were collected from the center of the vertical pipe upstream of the test unit with the use of a 0.75-inch isokinetic sampler, shown on **Figure 8**.



Figure 8 Photograph Showing the Background Isokinetic Sampler

Sample Concentration Analysis

Effluent and background concentration samples were analyzed by Alden in accordance with Method B, as described in ASTM Designation: D 3977-97 (Re-approved 2013), “Standard Test Methods for Determining Sediment Concentration in Water Samples”. The required silica sand used in the sediment testing did not result in any dissolved solids in the samples and therefore, simplified the ASTM testing methods for determining sediment concentration.

2.6 Data Management and Acquisition

A designated Laboratory Records Book was used to document the conditions and pertinent data entries for each test conducted. All entries are initialed and dated.

A personal computer running an Alden in-house Labview[®] Data Acquisition program was used to record all data related to instrument calibration and testing. A 16-bit National Instruments[®] NI6212 Analog to Digital (A/D) board was used to convert the signal from the pressure cells to a voltage. Alden’s in-house data collection software, by default, collects one-second averages of data collected at a raw rate of 250 Hz. The system allows very long contiguous data collection by continuously writing the collected 1-second averages and their RMS values to disk. The data output from the program is in tab delimited text format with a user-defined number of significant figures.

Test flow and pressure data were continuously collected at a frequency of 250 Hz. The flow data was averaged and recorded to file every 5 to 30 seconds, depending on the duration of the test. Steady-state pressure data was averaged and recorded over a duration of 60 seconds for each point. The recorded data files were imported into Excel for further analysis and plotting.

Excel based data sheets were used to record all sediment related data used for quantifying injection rate, effluent and background sample concentrations, captured mass and PSD data. The data was input to the designated spreadsheet for final processing.

2.7 Quality Assurance and Control

All instruments were calibrated prior to testing and periodically checked throughout the test program. Instrumentation calibrations were provided.

Flow

The flow meters and pressure cells were calibrated in Alden's Calibration Laboratory. All pressure lines were purged of air prior to initiating each test. A standard water manometer board and Engineers Rule were used to measure the differential pressure and verify the computer measurement of the selected flow meter.

Sediment Injection

The sediment feed (g/min) was verified with the use of a digital stop watch and 4000g calibrated digital scale. The tare weight of the sample container was recorded prior to collection of each sample. The samples were a minimum of 0.1 liters in size, with a maximum collection time of 1-minute. The final sediment concentrations were adjusted for moisture.

Sediment Concentration Analysis

All sediment concentration samples were processed in accordance with the ASTM D3977-97 (2013) analytical method. Gross sample weights were measured using a 4000g x 0.1g calibrated digital scale. The dried sample weights were measured with a calibrated 0.0001g analytical balance. The change in filter weight due to processing was accounted for by including three control filters with each test set. The average of the three values, which was typically (+/- 0.1mg), was used in the final concentration calculations.

Analytical accuracy was verified by preparing two blind control samples and processing using the ASTM method. The final calculated values were within 0.26% and 0.87% of the theoretical sample concentrations, with an average of 0.57% accuracy.

3. Performance Claims

Per the NJDEP verification procedure, the following are the performance claims for the Hydroworks HS 4 based on the results of the laboratory testing conducted.

Total Suspended Solids (TSS) Removal Efficiency

The TSS removal rate of the Hydroworks HS 4 was calculated using the weighted method required by the NJDEP HDS MTD protocol. Based on a MTFR of 0.88 cfs, the HS 4 achieved a weighted TSS removal rate of 50%.

Maximum Treatment Flow Rate (MTFR).

The Hydroworks HS 4 had a total sedimentation area of 12.57 ft² and demonstrated a maximum treatment flow rate (MTFR) of 0.88 cfs (395 gpm). This corresponds to a surface loading rate of 31.4 gpm/ft² of sedimentation area.

Maximum Sediment Storage Depth and Volume

The maximum sediment storage depth is 12” which equates to 12.6 ft³ of sediment storage volume. A sediment storage depth of 6 inches corresponds to 50% full sediment storage capacity (6.3 ft³).

Effective Treatment/Sedimentation Area

The effective treatment area is 12.57 ft².

Detention Time and Wet Volume

The wet volume for the HS 4 is 375 gallons. The detention time of the HS 4 is dependent upon flow rate. At the MTFR, the detention time in the HS 4 is 57 seconds.

Online/Offline Installation

Based on the scour testing results the Hydroworks HS 4 qualifies for online installation.

4. Supporting Documentation

The NJDEP Procedure (NJDEP, 2013b) for obtaining verification of a stormwater manufactured treatment device (MTD) from the New Jersey Corporation for Advanced Technology (NJCAT) requires that “copies of the laboratory test reports, including all collected and measured data; all data from performance evaluation test runs; spreadsheets containing original data from all performance test runs; all pertinent calculations; etc.” be included in this section. This was discussed with NJDEP and it was agreed that as long as such documentation could be made available by NJCAT upon request that it would not be prudent or necessary to include all this information in this verification report. This information was provided to NJCAT and is available upon request.

4.1 Test Sediment PSD Analysis

A commercially-available blend (AGSCO NJDEP 1-1000) was provided by AGSCO Corp., a QAS International ISO-9001 certified company, and adjusted by Alden to meet the NJDEP %-finer acceptance criteria. Test batches of approximately 30 lbs each were prepared in individual 5-gallon buckets, which were arbitrarily selected for each removal test. A well-mixed sample was collected from four (4) random test batches and analyzed for PSD by GeoTesting Express. The average of the samples was used for compliance to the protocol specifications. The D₅₀ of the samples ranged from 63 to 71 microns, with an average of 67 microns. The PSD data of the

samples are shown in **Table 2** and the corresponding curves are shown on **Figure 9**. The specific gravity of the sediment mix was 2.65.

Table 2 PSD Analysis of Alden NJDEP 1-1000 Micron Test Sediment

Particle size (µm)	NJDEP Target (percent-finer)	Test Sediment Particle Size Distribution (percent-finer)					QA / QC Compliant
		Bucket 1	Bucket 6	Bucket 10	Bucket 14	Average	
1000	100	100	100	100	100	100	Yes
500	95	96	95	95	96	96	Yes
250	90	91	90	90	92	91	Yes
150	75	75	74	76	77	76	Yes
100	60	61	60	60	61	61	Yes
75	50	52	51	51	52	52	Yes
50	45	46	45	46	47	46	Yes
20	35	35	35	36	36	35	Yes
8	20	21	20	22	22	21	Yes
5	10	14	14	16	16	15	Yes
2	5	6	7	7	7	7	Yes
D ₅₀	75	65	71	68	63	67	Yes

The sediment particle size distribution (PSD) used for removal efficiency testing exceeded the NJDEP PSD sediment specifications (**Table 1**) across the entire distribution. The D50 of 67 microns was less than the required 75 microns.




Figure 9 Comparison of PSD Curves of NJDEP and Alden Test Sediments

4.2 Removal Efficiency Testing

Summary

Removal efficiency tests were conducted at the five (5) required flows of 25%, 50%, 75%, 100% and 125% MTRF. The 100% MTRF was 0.88 cfs, resulting in target flows of 0.22, 0.44, 0.66, 0.88 and 1.10 cfs. The 25% MTRF test flow was slightly greater than the +10% target allowance (+13.7%). However, since the higher flow will result in a slightly lower removal efficiency, the measured removal efficiency is deemed conservative and, therefore, the data from this run was accepted. The target influent sediment concentration was 200 mg/l.

The target and measured flow and temperature parameters are shown in **Table 3** and the injected sediment and background data summary is shown in **Table 4**.

Table 3 Test Flow and Temperature Summary

MTRF	Target Flow		Measured Flow		Deviation from Target	Flow Measurement COV	Maximum Temperature	QA/QC Compliant
	cfs	gpm	cfs	gpm				
							Deg. F	
25%	0.22	98.7	0.25	112.2	13.7%	0.001	62.5	No
50%	0.44	197.5	0.44	195.4	-1.1%	0.002	67.8	Yes
75%	0.66	296.2	0.67	298.7	0.8%	0.004	72.4	Yes
100%	0.88	395.0	0.84	378.4	-4.2%	0.003	76.1	Yes
125%	1.10	493.7	0.99	446.6	-9.5%	0.002	75.7	Yes

Table 4 Injected Sediment Summary

Flow	Target Concentration	Average Injected Concentration	Injector Measurements COV	Mass/Volume Concentration	Injected Mass	Maximum Background Concentration	QA/QC Compliant
gpm	mg/L	mg/L		mg/L	lbs	mg/L	
112.2	200	202	0.01	188	27.28	4.42	Yes
195.4	200	199	0.00	188	26.81	3.54	Yes
298.7	200	209	0.00	209	28.10	8.09	Yes
378.4	200	206	0.00	191	25.92	6.82	Yes
446.6	200	199	0.00	198	26.99	8.91	Yes

Average Influent TSS (mass/volume concentration)

$$\text{Average Influent TSS} \left(\frac{mg}{L} \right) = \frac{\text{Average Feed Rate} \left(\frac{g}{min} \right) \times \frac{1000 \text{ mg}}{g}}{\text{Average Water Flow Rate} \left(\frac{gal}{min} \right) \times \frac{3.785 \text{ L}}{gal}}$$

At the end of each test run, the collected effluent and background samples were processed and quantified. The calculated removal efficiencies ranged from 42.8% to 58.5%, with a weighted removal of 50.1% for the five (5) flows tested. The removal efficiency summary is shown **Table 5** with the corresponding removal curve shown on **Figure 10**. Data for individual flow rate tests is presented in each testing sub-section.

Repeat Tests

It was required to repeat the 50% and 100% MTRF tests due to the background concentrations exceeding the 20 mg/L acceptance limit.

Table 5 Removal Efficiency Summary

Flow	Influent Concentration	Average Adjusted Effluent Concentration	Removal Efficiency	Weight Factor	Weighted Removal
gpm	mg/L	mg/L			
112.2	188.2	78.1	58.5%	0.25	14.6%
195.4	188.3	89.9	52.3%	0.30	15.7%
298.7	208.7	115.7	44.6%	0.20	8.9%
378.4	191.0	107.6	43.7%	0.15	6.6%
446.6	197.7	113.0	42.8%	0.10	4.3%
				1.00	50.1%




Figure 10 Hydroworks HS 4 Removal Efficiency Curve

25% MTFR (99 gpm)

The test was conducted over a period of 160 minutes. The flow exceeded the +10% tolerance, hence the removal efficiency is considered conservative. The resulting removal efficiency was 58.5%. The test flow was averaged and recorded every 10 seconds throughout the test. The average recorded test flow was 112 gpm, with a COV of 0.001. The recorded temperature for the full test ranged from 61.6 to 62.5 degrees F. The resulting data is shown in **Table 6**.

The injection feed rate of 84.8 g/min was verified by collecting 1-minute weight samples from the injector. The measured influent injection concentrations for the full test ranged from 200 to 206 mg/L, with a mean of 202 mg/L and COV of 0.01. The total mass injected into the unit was 27.3 lbs. The calculated mass-volume concentration for the test was 188 mg/L.

The measured influent concentration and flow data for the complete test is shown on **Figure 11**.

Eight (8) background concentrations samples were collected throughout the test and ranged from 0.3 to 4.4 mg/L. The background curve and equation are shown on **Figure 12**.

Table 6 25% MTFR Background and Effluent Concentration Data

Injection Sample	Sample Time minutes	Sample ID	Sample Time minutes	Effluent Concentration mg/L	Background Concentration mg/L	Adjusted Effluent mg/L
Inj 1	2	Eff 1, BG 1	12	77.7	0.6	77.1
Inj 2	30	Eff 2	18	71.1	0.6	70.6
Inj 3	59	Eff 3, BG 2	24	81.7	0.6	81.1
Inj 4	87	Eff 4	41	71.3	1.0	70.3
Inj 5	115	Eff 5, BG 3	47	67.7	1.3	66.5
Inj 6	144	Eff 6	53	60.1	1.6	58.5
Injection Sampling Duration 60 seconds		Eff 7, BG 4	69	78.0	2.4	75.5
		Eff 8	75	73.2	2.8	70.4
		Eff 9, BG 5	81	87.8	3.1	84.7
		Eff 10	98	93.5	3.9	89.6
		Eff 11, BG 6	104	87.4	4.1	83.3
		Eff 12	110	79.2	4.2	75.0
		Eff 13, BG 7	126	85.9	4.2	81.7
		Eff 14	132	81.8	4.0	77.8
		Eff 15, BG 8	138	113.0	3.8	109.3
					Average	78.1
Detention Time (seconds) = 186						
Detention Volume Based on Hydraulic Head (cu.ft.) = 46.5						
Mass/Volume Influent Concentration (mg/L) = 188						




Figure 11 25% MTFR Measured Flow and Influent Concentrations




Figure 12 25% MTFR Measured Background Concentrations

50% MTFR (197 gpm)

The test was conducted over a period of 94 minutes. The resulting removal efficiency was 52.3%. The test flow was averaged and recorded every 10 seconds throughout the test. The adjusted average recorded test flow was 195 gpm, with a COV of 0.002. The recorded temperature for the full test ranged from 67.7 to 67.8 degrees F. The resulting data is shown in **Table 7**.

The injection feed rate of 147.6 g/min was verified by collecting 1-minute weight samples from the injector. The measured influent injection concentrations for the full test ranged from 199 to 200 mg/L, with a mean of 199 mg/L and COV of 0.00. The total mass injected into the unit was 26.8 lbs. The calculated mass-volume concentration for the test was 188 mg/L.

The measured influent concentration and flow data for the complete test is shown on **Figure 13**.

Eight (8) background concentrations samples were collected throughout the test and ranged from 0.0 to 3.5 mg/L. The background curve and equation are shown on **Figure 14**.

Table 7 50% MTFR Background and Effluent Concentration Data

Injection Sample	Sample Time minutes	Sample ID	Sample Time minutes	Effluent Concentration mg/L	Background Concentration mg/L	Adjusted Effluent mg/L
Inj 1	2	Eff 1, BG 1	9	51.2	0.0	51.2
Inj 2	18	Eff 2	12	85.1	0.1	85.0
Inj 3	34	Eff 3, BG 2	15	94.3	0.2	94.1
Inj 4	50	Eff 4	25	93.0	0.5	92.5
Inj 5	66	Eff 5, BG 3	28	91.5	0.6	90.8
Inj 6	82	Eff 6	31	91.8	0.7	91.1
Injection Sampling Duration 60 seconds		Eff 7, BG 4	41	89.1	1.1	87.9
		Eff 8	44	99.6	1.2	98.3
		Eff 9, BG 5	47	96.5	1.4	95.1
		Eff 10	57	96.9	1.9	95.0
		Eff 11, BG 6	60	90.1	2.1	88.1
		Eff 12	63	100.0	2.3	97.8
		Eff 13, BG 7	73	97.0	3.0	94.0
		Eff 14	76	125.9	3.2	122.7
		Eff 15, BG 8	79	67.6	3.5	64.1
					Average	89.8
Detention Time (seconds) = 112						
Detention Volume Based on Hydraulic Head (cu.ft.) = 48.8						
Mass/Volume Influent Concentration (mg/L) = 188						




Figure 13 50% MTR Measured Flow and Influent Concentrations




Figure 14 50% MTR Measured Background Concentrations

75% MTFR (296 gpm)

The test was conducted over a period of 60 minutes. The resulting removal efficiency was 44.6%. The test flow was averaged and recorded every 10 seconds throughout the test. The adjusted average recorded test flow was 299 gpm, with a COV of 0.004. The recorded temperature for the full test ranged from 72.1 to 72.4 degrees F. The resulting data is shown in **Table 8**.

The injection feed rate of 227.1 g/min was verified by collecting 1-minute weight samples from the injector. The measured influent injection concentrations for the full test ranged from 209 to 210 mg/L, with a mean of 209 mg/L and COV of 0.00. The total mass injected into the unit was 28.1 lbs. The calculated mass-volume concentration for the test was 209 mg/L.

The measured influent concentration and flow data for the complete test is shown on **Figure 15**.

Eight (8) background concentrations samples were collected throughout the test and ranged from 0.9 to 8.1 mg/L. The background curve and equation are shown on **Figure 16**.

Table 8 75% MTFR Background and Effluent Concentration Data

Injection Sample	Sample Time minutes	Sample ID	Sample Time minutes	Effluent Concentration mg/L	Background Concentration mg/L	Adjusted Effluent mg/L
Inj 1	2	Eff 1, BG 1	6	107.1	1.2	105.8
Inj 2	13	Eff 2	8	109.7	1.0	108.7
Inj 3	24	Eff 3, BG 2	10	110.3	0.9	109.4
Inj 4	35	Eff 4	17	125.1	0.8	124.3
Inj 5	46	Eff 5, BG 3	19	120.7	0.9	119.9
Inj 6	57	Eff 6	21	139.0	1.0	138.1
Injection Sampling Duration 60 seconds		Eff 7, BG 4	28	108.9	1.7	107.2
		Eff 8	30	114.8	2.0	112.8
		Eff 9, BG 5	32	117.0	2.3	114.7
		Eff 10	39	120.3	3.5	116.7
		Eff 11, BG 6	41	128.7	4.0	124.8
		Eff 12	43	128.9	4.4	124.5
		Eff 13, BG 7	50	85.4	6.0	79.4
		Eff 14	52	137.1	6.5	130.7
		Eff 15, BG 8	54	124.8	7.0	117.8
					Average	115.7
Detention Time (seconds) = 75						
Detention Volume Based on Hydraulic Head (cu.ft.) = 50.0						
Mass/Volume Influent Concentration (mg/L) = 209						




Figure 15 75% MTR Measured Flow and Influent Concentrations




Figure 16 75% MTR Measured Background Concentrations

100% MTFR (395 gpm)

The test was conducted over a period of 48 minutes. The resulting removal efficiency was 43.7%. The test flow was averaged and recorded every 10 seconds throughout the test. The adjusted average recorded test flow was 378 gpm, with a COV of 0.003. The recorded temperature for the full test ranged from 76.0 to 76.1 degrees F. The resulting data is shown in **Table 9**.

The injection feed rate of 288.8 g/min was verified by collecting 45-second weight samples from the injector. The measured influent injection concentrations for the full test ranged from 206 to 207 mg/L, with a mean of 206 mg/L and COV of 0.00. The total mass injected into the unit was 25.9 lbs. The calculated mass-volume concentration for the test was 191 mg/L.

The measured influent concentration and flow data for the complete test is shown on **Figure 17**.

Eight (8) background concentrations samples were collected throughout the test and ranged from 0.0 to 6.8 mg/L. The background curve and equation are shown on **Figure 18**.

Table 9 100% MTFR Background and Effluent Concentration Data

Injection Sample	Sample Time minutes	Sample ID	Sample Time minutes	Effluent Concentration mg/L	Background Concentration mg/L	Adjusted Effluent mg/L
Inj 1	2	Eff 1, BG 1	5	89.2	0.2	89.0
Inj 2	11	Eff 2	7	104.4	0.1	104.2
Inj 3	20	Eff 3, BG 2	9	107.5	0.1	107.4
Inj 4	29	Eff 4	14	99.9	0.2	99.7
Inj 5	38	Eff 5, BG 3	16	97.1	0.3	96.8
Inj 6	47	Eff 6	18	107.7	0.4	107.3
Injection Sampling Duration 45 seconds		Eff 7, BG 4	23	104.9	0.9	104.0
		Eff 8	25	128.2	1.1	127.1
		Eff 9, BG 5	27	113.3	1.4	111.9
		Eff 10	32	137.8	2.3	135.5
		Eff 11, BG 6	34	121.6	2.7	118.9
		Eff 12	36	126.9	3.2	123.7
		Eff 13, BG 7	41	109.0	4.5	104.5
		Eff 14	43	124.6	5.1	119.5
		Eff 15, BG 8	45	69.8	5.7	64.1
					Average	107.6
Detention Time (seconds) = 60						
Detention Volume Based on Hydraulic Head (cu.ft.) = 51.0						
Mass/Volume Influent Concentration (mg/L) = 191						




Figure 17 100% MTR Measured Flow and Influent Concentrations




Figure 18 100% MTR Measured Background Concentrations

125% MTFR (494 gpm)

The test was conducted over a period of 41 minutes. The resulting removal efficiency was 42.8%. The test flow was averaged and recorded every 10 seconds throughout the test. The adjusted average recorded test flow was 447 gpm, with a COV of 0.002. The recorded temperature for the full test was 75.7 degrees F. The resulting data is shown in **Table 10**.

The injection feed rate of 339.8 g/min was verified by collecting 30-second weight samples from the injector. The measured influent injection concentrations for the full test ranged from 198 to 199 mg/L, with a mean of 199 mg/L and COV of 0.00. The total mass injected into the unit was 27.0 lbs. The calculated mass-volume concentration for the test was 198 mg/L.

The measured influent concentration and flow data for the complete test is shown on **Figure 19**.

Eight (8) background concentrations samples were collected throughout the test and ranged from 1.5 to 8.9 mg/L. The background curve and equation are shown on **Figure 20**.

Table 10 125% MTFR Background and Effluent Concentration Data

Injection Sample	Sample Time minutes	Sample ID	Sample Time minutes	Effluent Concentration mg/L	Background Concentration mg/L	Adjusted Effluent mg/L
Inj 1	2	Eff 1, BG 1	5	126.9	1.7	125.2
Inj 2	10	Eff 2	7	118.0	1.6	116.5
Inj 3	17	Eff 3, BG 2	8	107.6	1.5	106.1
Inj 4	25	Eff 4	13	109.0	1.5	107.5
Inj 5	32	Eff 5, BG 3	14	106.2	1.6	104.7
Inj 6	40	Eff 6	16	118.5	1.7	116.8
Injection Sampling Duration 30 seconds		Eff 7, BG 4	20	113.1	2.4	110.7
		Eff 8	22	121.7	2.7	119.0
		Eff 9, BG 5	23	125.3	3.1	122.2
		Eff 10	28	121.5	4.3	117.2
		Eff 11, BG 6	29	125.9	4.8	121.0
		Eff 12	31	116.6	5.3	111.3
		Eff 13, BG 7	35	113.8	7.0	106.8
		Eff 14	37	108.7	7.6	101.1
		Eff 15, BG 8	38	117.2	8.2	108.9
					Average	113.0
Detention Time (seconds) = 52						
Detention Volume Based on Hydraulic Head (cu.ft.) = 51.9						
Mass/Volume Influent Concentration (mg/L) = 198						




Figure 19 125% MTR Measured Flow and Influent Concentrations




Figure 20 125% MTR Measured Background Concentrations

4.3 Scour Test

The commercially-available AGSCO NJDEP 50-1000 certified sediment mix was utilized for the scour test. Three random samples of the batch mix were analyzed in accordance with ASTM D422-63 (2007), by CTLGroup prior to testing. The specified less-than (%-finer) values of the sample average were within the specifications listed in Column 3 of **Table 1**, as defined by the protocol. The D₅₀ of the 3-sample average was 202 microns. The PSD data of the samples are shown in **Table 11** and the corresponding curves, including the initial AGSCO in-house analysis, are shown on **Figure 21**.

The scour test was conducted with the 50% capacity (6”) false floor installed. An additional 4” of the 50-1000-micron test sediment was preloaded on top of the false floor, resulting in the unit being preloaded to the 83% storage capacity of 10”.

The test was conducted at a target flow of 900 gpm, which is equal to 228% MTFR. The flow data was recorded every 5 seconds throughout the test and is shown on **Figure 22**. The target flow was reached within 5 minutes of initiating the test. The average recorded steady-state flow was 903 gpm, with a COV of 0.002. The recorded water temperature was 66.2 degrees F.

Eight background samples were collected throughout the duration of the test. The measured concentrations ranged from 1.2 to 3.1 mg/L, with an average concentration of 2.2 mg/L.

A total of 15 effluent samples were collected throughout the test. The measured concentrations ranged from 10.9 to 30.3 mg/L, with an average concentration of 16.8 mg/L. The average adjusted effluent concentration for the test was 14.6 mg/L. The effluent and background concentration data are shown in **Table 12** and on **Figure 23**.

Table 11 PSD Analyses of AGSCO NJDEP 50-1000 Batch Mix

Particle size (µm)	NJDEP %-Finer Specifications	Test Sediment Particle Size (%Finer)			
		Sample 1	Sample 2	Sample 3	Average
1000	100	100	100	100	100
500	90	95	95	95	95
250	55	58	58	59	58
150	40	41	41	42	41
100	25	23	23	23	23
75	10	10	10	11	10
50	0	1	1	1	1




Figure 21 PSD Curves of AGSCO Batch Analysis and NJDEP Specifications




Figure 22 Scour Test Recorded Flow Data

Table 12 Scour Test Background and Effluent Concentration Data

Sample ID	Timestamp (minutes)	Effluent Concentration (mg/L)	Background Concentration (mg/L)	Adjusted Effluent Concentration (mg/L)
EFF 1	6	30.3	1.2	29.1
EFF 2	8	18.4	1.3	17.1
EFF 3	10	24.9	1.4	23.5
EFF 4	12	16.9	2.2	14.7
EFF 5	14	10.9	3.1	7.8
EFF 6	16	19.5	2.6	16.9
EFF 7	18	15.9	2.0	13.9
EFF 8	20	18.0	2.3	15.7
EFF 9	22	12.1	2.5	9.6
EFF 10	24	14.5	2.5	12.0
EFF 11	26	10.9	2.5	8.4
EFF 12	28	15.8	2.4	13.4
EFF 13	30	16.0	2.2	13.8
EFF 14	32	16.5	2.3	14.2
EFF 15	34	11.3	2.4	8.9
Average		16.8	2.2	14.6




Figure 23 Scour Test Measured Background and Effluent Concentrations

4.4 Hydraulics

Flow (gpm) and water level (ft) within the unit were measured for 15 flows ranging from 0 to 1745 gpm (3.9 cfs). The influent pipe was flowing full at approximately 1500 gpm. The entrance to the effluent pipe was submerged at approximately 1745 gpm. The flow reached bypass at approximately 430 gpm. The recorded data and calculated losses are shown in **Table 13**. The Elevation Curves for five (5) locations are shown on **Figure 24**.

Table 13 Recorded Flow and Elevation Data

Measured Flow		Water Elevations (adjusted to outlet invert)					Losses				
		Inlet Pipe A ft	Inlet Area sq-ft	Pretreatment Channel B ft	Inner Chamber C ft	Outlet Shelf D ft	Outlet Pipe E ft	Inlet El. (A') Corrected for Energy ft	Outlet El. (E') Corrected for Energy ft	System Energy Loss A'-E' ft	Loss Coeff. Outlet Area Cd
0	0	0.170	0.000	0.000	0.000	0.000	-0.009	0.170	0.000	0.000	0.000
25.0	0.06	0.249	0.032	0.153	0.129	0.128	0.064	0.297	0.155	0.142	0.025
50.2	0.11	0.284	0.054	0.201	0.187	0.186	0.095	0.350	0.211	0.139	0.050
100.4	0.22	0.326	0.086	0.284	0.267	0.262	0.144	0.432	0.279	0.153	0.095
150.9	0.34	0.357	0.111	0.360	0.330	0.321	0.185	0.499	0.332	0.166	0.137
202.1	0.45	0.389	0.140	0.433	0.389	0.372	0.219	0.551	0.382	0.169	0.182
278.1	0.62	0.520	0.270	0.545	0.468	0.433	0.265	0.602	0.444	0.157	0.260
350.1	0.78	0.647	0.412	0.653	0.539	0.484	0.300	0.703	0.500	0.203	0.288
431.2	0.96	0.802	0.592	0.803	0.616	0.541	0.342	0.843	0.552	0.291	0.296
502.4	1.12	0.858	0.657	0.871	0.672	0.596	0.371	0.903	0.598	0.305	0.337
602.1	1.34	0.916	0.722	0.927	0.728	0.639	0.418	0.970	0.654	0.316	0.397
702.1	1.56	0.960	0.771	0.973	0.779	0.702	0.461	1.024	0.707	0.317	0.462
999.6	2.23	1.094	0.909	1.091	0.906	0.797	0.571	1.187	0.856	0.332	0.643
1514.0	3.37	1.289	1.054	1.295	1.141	1.024	0.724	1.448	1.088	0.360	0.934
1745.4	3.89	1.404	1.069	1.409	1.271	1.199	0.728	1.610	1.205	0.405	1.016

As seen on **Figure 25**, the calculated system energy loss (influent to effluent) ranged from 0 to 0.291 ft at the point of bypass (431 gpm). The loss decreased as expected due to bypass flow and started increasing once the water elevation reached the top of the outlet pipe. The maximum calculated system loss at 1745 gpm was 0.405 ft. The loss coefficient (Cd) for the insert was based on the area of the insert outlet (0.75 ft²). The Cd values prior to bypass ranged from 0.03 to 0.30.




Figure 24 Measured Flow vs Water Elevations




Figure 25 Calculated Losses and Insert Outlet Cd

5. Design Limitations

Hydroworks has been designing separators for site specific applications for over 15 years. Site constraints and design requirements are addressed on a project specific basis. Sizing calculations are performed based on site specific criteria and submittals are provided upon request. Hydraulic assessments including hydraulic gradeline calculations, and buoyancy calculations are provided as part of the design as required.

Required Soil Characteristics

The Hydroworks HS is delivered to the job site as a complete pre-assembled unit housed in a concrete structure. The hydrodynamic separator can be modified to account for most soil conditions (bearing capacity, chemistry, contamination) through changes in footprint, materials and coatings.

Pipe Slope

The Hydroworks HS can be designed as an inlet structure and as a drainage structure with horizontal inlet pipes. Typical pipe slopes range from 0.2% (scour velocity) to 5 % and the use of the HS is acceptable without alteration for these slopes. Higher pipe slopes should be reviewed for hydraulics since the higher velocities will trigger greater headloss and the flow rate for bypass needs to be reviewed to determine if the height of the weirs needs to be modified for site specific conditions.

Invert to Grade

The depth of pipe burial (invert to grade) needs to be reviewed to ensure proper pipe cover for traffic loading and frost requirements as well as constructability/conflicts with minimum product dimensions (thickness of top cap/height of frame and cover). Most design conditions can be accommodated through site specific design changes (ex. Embedding frame and cover in the top cap).

Maximum Flow Rate

Maximum treatment flow rate is dependent on model size. The Hydroworks HS will be sized in New Jersey based upon the NJCAT tested hydraulic loading rate of 31.4 gallons per minute per square foot of settling surface area. Section 6 includes details pertaining to inspection and maintenance of the Hydroworks HS.

Maintenance Requirements

Requirements pertaining to maintenance of the Hydroworks HS will vary depending on pollutant loading and individual site conditions. It is recommended that the system be inspected at least twice during the first year to determine loading conditions for each site. These first-year inspections can be used to establish inspection and maintenance frequency for subsequent years. A maintenance manual is available for download from the Hydroworks website.

Ensuring Proper Installation

All components are pre-installed at the manufacturing plant prior to delivery so installing the separator is the same as installing a standard drainage structure. The inlet and outlet are clearly marked on the precast, so the contractor can properly orient the structure. The contractor is provided with drawings that show the orientation of the cap, inlet and outlet pipes orientation and size, rim and invert elevations, the number of concrete pieces, and heaviest picks. Match lines are provided on the precast pieces to ensure the top cap is properly oriented for maintenance access. The cast iron cap is provided with the structure and is embossed with “Hydroworks” to ensure the structure is easily located for maintenance.

Configurations

The Hydroworks HS separator is available in various configurations. The units can be installed online or offline. The HydroStorm separator has an internal bypass which allows for it to be installed online without the need for any external high flow diversion structure. The Hydroworks HS separator can accept multiple inlet pipes without any modification to the system.

Structural Load Limitations

The Hydroworks HS is housed in a pre-cast concrete structure. All structures are designed for traffic loading based on the standard AASHTO H20 design standard. Installations requiring heavier loading (airports) or non-traffic bearing locations can be accommodated based on a site-specific design by including more or less structural steel and/or greater or less concrete thickness.

Pre-treatment Requirements

The Hydroworks HS has no pre-treatment requirements.

Tailwater Considerations

Site specific tailwater conditions must be assessed on each individual project. Tailwater conditions increase the amount of driving head required for system operation reducing the treatment flow rate prior to bypass if not considered during the design stage. Tailwater conditions need only be considered if they occur frequently enough to affect the long-term performance of the separator (i.e. daily (tidal) or weekly). Hydroworks relies on the engineer of record to provide tailwater information during the design process to determine whether any modifications to the design of the separator are required. Modifications would include changing the weir heights to counteract the reduction in driving head created by the tailwater elevation. Modifications to the weir heights for tailwater conditions must be considered in the context of allowable headloss in the drainage system.

Allowable Headloss

Headloss for the HydroStorm separator is a function of flow velocity in the piping system and the geometry of the internal separator components. The sensitivity of a drainage system to headloss and upstream flooding is site-specific based on downstream tailwater elevations, and the design of the drainage system itself. The introduction of any structure to a drainage system will increase the headloss and hydraulic gradeline. Hydroworks can provide calculations to determine the headloss through the HydroStorm separator based on the hydraulic tests performed at Alden Labs. The engineer of record can determine if the calculated headloss is acceptable for the drainage system in question.

Depth to Seasonal High-Water Table

High groundwater conditions will not affect the operation of the Hydroworks HS. Although the drainage system is intended to be a sealed system and the water table is typically reduced to the level of drainage pipes since water infiltrates the storm network and/or flows through pipe bedding. However, some agencies require buoyancy calculations based on an empty vessel with the water table at the surface. The base of the concrete structure is made with an extension in these cases to satisfy this condition.

6. Maintenance

Routine inspection and maintenance of the Hydroworks HS ensures optimal performance. Stormwater regulations require that all BMPs be inspected and maintained to ensure they are operating as designed to allow for effective pollutant removal and provide protection to receiving water bodies. The frequency of inspection and maintenance depends on numerous factors including land use, average daily traffic, nearby construction activities, on-site material storage, site spill potential, winter sanding activities, and how the separator was sized with respect to annual TSS removal, size of TSS and required sediment storage.

Typically, drainage structures are installed during the early stages of construction. Even if they are not installed to provide sediment and erosion control they will provide this function if installed prior to stabilization of the site. Therefore, it is recommended that the separator be cleaned at the end of the construction period. The Hydroworks HS should be inspected once during the first year of operation for stabilized sites and twice for hot spot installations. Hot spots include:

- High spill potential
- On-site material storage
- Nearby construction or unstabilized site conditions
- High average daily traffic (> 500 vehicles/day)

The inspection and maintenance period can be lengthened or shortened based on the results from the first, and subsequent inspections.

Procedures for inspection, as well as a checklist, are provided in the HydroStorm O&M Manual at: www.hydroworks.com/hydrostormo&m.pdf. Hydroworks recommends the use of a coring tube (Core Pro; Sludge Judge) to determine depths of oil and sediment in the unit. Sediment collected in the separator has a high-water content and can be fine. It is difficult to measure sediment depths in these circumstances with rods or measuring sticks. A coring tube provides the best way to measure sediment depth in a separator.

Depths are provided in the maintenance manual as well as the verification appendix for sediment depths prior to maintenance. Increasing the depth of the structure will also increase the depth for sediment accumulation prior to maintenance, and therefore, needs to be considered for any site-specific application.

The Hydroworks HydroStorm separator should be cleaned using a vacuum truck.

7. Statements

The following signed statements from the manufacturer (Hydroworks, LLC), independent testing laboratory (Alden Research Laboratory) and NJCAT are required to complete the NJCAT verification process.

In addition, it should be noted that this report has been subjected to public review (e.g. stormwater industry) and all comments and concerns have been satisfactorily addressed.



January 26, 2018

New Jersey Corporation for Advanced Technology
Stevens Institute of Technology
Castle Point on Hudson
Hoboken, NJ 07030

Attention: Mr. Richard Magee, Sc.D., P.E., BCEE

Subject: HydroStorm Verification Report

Dear Mr. Magee,

We certify that the Hydroworks HydroStorm hydrodynamic separator was tested in strict adherence to the New Jersey Department of Environmental Protection Laboratory Protocol to Assess The Suspended Solids Removal by a Hydrodynamic Sedimentation Manufactured Treatment Device (NJDEP HDS Protocol, January 2013).

We certify that all requirements and criteria were met or exceeded during testing of the HydroStorm hydrodynamic separator.

Please do not hesitate to contact us if you have any questions regarding this letter.

Sincerely,

HYDROWORKS LLC,

A handwritten signature in blue ink that reads "Graham Bryant".

Graham Bryant, M.Sc., P.Eng.
President

Hydroworks, LLC
136 Central Ave.
Clark NJ 07066



February 12, 2018

Dr. Richard Magee, P.E., BCEE
Executive Director
New Jersey Corporation for Advanced Technology
Center for Environmental Systems
Stevens Institute of Technology
One Castle Point
Hoboken, NJ 07030

Conflict of Interest Statement

Alden Research Laboratory (ALDEN) is a non-biased independent testing entity which receives compensation for testing services rendered. ALDEN does not have any vested interest in the products it tests or their affiliated companies. There is no financial, personal or professional conflict of interest between ALDEN and Hydroworks, LLC.

Protocol Compliance Statement

Alden performed design research testing, as well as verification testing on the Hydroworks HydroStorm 4 (HS 4) separator. All data collected on the selected final design was submitted, including two test runs (50% and 100% MTR) where the background concentration exceeded the allowable concentration, as discussed in the report. The Technical Report and all required supporting documentation has been submitted as required by the protocol.

Testing performed by ALDEN on the Hydroworks HydroStorm HS 4 unit met or exceeded the requirements as stated in the "New Jersey Department of Environmental Protection Laboratory Protocol to Assess Total Suspended Solids Removal by a Hydrodynamic Sedimentation Manufactured Treatment Device", (January 25, 2013), with the following exception:

The reported 25% MTR test flow was higher than the +10% allowance as per the protocol. However, the higher test flow also results in a higher treatment velocity, which is conservative for removal of sediment particles.

James T. Mailloux

A handwritten signature in blue ink that reads 'James T. Mailloux'.

Senior Engineer
Alden Research Laboratory
jmailloux@aldenlab.com

(508) 829-6000 x6446



**Center for Environmental Systems
Stevens Institute of Technology
One Castle Point
Hoboken, NJ 07030-0000**

January 25, 2018

Jim Murphy, Chief
NJDEP
Bureau of Non-Point Pollution Control
Division of Water Quality
Mail Code 401-02B, PO Box 420
Trenton, NJ 08625-0420

Dear Mr. Murphy,

Based on my review, evaluation and assessment of the testing conducted on the Hydroworks HydroStorm (Model HS 4) hydrodynamic separator at the Alden Research Laboratory, Inc. (Alden), Holden, Massachusetts, under the direct supervision of Alden's senior stormwater engineer, James Mailloux, the test protocol requirements contained in the "*New Jersey Laboratory Testing Protocol to Assess Total Suspended Solids Removal by a Hydrodynamic Sedimentation Manufactured Treatment Device (January 25, 2013)*" (NJDEP HDS Protocol) were met or exceeded. Specifically

Test Sediment Feed

The mean PSD of the test sediments comply with the PSD criteria established by the NJDEP HDS protocol. The removal efficiency test sediment PSD analysis was plotted against the NJDEP removal efficiency test PSD specification. The test sediment was shown to be slightly finer than the sediment blend specified by the protocol ($<75\mu$); the test sediment d_{50} was 67 microns. The scour test sediment PSD analysis was plotted against the NJDEP scour test PSD specification and shown to meet the protocol specifications.

Removal Efficiency Testing

In accordance with the NJDEP HDS Protocol, removal efficiency testing was executed on the HydroStorm (HS 4), a 4-ft. diameter commercially available unit, to establish the ability of the HydroStorm to remove the specified test sediment at 25%, 50%, 75%, 100% and 125% of the

target MTFR. The HS 4 demonstrated 50.1% annualized weighted solids removal as defined in the NJDEP HDS Protocol. The flow rates, feed rates and influent concentration all met the NJDEP HDS test protocol's coefficient of variance requirements and the background concentration for all five test runs never exceeded 20 mg/L (maximum of 8.9 mg/L).

Scour Testing

To demonstrate the ability of the HydroStorm to be used as an online treatment device, scour testing was conducted at 228% of the MTFR which exceeds the 200% MTFR required by the NJDEP HDS Protocol. The scour test was conducted with the 50% capacity (6") false floor installed. An additional 4" of the 50-1000-micron test sediment was preloaded on top of the false floor, resulting in the unit being preloaded to the 83% storage capacity of 10".

The average flow rate during the online scour test was 2.01 cfs (903 gpm), which represents 228% of the MTFR (MTFR = 0.88 cfs). Background concentrations were <3.1 mg/L throughout the scour testing, which complies with the 20 mg/L maximum background concentration specified by the test protocol. Unadjusted effluent concentrations ranged from 10.9 mg/L to 30.3 mg/L, with an average concentration of 16.8 mg/L. When adjusted for background concentrations, the average effluent concentration was 14.6 mg/L. These results confirm that the HS 4 did not scour at 200% MTFR and meets the criteria for online use.

Maintenance Frequency

The predicted maintenance frequency for all HydroStorm models is 50 months.

Sincerely,



Richard S. Magee, Sc.D., P.E., BCEE

8. References

ASME (1971), *“Fluid Meters Their Theory and Application- Sixth Edition”*.

ASTM (2007), *“Standard Test Method for Particle Size Analysis of Soils”*, Annual Book of ASTM Standards, D422-63, Vol. 04.08.

ASTM (2007), *“Standard Test Methods for Determination of Water (Moisture) Content of Soil by Direct Heating”*, Annual Book of ASTM Standards, D4959-07, Vol. 04.08.

ASTM (2013), *“Standard Test Methods for Determining Sediment Concentration in Water Samples”*, Annual Book of ASTM Standards, D3977-97, Vol. 11.02.

NJDEP 2013a. *New Jersey Department of Environmental Protection Laboratory Protocol to Assess Total Suspended Solids Removal by a Hydrodynamic Sedimentation Manufactured Treatment Device*. Trenton, NJ. January 25, 2013.

NJDEP 2013b. *New Jersey Department of Environmental Protection Procedure for Obtaining Verification of a Stormwater Manufactured Treatment Device from New Jersey Corporation for Advanced Technology*. Trenton, NJ. January 25, 2013.

VERIFICATION APPENDIX

Introduction

- Manufacturer – Hydroworks, LLC. National Headquarters 136 Central Ave, 2nd FL, Clark, NJ 07066. www.hydroworks.com (888)-290-7900
- Hydroworks HydroStorm verified models are shown in **Table A-1** and **Table A-2**.
- TSS Removal Rate – 50%
- Online installation

Detailed Specification

- NJDEP sizing tables and physical dimensions of the Hydroworks HydroStorm verified models are attached (**Table A-1** and **Table A-2**).
- New Jersey requires that the peak flow rate of the NJWQ Design Storm event of 1.25 inch in 2 hours shall be used to determine the appropriate size for the MTD. The HS 4 model has a maximum treatment flow rate (MTFR) of 0.88 cfs (395 gpm), which corresponds to a surface loading rate of 31.4 gpm/ft² of sedimentation area.
- Maximum recommended sediment depth prior to cleanout is 6 inches for all model sizes based on the depths provided in **Table A-2**. Hydroworks can increase the overall depth of any model to increase the sediment storage depth for any site-specific storage/maintenance criteria.
- Operations and Maintenance Guide is at: www.hydroworks.com/hydrostormo&m.pdf
- The maintenance frequency for all the HydroStorm models is 4.2 years (50 months).
- Under N.J.A.C. 7:8-5.5, NJDEP stormwater design requirements do not allow a hydrodynamic separator such as the HydroStorm to be used in series with another hydrodynamic separator to achieve an enhanced TSS removal rate.

Table A-1 MTFRs and Sediment Removal Intervals for HydroStorm Models

Model	Diameter (ft)	Maximum Treatment Flow Rate¹ (cfs)	Treatment Area (ft²)	Hydraulic Loading Rate (gpm/ft²)	50% Maximum Sediment Storage³ (ft³)	Sediment Removal Interval² (years)
HS 3	3	0.50	7.1	31.4	3.6	4.2
HS 4	4	0.88	12.6	31.4	6.3	4.2
HS 5	5	1.37	19.6	31.4	9.8	4.2
HS 6	6	1.98	28.3	31.4	14.2	4.2
HS 7	7	2.69	38.5	31.4	19.3	4.2
HS 8	8	3.52	50.3	31.4	25.2	4.2
HS 9	9	4.45	63.6	31.4	31.8	4.2
HS 10	10	5.49	78.5	31.4	39.3	4.2
HS 11	11	6.65	95.0	31.4	47.5	4.2
HS 12	12	7.91	113.0	31.4	56.5	4.2

1. Based on a verified loading rate of 31.4 gpm/ft² for test sediment with a mean particle size of 67 µm and an annualized weighted TSS removal of at least 50% using the methodology in the current NJDEP HDS protocol.
2. Sediment Removal Interval (years) = (50% HDS MTD Max Sediment Storage Volume) / (3.366 * MTFR * TSS Removal Efficiency) calculated using equation in Appendix B, Part B of the NJDEP HDS Protocol.
3. 50% Sediment Storage Capacity is equal to manhole area x 6 inches of sediment depth. Each HydroStorm separator has a 12-inch-deep sediment sump.

Table A-2 Standard Dimensions for HydroStorm Models

Model	Diameter (ft)	Maximum Treatment Flow Rate (cfs)	Total Chamber Depth (ft)	Treatment Chamber Depth¹ (ft)	Aspect Ratio² (Depth/Diameter)	Sediment Sump Depth (ft)
HS 3	3	0.50	3	2.5	0.83	0.5
HS 4	4	0.88	4	3.5	0.88	0.5
HS 5	5	1.37	4	3.5	0.70	0.5
HS 6	6	1.98	4	3.5	0.58	0.5
HS 7	7	2.69	6	5.5	0.79	0.5
HS 8	8	3.52	7	6.5	0.81	0.5
HS 9	9	4.45	7.5	7	0.78	0.5
HS 10	10	5.49	8	7.5	0.75	0.5
HS 11	11	6.65	9	8.5	0.77	0.5
HS 12	12	7.91	9.5	9	0.75	0.5

1. Treatment chamber depth is defined as the total chamber depth minus ½ the sediment storage depth.
 The aspect ratio is the unit’s treatment chamber depth/diameter. The aspect ratio for the tested unit (HS 4) is 0.875. Larger models (>250% MTFR of the unit tested, >2.2 cfs) must be geometrically proportionate to the test unit. A variance of 15% is allowable (0.74 to 1.00).


2. For units <250% MTFR (5 and 6 ft models), the depth must be equal or greater than the depth of the unit treated.

FIGURES



PUTNAM COUNTY

WESTCHESTER COUNTY



Z:\E\19195100 NY Fuel Dist\Stormwater\Figures\Figure 1 - Location Map.dwg, 10/10/2019 1:49:22 PM, swashuk, 11

PROJECT: **NY FUEL DISTRIBUTORS**
3700 BARGER STREET, TOWN OF YORKTOWN, WESTCHESTER COUNTY

DRAWING: **LOCATION MAP**

PREPARED BY:



INSITE
ENGINEERING, SURVEYING &
LANDSCAPE ARCHITECTURE, P.C.
3 Garrett Place • Carmel, New York 10512
Phone (845) 225-9690 • Fax (845) 225-9717
www.insite-eng.com

DATE:	10-10-19
SCALE:	1" = 1000'
PROJECT NO.:	19195.100
FIGURE:	1



LEGEND


- SUBCATCHMENT
- TIME OF CONCENTRATION SHEET FLOW
- TIME OF CONCENTRATION SHALLOW CONCENTRATED FLOW
- TIME OF CONCENTRATION CHANNEL FLOW
- DESIGN POINT

* ARROW HEAD DENOTES CHANGE IN TIME OF CONCENTRATION PATH FLOW TYPE.

- GENERAL NOTES:**
1. Property survey data, topography and existing features based upon field survey prepared by Galois Surveying Group L.S. no. 50124.
 2. The gas, electric and communication utilities shall be installed in accordance with the utility provider specifications including but not limited to provided the proper bedding, cover, and detectible warning tape / tracer wire. The utility service provided shall ultimately select the utility location.

MAP 16.07
BLOCK 1
LOT 42
N/F REPUTED OWNER
ROC-SHRUB OAK ASSOCIATE
LIBER 7432, PG. 551

MAP 16.07
BLOCK 1
LOT 44
N/F REPUTED OWNER
TRANSITIONAL PROPERTIES, LLC
LIBER 12243, PG. 238




NO.	DATE	REVISION	REVISOR	TMB
1	9-3-20	REVISED PER PLANNING BOARD COMMENTS		TMB








		3 Garrett Place Carmel, NY 10512 (845) 225-9690 (845) 225-9717 fax www.insite-eng.com					
PROJECT: NY FUEL DISTRIBUTORS							
3700 BARGER STREET, TOWN OF YORKTOWN, WESTCHESTER COUNTY							
DRAWING: PRE-DEVELOPMENT DRAINAGE MAP							
PROJECT NUMBER	19195.100	PROJECT MANAGER	R.D.W.	FIGURE:	2	SHEET	2
DATE	10-10-19	DRAWN BY	S.V.W.				3
SCALE	1" = 10'	CHECKED BY	R.D.W.				

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.

Z:\E\19195\100 NY Fuel Dev\19195\100 NY Fuel Dev.dwg, 20/10/2019 11:54:41 PM, 1:11



LEGEND

-  SUBCATCHMENT
-  STORMWATER MANAGEMENT PRACTICE
-  TIME OF CONCENTRATION SHEET FLOW
-  TIME OF CONCENTRATION SHALLOW CONCENTRATED FLOW
-  TIME OF CONCENTRATION PIPE FLOW
-  TIME OF CONCENTRATION CHANNEL FLOW
-  DESIGN POINT

GENERAL NOTES:

- Property survey data, topography and existing features based upon field survey prepared by Gallos Surveying Group, L.S. no. 50124.
- The gas, electric and communication utilities shall be installed in accordance with the utility provider specifications including but not limited to provided the proper bedding, cover, and detectible warning tape / tracer wire. The utility service provided shall ultimately select the utility location.


NO.	DATE	REVISION	TMB	BY
1	9-3-20	REVISED PER PLANNING BOARD COMMENTS		

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.
 3 Garrett Place
 Carmel, NY 10512
 (845) 225-9690
 (845) 225-9717 fax
 www.insite-eng.com

PROJECT:
 NY FUEL DISTRIBUTORS
 3700 BARGER STREET, TOWN OF YORKTOWN, WESTCHESTER COUNTY

DRAWING:
 POST DEVELOPMENT DRAINAGE MAP

PROJECT NUMBER	19195.100	PROJECT MANAGER	R.D.W.	FIGURE:	
DATE	10-10-19	DRAWN BY	S.V.W.		3
SCALE	1" = 10'	CHECKED BY	R.D.W.		3



ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2209 OF ARTICLE 145 OF THE EDUCATION LAW.

Z:\19195\19195.DWG NY Fuel Distributors\Figures\Plan-Development\DWG\Map.dwg, 9/27/2020 6:48:27 PM, Herts, 11.10.20